

GOVERNMENT OF INDIA  
ARCHÆOLOGICAL SURVEY OF INDIA  
ARCHÆOLOGICAL  
LIBRARY

ACCESSION NO. 30591

CALL No. R 910.3095442G  
P.D.G./Fer

D.G.A. 79

३०५१

D9002





PANJAB DIST.  
GAZETTEERS.

OF THE

FEROZEPORE DISTRICT.


1888-89.

30591

D 9002



R 910.3095442G  
P.D.G./Ferr



Compiled and Published under the Authority  
of the  
PUNJAB GOVERNMENT.

CENTRAL ARCHAEOLOGICAL  
LIBRARY, NEW DELHI.

Acc. No. 30591 ...

Date. 11.3.57

Call No. 910.3095442 G

P.D.G. | Fex

## P R E F A C E.

---

The following preface was prefixed to the first edition of the *Gazetteer* of this district published in 1883-84:—

“ The period fixed by the Punjab Government for the compilation “ of the *Gazetteer* of the Province being limited to twelve months, the “ Editor has not been able to prepare any original matter for the pre- “ sent work; and his duties have been confined to throwing the already “ existing material into shape, supplementing it, as far as possible, by “ contributions obtained from district officers, passing the draft through “ the press, circulating it for revision, altering it in accordance with the “ corrections and suggestions of revising officers, and printing and “ issuing the final edition.

“ The material available in print for the *Gazetteer* of this district “ consisted of the Settlement Reports and a draft *Gazetteer* compiled “ between 1870 and 1874 by Mr. F. Cunningham, Barrister-at-Law. “ Notes on certain points have been supplied by district officers; while “ the report on the Census of 1881 has been utilized. Of the present “ volume, Section A. of Chap. V. (General Administration) and the “ whole of Chap. VI. (Towns) have been for the most part supplied by “ the Deputy Commissioner; Section A. of Chap. III. (Statistics of “ Population) has been taken from the Census Report; while here and “ there passages have been extracted from existing publications, or “ have been specially written for the *Gazetteer* by officers acquainted “ with the district. But much of the text has been taken almost, if “ not quite verbally, from Mr. Cunningham’s compilation already refer- “ ed to, which again was largely based upon Mr. Edward Brandroth’s “ Settlement Report of the district.

“ The report in question was written in 1855, and, modelled on the “ meagre lines of the older settlement reports, affords very inadequate “ material for an account of the district. No better or fuller material,

" however, was either available or procurable within the time allowed.  
 " But when the district again comes under Settlement, a second and  
 " more complete edition of this *Gazetteer* will be prepared; and mean-  
 " while the present edition will serve the useful purpose of collecting  
 " and publishing in a systematic form information which had before  
 " been scattered and in part unpublished.

" The draft edition of this *Gazetteer* has been revised by Colonel Grey,  
 " Mr. Wilkinson, Mr. Purser, and Mr. Fanahawa. The Deputy Com-  
 " missioner is responsible for the spelling of vernacular names, which  
 " has been fixed throughout by him in accordance with the prescribed  
 " system of transliteration. The final edition, though compiled by the  
 " Editor, has been passed through the press by Mr. Stack."

Since the publication of the first edition, the area of the district has been considerably enlarged in consequence of the partition of the Sirsa District which took place in November 1884. The whole of the tahsil of Fazilka (together with a few villages from the Dabwali Tahsil) was attached to this district.

The necessary additions to the text and statistics of the *Gazetteer* have been made accordingly, and the information and figures have been brought up to date.

For the history of the district and for its condition during the earlier years of British rule, the materials from which the first edition was compiled are still the best that are available, and it has been thought better not to make unnecessary alterations.

The census figures cannot yet be amended, as there has been no new enumeration since the date of the first edition; thus they do not include the Fazilka Tahsil.

THE EDITOR,

## CONTENTS

---

	PAGE.
<b>CHAP. I.—THE DISTRICT</b>	1
<b>II.—HISTORY</b>	12
<b>III.—THE PEOPLE</b>	36
A.—STATISTICAL	6.
B.—SOCIAL AND RELIGIOUS LIFE	41
C.—TRIBES, CASTES AND LEADING FAMILIES	50
D.—VILLAGE COMMUNITIES AND TENURES	71
<b>IV.—PRODUCTION AND DISTRIBUTION</b>	87
A.—AGRICULTURE AND LIVE-STOCK	ib.
B.—OCCUPATIONS, INDUSTRIES, COMMERCE AND COMMUNICATIONS	106
<b>V.—ADMINISTRATION AND FINANCE</b>	114
<b>VI.—TOWNS, MUNICIPALITIES AND CANTONMENTS</b>	132
<b>STATISTICAL TABLES (INDEX ON PAGE ii)</b>	143

---

### CHAPTER I.—THE DISTRICT

General description	1
Physical features—Changes in course of river Satlej	2
Miscellaneous	4
<i>ibid.</i>	ib.
The river Satlej	ib.
The Inundation Canals	5
Climate, temperature, rainfall	7
Geology—Vegetation—Wild animals : Sport	9

## CHAPTER II.—HISTORY.

	PAGE.
Early history	12
The Dogars	15
The Dogars—Sikh period	16
Sikh period—First introduction of British rule	19
First introduction of British rule—History of the <i>dekkas</i> subsequently added to the district—Khai Mallanwala, Baghwala, Makho	21
History of the <i>dekkas</i> subsequently added to the district—Zira—Dominion of Raja Jan	22
History of the <i>dekkas</i> subsequently added to the district: Kot Iso Khan—Dharmkot—Fatahgarh—Sada Singhwala—Badhni	23
History of the <i>dekkas</i> subsequently added to the district: Badhni—Chular Chak—Chirak—Kot-Kapur, Mokatpur, Mari and Mudki	24
History of the <i>dekkas</i> subsequently added to the district: Sultan Khánwala—Rimcheho, Kot Bhai, Jhumba, and Mahráj—Gurn Har Sahai—Mamdot	25
History of the <i>dekkas</i> subsequently added to the district: Mamdot—Faridkot, and Faridkot	26
Gradual formation of the present district	28
Gradual formation of the present district—The Mutiny	30
The Mutiny—District officers since annexation	32
District officers since annexation—Development of the district	33
Development of the district	34

## CHAPTER III.—THE PEOPLE.

## Section A—Statistical—

Distribution of population—Migration and birth-place of population	36
Migration and birth-place of population—Increase and decrease of population	37
Increase and decrease of population	38
Births and deaths—Age, sex and civil condition	39
Age, sex and civil condition—Infirmities—European and Eurasian population	40

CHAPTER III.—THE PEOPLE—*concluded.*

PAGE

**Section B.—Social and Religious Life—**

Habitations—Dress	...	...	...	...	...	41
Dress—Food—Condition of women	...	...	...	...	...	43
Condition of women—Marriage customs—General statistics and distribution of Religions	...	...	...	...	...	44
General statistics and distribution of Religions—Religious gatherings	...	...	...	...	...	45
Religious gatherings—Ferozepore Mission—Language	...	...	...	...	...	46
Language—Education	...	...	...	...	...	47
Character and disposition of the people—Poverty or wealth of the people	...	...	...	...	...	48

**Section C.—Tribes, Castes, and Leading Families—**

Statistics and local distribution of tribes and castes	...	...	...	...	...	50
Jat and Rājpūt tribes—Agricultural tribes of the <i>bet</i>	...	...	...	...	...	51
Agricultural tribes of the <i>bet</i> : Gujars—Manj Rājpūts— Nāipals—Dogurs	...	...	...	...	...	52
Arāins—Jat tribes of the <i>rohi</i> —The Sidihs	...	...	...	...	...	58
Giles—Dhāriwāls—Khosās—Sandhās—Wattās—Bodlas and Chishtis—Mahitams—Criminal Tribes: Bauriās, Hārnīs & Sānsās	...	...	...	...	...	61
Criminal Tribes: Bauriās, Hārnīs and Sānsās—Mercantile castes	...	...	...	...	...	67
The leading families	...	...	...	...	...	69

**Section D.—Village Communities and Tenures—**

Village tenures—The <i>sawāndārī</i> tenure	...	...	...	...	...	71
Pattidārī and Bisiachārs tenures	...	...	...	...	...	73
Riparian customs regulating property	...	...	...	...	...	75
Riparian customs regulating property—Proprietary tenures— Tenures in the Mukatsar <i>chāks</i>	...	...	...	...	...	76
Tenures in the Mamdot <i>chāks</i>	...	...	...	...	...	78
Tenants and rent	...	...	...	...	...	79
Village officers	...	...	...	...	...	80
Village dues—Kamins: their dues and duties	...	...	...	...	...	82
Agricultural laborers—Petty village grants	...	...	...	...	...	83
Poverty or wealth of the proprietors	...	...	...	...	...	84

## CHAPTER IV.—PRODUCTION AND DISTRIBUTION.

	PAGE.
<b>Section A.—Agriculture and Live-stock—</b>	
General statistics of agriculture—The seasons: Rainfall	86
Irrigation—Inundation Canals	ib.
Soils—General system of agriculture—The two-years course— Superior cultivation—Manure—Ploughing	88
Other Agricultural operations and implements	94
Carts—Principal staples—Average yield: Production and consumption of food-grains	96
Arboriculture and forests	102
Cattle—Government breeding operations and horse and cattle fairs	ib.
<b>Section B.—Occupations, Industries, Commerce, and Communications—</b>	
Occupations of the people	106
Principal industries and manufactures	ib.
Course and nature of trade—Prices, wages, rent rates, interest	107
Prices, wages, rent-rates interest—Weights and measures: Land Measure—Weights—Measures of capacity	110
Communications—Rivers—Railways	111
Roads, rest-houses, and encamping grounds	112
Post offices—Telegraph stations	113

## CHAPTER V.—ADMINISTRATION AND FINANCE.

Executive and Judicial—Criminal, Police and Gaols	114
Criminal, Police and Gaols—Revenue, Taxation and Registration, Revenue, Taxation, and Registration—Education—The District School	115
The District School	116
Medical—Ferozepore Civil Hospital—Ecclesiastical—Head- quarters of other Departments	118
Head-quarters of other Departments—Cantonments, troops, &c. Cantonments, Troops, &c.—Statistics of Land Revenue—Settle- ment of Land Revenue	120
Settlement of Land Revenue: Summary and Regular assessments compared	122
	123
	124

## CHAPTER V.—ADMINISTRATION AND FINANCE—concluded

	PAGE.
Settlement of Land Revenue: Re-settlement of Mukatsar and Mundot ... ... ... ... ... ... ...	125
Fazilka assessment... ... ... ... ...	ib.
Revisions of Settlement 1884—88 ... ... ...	126
Cesses—Government lands, forests, &c.—Assignments of land revenue— ... ... ... ... ...	ib.
Minor assignments—Administration of Irrigation Canals ...	127
Sirhind Canal ... ... ... ...	128

---

## CHAPTER VI.—TOWNS, MUNICIPALITIES AND CANTONMENTS.

General statistics of towns—Ferozepore town: Description ...	132
Cantonments—History—Population and vital statistics ...	134
Population and vital statistics—Taxation, trade, &c.—Institu- tions and public buildings ... ... ...	135
Dharmkot town—Zira town ... ... ...	ib.
Zira town—Makhu town ... ... ...	137
Moga town—Mudki ... ... ...	138
Maharaj—Town of Mukatsar ... ... ...	139
Fazilka ... ... ...	140

Details of area taken from Statements Nos. V., VIII., & VI.O. of Agricultural Statistics; detail of rainfall from Meteorological Report of 1887-88; detail of population from the Census Report of 1881; and detail of Revenue from Table No. III of Administration Reports. Fazilka was added to this district in November 1884.

Table No. I, showing LEADING STATISTICS

(Punjab Gazetteer)

Details	District	Population	Area	Details of Taxab.			
				1	2	3	4
Total square miles (1887-88) .....	... ..	... ..	... ..	4,070.05	408.75	10,277	142,80
Chittenden square miles (1887-88) .....	... ..	... ..	... ..	700.2	67.1	46.1	1,260.7
Chittenden square miles (1887-88) .....	... ..	... ..	... ..	400	40.0	36.5	483.4
Chittenden square miles (1887-88) .....	... ..	... ..	... ..	400	40.0	36.5	483.4
Chittenden square miles (1887-88) .....	... ..	... ..	... ..	4,018.7	400.0	36.5	514.5
Imperial square miles (1887-88) .....	... ..	... ..	... ..	742.8	74.1	74.1	749.8
Average square miles under crops (1887-88 to 1887-88) .....	... ..	... ..	... ..	400	100.5	105.1	327.5
Average square miles under crops (1887-88 to 1887-88) .....	... ..	... ..	... ..	4,200.7	378.0	369.5	427.3
Annual rainfall in inches of past year .....	... ..	... ..	... ..	22.31	20.10	20.10	12.12
Number of inhabited towns and villages (1881) .....	... ..	... ..	... ..	1,023.4	32.2	40.7	32.2
Total population (1881) .....	... ..	... ..	... ..	76,117	125,103	104,316	111,214
Rural population (1881) .....	... ..	... ..	... ..	70,000	113,608	108,500	109,801
Urban population (1881) .....	... ..	... ..	... ..	6,117	10,501	9,811	9,413
Total population per square mile (1881) .....	... ..	... ..	... ..	22,406	23,570	21,457	21,320
Total population per square mile (1881) .....	... ..	... ..	... ..	1,574.8	2,280.0	2,171.4	2,164.4
Total population per square mile (1881) .....	... ..	... ..	... ..	1,011.1	1,417	1,367	1,351.1
Hijlias (1881) .....	... ..	... ..	... ..	...	...	30,810	31,760
Ghias (1881) .....	... ..	... ..	... ..	...	...	10,025	12,917
Jain (1881) .....	... ..	... ..	... ..	...	...	26,101	21,916
Muslims (1881) .....	... ..	... ..	... ..	...	...	107,463	61,986
Average annual land revenue (from 1882-83 to 1887-88) .....	... ..	... ..	... ..	100.00	87,101	143,701	101,241
Average annual grain revenue from 1882-83 to 1887-88 .....	... ..	... ..	... ..	80.00	...	...	80.00

## CHAPTER I.

---

### THE DISTRICT.

The Ferozepore District is the southernmost of the five districts of the Jullundur Division, and lies between north latitude  $29^{\circ} 56'$  and  $31^{\circ} 11'$  and between east longitude  $73^{\circ} 55'$  and  $75^{\circ} 37'$ . It is bounded on the north-east by the river Sutlej, which separates it from the Jullundur District, and by the Kapurthala State, the boundary of which does not quite agree with the present position of the river; on the north-west and west by the united stream of the Sutlej and Beas, which divides it from the districts of Lahore and Montgomery; on the east and south-east by the Luddiana District and the Native States of Faridkot, Patiala, Nabha, and Jind; and on the south and south-west by the Hissar District and by the territories of Bilanpur and Bahawalpur. Were it not for the interposition of the Faridkot State in its midst, the district would form a fairly regular block occupying the left bank of the Sutlej for about 110 miles of its course and extending back from the river to a distance of between 30 and 40 miles. It is divided into five talukas, of which Mukataar and Fazilka lie below the Faridkot State, and Zim, Ferozepore, and Moga lie above it. Moga is entirely away from the river: Zim occupies the angle opposite the Beas confluence, followed by Ferozepore, which extends down to the point where the district is narrowest; while Mukataar and Fazilka have limited river frontages, but great depth towards the interior. There is an outlying group of thirty-seven villages, known as the Mahrājā Hāka, a little to the south of the main body of the Moga Taluk, and in the centre of the same taluk is a smaller group of Chāirkā and five other villages belonging to the Kalsia State. The riverside country from about 6 miles below Ferozepore to the southern limit of the Mukataar Taluk forms the jagir of the Nawāb of Māmīt, whose predecessors up to 1836 were ruling Chiefs. The Fazilka Taluk was added to this district on the reduction of the Sirsa District in November 1884.

Chapter I.  
Descriptive.  
General description.

Some leading statistics regarding the district are given in Table 1 in the frontispiece. The district contains only one town of more than 10,000 souls, namely, Ferozepore itself, which with the cantonment had in 1881 a population of 39,570. The administrative head-quarters are situated at Ferozepore,  $4\frac{1}{2}$  miles from the right bank of the Sutlej and about the middle of the western border of the district.

**Chapter I.****Description.****General description.**

TOWN.	NORTH LATITUDE.	EAST LONGITUDE.	EXTENT IN SQUARE MILES.
Ferozepore	30° 12'	74° 47'	440
Zira	30° 12'	74° 47'	320
Moga	30° 12'	74° 47'	120
Mukatsar	30° 12'	74° 47'	220
Fazilka	30° 12'	74° 47'	300

cent. of the total population, and 3·2 per cent. of the urban population of British territory. The latitude, longitude, and height in feet above the sea of the principal places of the district are shown in the margin.

**Physical features.**

The surface of the district slopes very gently from the north-east towards the south-west at the rate of about 1½ feet in the mile. It is all of an alluvial formation and contains no hills, and indeed not a rock or stone. On closer acquaintance it is found to be divided into three broad plateaux raised slightly one above the other, the edges of which, in the form of two broken and shelving banks, run nearly parallel to the course of the river. The highest of these three tracts contains nearly all the Moga Tahsil, a few villages in the south of Zira, the extreme south-east corner of Ferozepore, and about half of the Mukatsar and Fazilka Tahsils. It might be conveniently distinguished as the Kot-Kapura plateau, the pargana so named (now in Faridkot territory) being near its centre and forming a link between the Moga and Mukatsar portions. Its surface is extremely smooth. The soil is a rather sandy loam of a reddish-brown colour, broken only by the lines of old water-courses along which sand-drifts are always to be found. On the extreme south-east, however, sand-ridges become common, and in places form the main feature of the landscape. The upper or greater bank which bounds this tract has an elevation of about 15 or 20 feet. It is most distinctly marked about Dagru on the Ludhiana road, 28 miles from Ferozepore, and in the Mukatsar Tahsil. Below it is a tract of much more sandy soil having a width of 10 miles in the centre, but tapering off almost to nothing at both its upper and its lower ends. The Sutlej appears to have run under the foot of the upper bank up to a period about 350 or 400 years ago. In those days it did not meet the Beas River until some point between Bahawalpur and Hoshiar. This sandy plain has been overrun by the river in the subsequent interval. This plain comprises the southern half of the Zira Tahsil (excepting a few villages above-mentioned), the eastern half of the Ferozepore Tahsil, and all the north-west of Mukatsar and Fazilka, except a strip along the present course of the river. It might be called the Mandki plain, from the name of the well-known town and battlefield, which is situated midway in its length. A leading characteristic of this tract is the brackishness of the wells, which increases towards the south-west until the water is undrinkable. Below the Mandki plain is the riverside tract, sometimes called the Bet. Between Zira and the confluence of the Sutlej and

Bes the Bet has a width of 12 miles; elsewhere it is not generally more than about 8 miles wide. Its soil is a dark-grey clay intermixed with strata of sand. The lower or lesser bank which bounds the Bet is only 4 or 5 feet in height. Sometimes it is indistinct, so that the characteristic soils of the two tracts—the red sand of the uplands and the dark clay of the lowlands—are found for a short distance intermingled.

In Moga the upper plateau is locally known as the *Rohi*, which really means firm land, the term being applied to this sort of tract as contrasted with the sands of Rājputānā. The Mudki plateau has sometimes been called the lower *Rohi*. In Mukatsar the Kot-Kapāra plain is called the Utār or uplands, in contradistinction to the Mudki plain, which is there called the Hīthār or lowlands. But in Mamdot and elsewhere also the term *Hīthār* (which is only relative) is applied to the tract within the reach of the annual floods of the river, while the Utār in that part of the district is the tract immediately above the Hīthār, the name *Bet* not being in use in Mamdot. The "Rohi" in Mamdot is the western edge of the lower *Rohi* or sandy plain. In Mukatsar the same term was applied by the Settlement Officer in 1872 to the extreme south of the Kot-Kapāra plain, where it becomes uneven and sandy. Thus in the Mukatsar Tahsil there are two quite distinct tracts called *Rohi*, two equally distinct which are both called *Utār*, and again two tracts in no way resembling one another which are called *Hīthār*. The central region of the Bet in Mamdot and Ferozepore between the Utār and the lower *Rohi* is often called the *Dhors*, which means an elevated or dry tract.

The river ran under part of the lower bank about 150 years ago. Having probably shifted in that position suddenly from its former course, it met the channel of the Beas somewhere in the west of the Zira Tahsil. It then seems to have made a sudden turn to the north, reaching Shabikot in the Jullundur District. After this some of the water of the Sutlej returned temporarily to its former bed under the lower bank and flooded a large tract of country, eventually making its escape into the Beas near Ferozepore, and in its retreat cutting out two or three curiously regular channels, now called *Sukkas* or dry channels, which with other nullahs, the result of more recent changes, form the whole tract between the lower bank and the present stream. Mr. Brandreth in 1851 described the *Sukkas* as follows:—

Changes in course  
of river Sutlej.

"There is a curious channel, called the *Sukha Nai*, or 'dry channel,' between the new and old beds of the river, which has its origin near Tilla, in the Ludhiana District, whence it runs with a very serpentine course along the whole length of the district to our Mamdot. Notwithstanding its winding course, the banks of the channel are so regularly formed as to have induced many to think it entirely artificial. More probably, however, it was originally a natural water-course, afterwards shaped into a canal. Its breadth is 100 foot, and its depth seven or eight feet. As recently as forty years ago it is stated that some little water flowed into it, but since then it has remained quite dry. In former days its banks are said to have been fringed with beautiful sheesham trees, of which now no trace remains. Could the water be again brought

## Chapter I.

### Descriptive.

#### Physical features.

**Chapter I.****Descriptive.**

*Changes in course  
of river Sutlej.*

into the channel a very great benefit would result to the country through which it passes; it is to be feared, however, from the result of recent surveys, that such benefits are unattainable save at great expense, as the bed is so changed as to be unsuitable for the feeding of inundation canals."

With reference to these remarks, it may be noticed that lengths of this and other similar channels have been incorporated in the inundation canals made by Colonel Grey.

**Miscellaneous.**

In the southern part of Mandot there is a narrow belt of firm soil within the limits of the lower Roli tract which is called the *tarota*. This is discernible in places higher up the valley.

The Bet country is full of irrigation wells, each surrounded by a clump of trees. The depth to the water level in this tract is generally not more than about 18 feet; in the Mudki plain it is from 30 to 40 feet. In the Moga and Mukatsar country it commences at about 45 feet, but rapidly sinks to 70 or 80 feet, so that well irrigation is possible only on the north-east margin of this tract. In the Mahrâj villages water is reached at a depth of 150 feet, and in the further southern parts of Mukatsar and Fazilka at not less than 180 feet; and the cost of sinking a well to this depth is so considerable that wells, even for drinking-water, are not found in every village. Kankar is found in many villages in the Mudki plain, but is not plentiful.

**Soil.**

Along the top of the upper bank large mounds of earth and brick or pottery rubbish, called *tholu*, are often found, which mark the sites of former villages, and show that the bank of the river was inhabited in ancient times. No such remains are found in the tracts below the greater bank; any that existed must have been swept away by the river, which has crossed over all the lower country during the last two centuries. The most important of these mounds is that of Janer, 6 miles north of Moga.

The soil of each of the three levels is practically of the same quality throughout its length, and its capabilities depend mainly upon the supply of rain, which varies directly with the distance from the Himalaya from 25 inches on the north-east border to less than 10 inches in the extreme south-west. The soil of the uplands has a great power of retaining moisture, especially where the surface is more sandy than the subsoil, and it will produce fair crops even in very dry years. The stiff soil of the riverside tract, on the contrary, though fertile enough if saturated at proper intervals, requires both heavier and more frequent rain, and, except in the Zira Tahsil, it cannot be cultivated successfully without some form of irrigation. The cultivators of the Bet are nearly all Muslims, and those of the upper Roli are nearly all Sikh Jats. In the Mudki plain Sikhs Jats are the majority, but there are many villages of Bahomedans.

The Sutlej has a fall of about 13 inches in the mile, the winter level of the water being about 720 feet above sea-level at the Ladhiana border, and about 560 feet at the Bahawalpur border, which is about 115 miles lower down. The windings of the stream probably increase its length in the low season by one-third,

**The river Sutlej.**

and reduce the slope proportionately. The volume of water in the Sutlej has sensibly diminished since the opening of the Sirhind Canal at Rupar, and in the cold season it is now easily fordable almost anywhere above the Beas confluence. The water of this river is more turbid than the Beas, which from its clearness has obtained the local name of *Nili*, meaning blue. This name is also given to the combined stream below the junction. The width of the combined stream is generally about 1,000 yards when the water is low, but increases to two or three miles during floods; and the depth and velocity also are, of course, much increased at the same time. Mr. Brandreth, the former Settlement Officer, remarks:—

"The changes in the bed of the river are very frequent. Whole villages are constantly washed away in the course of a single season, while new lands are formed elsewhere with the same rapidity. The people are very superstitious on the subject of these inroads of the river, and have several imaginary methods of arresting its course. The practice they consider most efficacious is to throw a number of goats into the stream. . . . Pakirs and other sacred persons are also sometimes engaged to offer up prayers for the same purpose."

These practices have not yet disappeared. Since Mr. Brandreth's time the river has generally tended to shift somewhat over to the west. It has cut to the distance of about a mile into the Lahore District, and has left many islands and strips of lowlands deposited on the Ferozepore side. The bed of the river is a soft sand mixed with mud in layers. A surface of dry sand may overlay a bottom of wet mud, often forming very treacherous ground. It is not safe for a horseman to attempt to cross any of the channels, wet or dry, except along a track formed by the feet of cattle. The river is navigable only by very shallow, flat-bottomed punts, called *Chappu*. The larger docked boats of the western rivers, called *Beri* or *Zora*, only rarely come up as far as Ferozepore. The *Chappu* is only fit for short trips, but will carry 60 or 80 persons, or a proportionate number of horses or conveyances, and perhaps 100 maunds of goods.

The principal kinds of fish found in the Sutlej are the *maher*, *rohu*, and *sotal*. The following other kinds were observed by Mr. H. O'Brien, Deputy Commissioner: *shurana*, *dhingra*, *dambara*, *jhaila*, *muli*, *kohri*, *mohri*, and *ghogn*, the last being identified by him as *labeo bimaculatus*. Fish are caught in a drag-net, by which they are forced into a shallow.

The river is now crossed by a railway bridge made in 1880. It is 4,000 feet long, consisting of 27 girders founded upon groups of wells, and has a cart-road above the railway. A list of ferries is given in Chapter V, Section A.

A great change was effected in the Bet tract of this district by the inundation canals constructed by Colonel L. J. H. Grey when Deputy Commissioner of the district in 1874—77. Colonel (then Captain Grey) noticed, as soon as he joined the district in the beginning of 1874, the large areas of land in the Bet tract which was in want of irrigation, and with the opportunities presented by the lie of the country for the construction of inundation

### Chapter I.

#### Descriptive.

The river Sutlej.

Inundation Canals.

**Chapter I.****Descriptive.****Inundation Canals.**

canals upon the model of those in Bahawalpur and Multan, where he had been serving. Attempts had been before made by the people, with the aid, from time to time, of the district officials, to encourage the river water at the time of its annual rising to flow into some of the old irrigation channels, by means of which it is often possible to carry a stream two or three miles inland. Sometimes a cutting was made through a bar obstructing the mouth of such a channel, and sometimes a dam was thrown across the channel to force the water on to the fields. But for want of intelligent and systematic direction such works had never been permanently useful: after one or two seasons they usually silted up. Colonel Grey determined to lay out a few canals once upon a scientific plan, and with the assistance of Mr. Barnes, Superintendent of Irrigation in the Bahawalpur State, he succeeded in constructing seven small cuts of a total length of 52 miles in that very year. The excavation work was done entirely by the agriculturists, who were to get the benefit of the water, and the duty of supervision was performed by the Deputy Commissioner and his ordinary subordinates.

Colonel Grey then applied to Government for the grant of loans for more extensive operations, and in the meantime obtained money from the district funds and other sources. The Nawâb of Mandot undertook the cost of those canals which lie within his jagir. By the flood season of 1874-75 ten canals were ready, with a total length of 260½ miles. A full description of the works will be found in a report prepared in August 1875 by Mr. H. C. Fawcett, then Assistant Commissioner in this district. The system of construction and management are detailed in Colonel Grey's District Canal Manual, 1885. It is sufficient here to say the work is entirely co-operative. Government has never given any direct help, except in the form of a contribution to the cost of establishment on account of canals in Pâsikha. The labour required is furnished by those villages which take the water, in tasks proportioned to the area which each has irrigated in the preceding season. The task of each village (called *vak*) consists of a certain length of the canal in which the excavation (or in subsequent years the clearance of silt) has to be completed down to a fixed bench-mark. Those who do not perform the work personally are required to get it done by contractors. In 1880 a special establishment was appointed for the management of the canals, consisting of an Extra Assistant Commissioner\* as Superintendent, an Assistant Superintendent, *Darwaza*, or Overseer, on each canal, and various minor employees, the whole costing Rs. 9,400 per annum. This sum is raised by means of a rate amounting usually to 2½ annas per acre of land irrigated.

Further information regarding the canals will be found in Financial Commissioner's Selections, No. XLI, published in 1867. The statement on pages 8 and 9 shows statistics for the canals for the years 1883-84 to 1887-88.

\* At present Râi Maya Das, who was active in this work in former years, and whose name was given to one of the canals, the Mayawali.

The rainfall is very uncertain, the rainy season sometimes beginning in the end of June, and sometimes being delayed until the end of July, and the period of its termination is equally uncertain. Late rains are the most beneficial, as a favourable sowing season for the spring crop is of more importance than the success of the autumn crop. For a good spring harvest more rain is necessary in the cold season, about January. The rains become more uncertain and partial as well as more scanty as the distance from the hills increases. In the Fazilka uplands there was hardly any rain from 1886 to 1889. Ferozepore is proverbial for dust-storms, whence the proverb, *Kabul ki sard, Ferozpur ka garda* ("Kabul for sards melons, and Ferozepore for dust").

Chapter I.  
Descriptive.  
Climate, tempera-  
ture, and rainfall.

The uplands are very scantily wooded. An enormous area of natural scrub-jungle was removed to clear the land for cultivation in the first fifteen or twenty years after annexation, and the uplands were left almost bare of trees. In the Modki plain the clearance of the jungle has led to a great increase of sand-drifts. The bushes and grass which held the loose soil together having been removed and the soil having been stirred up by the plough, the wind has now great power over it, and it drifts into sand-ridges which grow neither corn nor grass. In recent years, however, the irrigation canals in the Bet and the Sirhind Canal in the Rohri are encouraging the growth of trees and will effect a decided improvement in the climate. The cold weather commences about the middle of October and ends about the middle of March, but the mornings and evenings remain cool until the middle of May. The latter part of May, all June, and sometimes all July, are extremely hot, and there are only temporary falls of temperature until September.

No systematic thermometrical record has ever been maintained in the district. Private observations, however, show that in December and January the temperature ranges in houses between 40° and 70°, whilst during June and July (with closed doors) its range in houses not artificially cooled is from 95° to 97°.

Table No. III. shows, in inches of an inch, the total rainfall registered at each of the雨 gauge stations in the district for each year, from 1883-84 to 1888-89. The fall at headquarters for four years is shown in the margin. The distribution of the rainfall throughout the year is shown in Tables Nos. IIIA. and IIIB.

Owning to the dryness of its climate, Ferozepore has acquired the name of being exceptionally healthy, and this reputation is still deserved as regards the city and environs, and also as regards all the upland plains. But in the irrigated lands of the Bet, and also in the towns of the Zira Tahsil standing on the lower bank between the Bet and the sandy country, fever is terribly prevalent in the months of September, October, and November. In Zira current business is often stopped, neither suitors being able to attend the offices, nor the officials able to hear them.

Disease.

Year.	Inches of an inch.
1883-84	177
1884-85	177
1885-86	199
1886-87	49

## Chapter I.

Descriptive.  
Cost and results.

## Statement showing cost and results of Ferozepore Inundation

Name of Canal	Length in miles through which it flows	Banks in miles	Cost of external works					Cost	
			INRAS.						
			1884-85.	1885-86.	1886-87.	1887-88.	1888-89.		
1. Abohar	22	45	—	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	
2. Baghelkot	32	45	—	821 7 8	279 2 2	300 2 2	—	4,272 19 2	
3. Bichkerwali	20	30	—	—	1,024 19 3	—	1,160 6 2	2,185 1 4	
4. Barnawali	23	40	—	1,231 8 0	1,128 4 22	—	128 4 0	4,330 11 0	
5. Mayowal	69	30	—	11,092 2 0	900 10 4	429 2 0	216 1 0	13,051 14 0	
6. Dihawali	22	77	—	1,023 2 0	529 6 0	—	—	600 8 0	
7. Jallianwala	32	40	—	22 3 0	1,512 18 0	—	3,008 10 0	4,800 11 0	
8. Kishanwali	27	40	—	4,000 6 0	3,742 12 0	—	382 12 0	4,387 8 0	
9. Khushwali	34	30	—	64 2 0	107 0 0	—	—	607 0 1	
10. Qutubwali	22	30	—	899 4 0	1,223 8 0	—	227 2 0	1,627 7 7	
11. Panjwali	48	40	—	8,818 2 0	21,342 13 0	—	—	306 4 0	
12. Daggarwali, now Mukhar- wali.	60	30	—	27,400 2 0	200 0 0	—	—	254 0 0	
13. Phulwali	22	30	11,322 15 7	6,308 7 2	—	—	—	1,287 0 0	
Total	—	—	21,897 35	192,607 4	7,39,379 19	6,073 7	6,123 11 6	4,072 1 4	

\* A branch of Panjwali, named Bhaghatwali.

† This year the Daggarwali was widened and

‡ During these two years the banks were

**Perozspore District.]**

CHAP. I.—THE DISTRICT.

9

Canals for 5 years from 1883-84 to 1897-98.

**Chapter I.**  
**Descriptive.**  
Cost and results.

10	11	12	13	14	15	16	17	18	19
<b>REMARKS, ESTIMATED REQUIREMENT.</b>									
<b>DATA ESTIMATED.</b>									
1884-85	1885-86	1886-87	1887-88	1888-89	1889-90	1890-91	1891-92	1892-93	1893-94
Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.	Rs. a. p.
1,220 0 0	4,011 2 0	8,000 0 0	7,700 0 0	9,000	9,400	11,800	11,400	14,300	
2,700 12 0	9,000 10 0	10,000 10 0	6,200 10 0	6,000	6,000	6,000	6,000	6,000	10,000
7,700 7 0	2,000 4 0	2,000 4 0	10,000 10 0	10,000	7,100	11,000	10,500	10,500	
2,700 11 0	6,100 4 0	6,100 10 0	4,000 10 0	4,000	6,100	11,000	9,000	10,000	
2,100 11 0	6,074 1 0	6,000 10 0	2,000 10 0	2,000	6,000	11,000	11,000	11,000	
200 1 0	400 4 0	8,000 10 0	2,000 10 0	2,000	2,000	1,000	1,000	1,000	
2,070 10 0	3,200 1 0	6,000 10 0	7,000 1 0	6,000	11,400	10,000	11,400	10,000	
6,100 10 0	5,200 10 0	6,000 10 0	5,000 10 0	5,000	11,700	10,000	11,000	10,000	
2,600 0 0	1,000 0 0	2,000 10 0	6,000 10 0	6,000	2,000	1,000	1,000	1,000	
1,000 12 0	900 1 0	2,000 11 0	6,000 10 0	6,000	6,000	2,000	2,000	2,000	
900 11 0	2,000 4 0	2,000 10 0	6,000 10 0	6,000	4,000	6,000	6,000	6,000	
1,000 10 0	8,000 2 0	2,000 10 0	6,000 9 0	6,000	10,000	6,000	7,000	10,000	
3,000 0 0	6,000 10 0	8,000 4 0	6,000 10 0	6,000	11,200	10,000	10,000	10,000	
42,300 4 0	40,000 0 0	11,600,110 3 11	71,377 0 0	69,328	130,000	121,000	121,000	121,000	176,000

was constructed during the year.  
lengthened and made into the Malleswaram,  
especially repaired.

**Chapter I.**  
**Descriptive.**  
**Disease.**

The fever is probably caused by the cold of the evenings and nights, which after the heat of the day is injurious to insufficiently-clothed persons. In the colder months it is followed by pleuro-pneumonia, small-pox, &c.

Small-pox used formerly to be a scourge, but since the more general spread of vaccination its ravages have been greatly reduced. Guinea-worm is not uncommon in the south of the district, and is traceable to the water. The natives themselves look upon it erroneously as hereditary, and attribute it to the curse of Bâla Farid upon all who crossed the Sutlej into Hindustan. Tables Nos. XI, XII, XIII and XLIV give annual and monthly statistics of births and deaths for the district and for its towns during the last five years; while the birth and death rates since 1868, so far as available, will be found at pages 38 and 39 for the general population and in Chapter VI under the heads of the several large towns of the district. Table No. XII shows the number of insane, blind, deaf-mutes, and lepers, as ascertained at the census of 1881; while Table No. XXXVIII shows the working of the Dispensaries since 1877.

**Geology.**

The whole district is, as already remarked, entirely alluvial. The upper plateau is probably the result of washings from the Himalaya, the sandy plateau of the effects of later and more rapid denudations of the Siwaliks rather than of the inner hills, and the latest river clay a detritus from all tracts through which the Beas and Sutlej have passed in their course.

**Vegetation.**

The original jungle of the uplands of Moga and Mukatpur consisted mostly of the *raan* (locally called *mali*) (*Salsola glomerata*), a gnarled and shapeless tree with stiff foliage, somewhat resembling the leaves of the mistletoe, which produces the berry called *pili*, the *khard* or leafless copper (*Cupressus spicata*), the *kilar* (*Acacia urticaria*), and to the south-west the *jord* (*Pithecellobium spinosum*). These species are still the common trees of those tracts. The *shisham* or *tali* (*Dalbergia sissoo*) and *sira* or *siria* (*Tectonia*, or *Aibertia speciosa*) are only found in the Bet or near it, and even the *forish* or *pharmi* (*Tamarix articulata*) is not very common above the upper bank. The *beri* (*Ziziphus jujuba*) is widely distributed, also the *desar* variety (*Z. nummularia*) which is considered a sign of good land. Other trees are the *deo* (*Adansonia digitata*), the *reec* (*Ecklonia laevigata*), and the *phalo* (*Tecton maderaspatana*). The *pipal* (*Ficus religiosa*) is mostly confined to the banks of ponds close to which the village homesteads are generally placed. The *dhae* or *chuchra* or *push* (*Butea frondosa*) is found in stiff soils in the eastern half of Moga. Parish cuttings were planted in great numbers along the inundation canals in 1876-79 and are now fully grown. An attempt at agriculture was made at the regular settlement in 1853, by causing each village in the drier tracts to set apart a small plot of land for the growth of trees, but these small plantations never having been tended have mostly disappeared. The villagers are now beginning to feel the want of wood for building and making implements, and in the Moga Tahsil many of

them are voluntarily starting small groves each in his own land. In the tracts where wells are used, trees are always planted around the well and for a short distance along the paths and water-courses, and form a small grove. Large numbers of trees have been planted by Government on the banks of the Sirhind Canal. The District Board maintains avenues along the principal roads in its care.

In the southern parts of the district the profuse and lofty growth of the *ak* (Hindustani, *madr*) (*Calotropis procera*) attracts attention. It attains a height of ten feet and forms stems of a foot in girth. The ground is often densely covered with the grey *bari* bush, and in Faziles with the *bira* or *salsola* of two species. In the river-side country many square miles are covered with the lofty *sare* grass (*Saccharum sare*), locally known as *jhall*. It usually thrives best on sandy soil unfit for cultivation. Wet land still nearer the river generally produces a dense thicket of *pithai* (Hindustani, *sho*; *Tomarix dioica*). The *sare* is used in making stools, and many other small articles, and its fibre is twisted into cordage. Baskets are made of the *pithai*. The following smaller grasses are common: *kusa* (*Saccharum spontaneum*) on the river-side, *dab* (*Eragrostis caryophyllea*), *dab* or *khabbai* (*Cynodon dactylon*), and *palmaria* (*Ambrepogon gonoides*); on the river-side, and *dhaman* (*Pennisetum compressum*), *chilimbar* (*Eleusine flagellifera*), *karmbar* (*Eleusine arghyptiaca*), *seu*, *leha*, *khurri*, and *gurham* in the upland tracts.

The only animals of prey commonly found in this district are wolves. Jackals and foxes are found, but are few in number. Snakes are occasionally found, the commonest being a species of *kerdit*. Rewards (Rs. 5) are given for the destruction of wolves, and these animals are being rapidly diminished in numbers as cultivation is extended. The rewards paid for wolves' heads amounted in 1865 to Rs. 535, in 1870 to Rs. 251, in 1875 to Rs. 224, in 1880 to Rs. 112, and in 1882 to Rs. 73. Wolves are now rare, but foxes (the small kind) plentiful. There are a few *nilgai*; also pig in jungles near the river. Bustard are rare. There are some florican about Nathana, and the chink is plentiful, as are black and grey curlews and the ox-eye plover. The Indian gazelle (*chital*) and antelopes are found in tolerable abundance, chiefly in the Moga and Mukatsar Talails, but are very much shot down. Hares, black and grey partridges, and sand-grouse are also abundant, and, in the cold season, *kulan* (*Dromocallis crassirostris*), wild geese, and wild duck are found on and near the river. Some of the kinds found are teal, mallard, spotted-billed duck, marlins-backed teal, red-headed pochard, and gadwall. No game laws are enforced, but the intense summer heat gives the game a natural close season.

Chapter L  
Descriptive.  
Vegetation.

Wild animals.  
Sport.

## CHAPTER II.

---

### HISTORY.

#### Chapter II.

##### History.

##### Early history.

Hardly any district in the Punjab has so little early history attached to it as Faridkot. It is almost entirely destitute of ancient buildings and contains no places mentioned in early records. Legends connected with Rāja Salivāhan attach to one or two other ruined sites, such as that at Sarai Nāngā a few miles to the east of Mukatsur. But none of the present villages or towns date from an earlier period than the reign of Akbar. This is mainly due to the fact mentioned in Chapter I, that the entire western side of the district has within the last four centuries been overrun by the river Sutlej, by which all relics of antiquity that may have existed have of course been effaced.

The Kot-Kapura plateau must in former days have formed the northern margin of the great Rājputāna Desert. Its situation and the proximity of the river, which then ran near the present towns of Mukatsur and Faridkot, rendering it more habitable than the regions further off to the south, now the Bikanī territory, it was gradually invaded by immigrants from the Jaisalmer and Bikanī country. The earliest known rulers in this district appear to have been the Punwār Rājpūts, one of whose capitals may have been Janer, the antiquities of which are described by General Cunningham in his *Archaeological Survey Reports* (XIV, 67-69). About the time of the first Muhammadan conquests of India a colony of Bhati Rājpūts, of whose stock the great tribes of Manj Rājpūts, Naipāls, and Dogars are branches, came up from Jaisalmer under a leader called Rai Hel, and settled to the south of the present town of Mukatsur. They overcame the local Punwār Chief and firmly established themselves. The pedigree of Rai Hel's descendants will be found in Chapter III, Section C.

Fifth in descent from Rai Hel were two brothers, Dhumbi and Chinn. The Dogars and Naipāls are descended from Dhumbi. This branch of the tribe turned to the left and lived for a time beyond the Beas about Pākpatian and Dipalpur. The grandson of Chinn was Rāja Manj. Mokalsi, the son of Manj, built Faridkot, then called Mokalsi. Mokalsi's sons divided into two families, called after the names of two of them, the Jairsis and Vairsis. Both became Muhammadans about the same

time, about 1285 A. D. The Punwars silently disappear from the history, and the Manj families advanced northwards to the river. In the beginning of the sixteenth century they built several towns or villages, which are still in existence, between Zira and Dharmkot, on what was then the river bank. Kot Ise Khan was built by Nawab Ise Khan of this branch about 1700 A. D.

Meanwhile the Vairais fixed their capital after two or three changes at Racket, now in the Ludhiana District, and ruled the east of the Jarrowa. These families acted as local Governors under the Moghal Sultans of Sirhind.

The immigration of the great Jat tribes who now people most of the district commenced about two hundred years after the time of Kai Kail. The Dhaliwals, to whose clan the Qilaipur Raja belongs, and who say they came from Dharanagri, somewhere in the south of India, appear to have been long established at Kangar, now in Pathiala territory to the south-east of Moga, and to have attained some distinction, as shown by a daughter of one of them being married to the Emperor Akbar.

The Gild, another tribe of Jats from Tharindu, spread over the west of the Moga Tricity not long after the Dhaliwals. In the end of the sixteenth century the Sidhes, who are of the same Bimbi stock as the Manj tribes, came up from Rajputana. One branch, the Sidha Barars, rapidly gained a footing in the south of the Gild country and drove its former inhabitants northwards, taking possession of their principal places. The Barars founded a chieftainship at Kot-Kapura, and after a time rebelled against Nawab Ise Khan, the Manj Governor. The Empire was by that time failing to pieces, and they were not long in gaining their independence. The Raja of Panikot is of this branch. Another branch, the descendants of Mohab, settled at Mahoraj. From among them arose the Panikian Rajas of Patiala, Nabha, and Jind. Most of the Jat tribes were converted to the Sikh religion by the seventh Guru, Har Rai, about 1626 A. D. The tenth Guru, Govind Singh, on his flight from Chamkaur in 1705 A.D., sought refuge at Kot-Kapura, but the Chief of that place, though a Sikh, refused to shelter an enemy of the Imperial Government, and the Guru fled on to Muktsar, where his followers were cut to pieces. He himself escaped to the Deccan. Not long after this event Nawab Ise Khan in 1715 rebelled against the authority of Delhi, but was defeated and killed. His territory was restored to his family, but from this time they had little power. The ascendancy of the Sikhs dates from about 1760, when they defeated Adina Beg, the Moghal Governor of Lahore. Three years later they sacked Kasur and enriched themselves with enormous booty. Many of the refugees from Kasur came over to Ferozepore and established the present town. At the same time Tara Singh Ghoba, of the Dalochwala Confederacy, a freebooter, who had become one of the Sikh Chiefs, began to make incursions into the north of this district from the opposite side of the Sutlej. He got possession of Fatehgarh, and his further progress will

**Chapter II.****History.****Early history.**

be related in the account of that *ilaka*. Tāra Singh's conquest extended as far as Rāmnwāla and Mari in the Moga Tahsil, at both of which places he built forts. Meanwhile Sardār Jassa Singh Ahluwalia took possession of the Naipal country, and extended his authority to within a few miles of Ferozepore. The Nawāb of Kot Ise Khan placed himself under the protection of the Ahluwalias.

In the *Ayin Akbari*, Ferozepore is mentioned as the centre of a large *pargana* attached to the Sāū of Mooltan, and paying a revenue of 11,479.401 *dinars*, equivalent to Rs. 2,36,985. Another *pargana* mentioned in the same work, that of Muhommadot, is probably to be identified with the modern Mamdot, and would therefore fall within the boundary of the present district. The revenue of this *pargana*, as given in the *Ayin Akbari*, amounted to 3,492.454 *dinars*, equivalent to Rs. 87,311. —

The fort of Ferozepore is stated to have been built in the time of Feroz Shah, Emperor of Delhi, from A.D. 1351 to 1387. Nothing more than a mound, surmounted by a Muhammadan tomb, marks its site. The following pages are taken from the report of Sir H. Lawrence, who was stationed at Ferozepore during the early years of the British occupation:—

Both town and territory of Ferozepore bear every appearance of having been not only long located, but of having been at one time rich and populous. It is true that the fort of Ferozepore is not mentioned in the *Ayin Akbari*, whereas that of Mamdot is mentioned. The *Ayin Akbari*, however, cannot (as is pointed out by Captain Lawrence) be considered a complete statistical return; while the position, extent, and importance of the *pargana*, as above described, give strong grounds for belief that in such times, and commanding then, as now, one of the chief passages over the Sutlej, and being on the high road between Lahore and Delhi, Ferozepore possessed at least a fortress of some kind; and the name and character of Feroz Shah\* afford fair grounds for supposing him to have been the founder. But the fact does not rest on any local tradition. The Manj Bājpūts say the town was named from their Chief Feroz Khan, who lived in the middle of the sixteenth century. The principal traders were Bhābrias. The place was desolated by a pestilence in 1543 A.D., and the traders withdrew to Kot Ise Khan. The fact that Ferozepore was not attached to the Sāū of Sirhind, but to that of Mooltan, goes to support the inference that it was at the time of Akbar on the right bank of the Sutlej. From its position, Ferozepore may have been a mart for the produce of the hills and the rich country between them and Amritsar; but being in the track of many of the hordes that ravaged the North-West Provinces, the town and territory seem to have suffered even more than the rest of the country bordering on the Sutlej.

\* The foundation of several towns, and among them of Hissar, in the country between the Jumna and Sutlej, is attributed to Feroz Shah.

During the decay of the Delhi Empire, the country, which had apparently become almost depopulated, was occupied by the Dogars, a clan of Rajput origin, who are still prominent among the occupants of the district. The Dogars were a wild and lawless race, owing no permanent habitations, and delighting rather in large herds of cattle than in the more laborious occupations of the soil. Originally they were alternately graziers and cattle-stealers, but at all times bad cultivators, and holding but loosely the bonds of allegiance. They paid tribute to the rulers set over them according to the means brought to enforce the claim, and when hard pressed they had little to lose by deserting their dwellings. On such occasions the Dogars would place their few chattels, their women and children, on bullockes, and flying into the tamarisk forests of what is now the Bahawalpur territory, or into the almost equally inaccessible desert of Abolar in Sirsa, there defy their pursuers, or take their time for coming to terms. These people, who are Muhammadans and call themselves converted descendants of the Chauhanas of Delhi, emigrated some years ago to the neighbourhood of Pakpatan; and from thence, two centuries ago, spread for a hundred miles along both banks of the river Sutlej from a few miles above Ferozepore to the borders of Bahawalpur. At one time they were undoubted masters of Mumdot and Khan, as well as of Ferozepore; their seats were principally in the Khidder of the Sutlej, and their occupations pastoral and predatory. But a colony of several thousands settled many years ago in the large inland town of Sunam, and both about Lahore and Dera Ismail Khan they are to be found. The Jan is subdivided into many branches; but almost all the Ferozepore Dogars trace their origin to Bidiot, a Muhammadan Dogar, who must have lived two hundred years ago.

It was gradually that the Dogars moved from about the neighbourhood of Pakpatan; and not until about 1740 A. D., that they reached Ferozepore, which appears at that time to have formed part of a district called the Lakhis jungle, and to have been administered by a *faujdar*, enjoying civil and military authority, residing at Kasur, and acting under the Governor of Lahore. A few villages occupied by Bhattis were at this time scattered over the Ferozepore plain; but on the coming of the Dogars the former moved southward, and Dogars soon established themselves in their room. The right of occupancy of the new possessors was allowed by the Lahore rular, who, however, on their failing to give security for the payment of Government dues, took their children as hostages. Their rebellious spirit, however, soon broke out, and they slew the *faujdar*, Ahmed Khan Lal; but in the weak state of the vice-regal Government they escaped punishment, and for a time remained independent of all authority.

Sukha Mallo, the head of a tribe as wild as that of the Dogars, and himself a cattle-stealer by profession, was then appointed *faujdar*; and such was the terror of his name, that many

**Chapter II.****History.****The Dogars.**

**Chapter II.****History.****The Dogars.**

of the Dogars absconded; but he enticed them back, and for six years managed the country, after which time the Dogars assembled in rebellion near the Tshia of Pir Balawal; and the *faujdar*, incitiously going among them unarmed and unattended, was speared by one Phaima, who had long vowed his death. The followers of Sukha, who were at hand, hearing of the fate of their leader, fled and were followed by Dogars, who plundered the *faujdar's* dwelling, and murdered his son Kuth. Jil Khan was now appointed *faujdar*. Being pressed by the Lahore Government for arrears of revenue, he took refuge among the Dogars, and was protected by them. But although the *faujdar* thus formed an intimacy with this troublesome portion of his dependents, he had no sooner arranged his affairs with his superior at Lahore, and returned to Kasdr, than the Dogars commenced the same systematic opposition to his rule that they had carried on against the administration of his predecessor.

Sheikh Shamir of Ulaki (then called Chanki), was a violent man, and stirred up his brethren, the Dogars, against Jil Khan. The latter, after some opposition, seized twenty-two of their leaders; but in a short time, after levying a heavy fine on them, he released all except three, Massa, Muhammad and Albar. Pir Khan, the head of the village of Dulchi, where the *faujdar* had been received during his temporary disgrace, went several times to Jil Khan and begged that he would release the prisoners. On his refusal to do so, Pir Khan concerted with Sheikh Shamir to seize or slay the *faujdar*. He again went to Kasdr, and enticed their victim to an interview with the rebels on the banks of the Sutlej, promising to use influence to effect improved arrangements, and to bring to submission the contumacious Dogars. In the midst of the interview Sheikh Shamir slew the *faujdar*, and in the scuffle that ensued was himself killed by a chance blow from his own brother, Miri. Yusuf Khan, the Naib of Jil Khan, avenged the murder of his master, put the hostages to death by sawing their bodies across and hacking them to pieces. The manuscripts do not show who succeeded Jil Khan as *faujdar*; and considering the then disturbed state of the Empire, it is probable the Dogars were left for a time to themselves; for they seem, on failure of a common enemy, to have turned their arms against each other. One party calling in a band of Pathans, the other of Moghals, to aid them, these auxiliaries formed posts in different villages, received a share of the *Hakimi* dues, and were neglected or respected according to their strength and character. One of the allies so called was Mahomed Khan, son of late *Faujdar* Jil Khan.

**Bik period.**

In 1763-64 A.D., Hari Singh, Chief of the Bhangi *Misl*, seized and plundered Kasdr and its neighbourhood. Among the Sardars in his train was Gurja (Gujar) Singh (whose son Sahib Singh afterwards married the sister of Baba Singh, the father of Ranjit Singh), who, taking his brother Nudisha Singh and his two nephews, Gurbakhsh Singh and Mustan Singh, crossed the Sutlej opposite Kasdr, and took possession of Ferozepore, the fort

of which was in ruins ; while Jai Singh Gheria, with another band from the same quarters, seized Khai, Wan, and Basidpur, in the neighbourhood of Ferozepore, and made them over to their subordinate, as Gurja Singh did Ferozepore to his nephew, Gurbakhsh Singh, son of Nusbahu Singh. The Ferozepore territory then contained 37 villages, the proceeds of which Sardar Gurbakhsh enjoyed in concert with Burhan Dogar and Muhammad Khan, son of Gul Khan ; but the two latter soon leagued and expelled Gurbakhsh Singh's garrison from the newly-repaired fort of Ferozepore. The latter then established himself in Suluk Khaniwala, where was a mud fort, and from thence still managed to get the third portion of the Government share of the Ferozepore villages, Burhan Dogar and Sumān Dogar, dividing between them a third, and Muhammad Khan receiving the remainder. In the year 1771 Muhammad Khan started for Amritsar with some horses for sale. On his first encamping-ground Gurbakhsh Singh attacked and took him prisoner, and then recovered the fort of Ferozepore. Between the years 1763 and 1771, Gurbakhsh Singh acquired a considerable territory on the right bank of the Sutlej ; but in 1771, the same year that he recovered Ferozepore, a change in the course of the Sutlej left the Salkar Nui dry, and carried away or rendered waste all the Ferozepore villages but seven. On regaining Ferozepore, Gurbakhsh Singh rebuilt the fort, and leaving his uncle, Raja Singh, as Governor, recrossed the Sutlej, and employed himself in increasing and securing his possession in the Panjab and in co-operating with his kinsmen and patron, Gurja Singh, in a dispute with whom, however, for a partition of their acquisitions, Mustan Singh, the brother of Gurbakhsh Singh, was soon after killed.

Gurbakhsh Singh, who was a native of Asil, near Khemkarn, where his father was originally a zamindar, had four sons and three daughters. The sons soon became troublesome to their father; Jai Singh, the youngest, even commenced operations on his own account, and when forbIDDEN to do so arrayed himself against his father. Most probably induced by such conduct, Gurbakhsh Singh resolved to divide his estates during his lifetime. The authorities differ as to dates, but it was about A. D. 1792 that the old Sardar divided his possessions among his sons, reserving Singhpura for himself. To his eldest son, Dhanna Singh, he gave Satiāgarh, Bhediān, and Mithalim, north of the Sutlej ; to the second, Dhanna Singh, the fort and territory of Ferozepore ; to the third, Gurmukhi Singh, Sehjara, north of the Sutlej ; and to Jai Singh, Naggar. Sardar Dhanna Singh resided in the fort of Ferozepore, and Gurbakhsh Singh and his other sons on their respective allotments beyond the Sutlej. But all seem to have kept up friendly communication with each other ; and Dhanna Singh especially appears to have been much at Ferozepore, and, as well as his father, to have afterwards found a refuge there when dispossessed of their respective territories by Nihal Singh Atariwala.

**Chapter II.**

History,  
Sixth period.

## Chapter II.

History.  
Sikh period.

Sardar Dhanna Singh appears to have been unable to match his grasping neighbours, or to restrain his unruly subjects, the Dogars, who almost immediately on his accession invited the inroads of Nizam-ud-din Khan, the Pathan Chief of Kasur, who accordingly sent troops to Dulchi. Dhanna Singh, being unable to resist them, entered into a compromise, and yielded to the Pathan a half share of the Dogar villages that had been spared by the last irruption of the Sutlej. The arrangement by no means pleased the Dogars, who immediately called in the Rai of Nakot to their assistance. The Rai's force lay for some weeks, if not months, under the walls of the fort, and in 1807 Sir H. Lawrence picked out one iron six-pound shot and several wooden plugs that appear to have been driven into the southern wall with a view of effecting a breach. But for those days the fort was strong and was relieved in time by Sardar Rai Singh, of Baria, the father-in-law of Sardar Dhanna Singh. He also expelled the Kasur Pathans from their portion of the seven villages; but on Rai Singh's retirement Nizam-ud-din returned and regained his footing. In A. D. 1807 Maharaja Ranjit Singh having acquired Kasur made it over in jagir to his favourite and coadjutor, Sardar Nihal Singh Atarwala, who soon dispossessed Gubakhsh Singh and his three sons of their Tams-Sutlej possessions in the neighbourhood of Kasur. The Dogars, who were looking for a change, invited Nihal Singh's approach to Ferozepore. He gladly acquiesced, and, crossing the river, dislodged Dhanna Singh's garrison from the village and fort of Dulchi.

About the same time another branch of the Dogar clan, the Ullakis, settled at Bareki. Having applied for aid against their Chief to Mora, a celebrated courtesan at the Court of Lahore, she asked the Maharaja for a grant of Ferozepore, and without a shadow of right in the matter he granted her request. Backed by the power of Ranjit Singh, Mora sent troops to enforce her claim, and seized the village of Bareki. Dhanna Singh being thus pressed, was offered assistance by his enemy Nihal Singh, and in his extremity accepted it. Uniting their troops they expelled Mora's garrison from Bareki; but had no sooner done so than Nihal Singh made an attempt on the fort of Ferozepore, which, however, resisted him.

In A. D. 1808 Sardar Nihal Singh again crossed the Sutlej in the train of Ranjit Singh, who, notwithstanding the remonstrances of Mr. Metcalfe, the British Agent, insisted on endeavouring to extend his dominions to the east of the Sutlej, and by stratagem he effected the lodgment of a garrison in the fort of Khai, a stronghold for the time, six miles south-west of Ferozepore, and then belonging to Nizam-ud-din Khan. Occupying thus Dulchi on the north, Bareki on the west, and Khai on the south-west, he hemmed in the Ferozeporians and shared the produce of their lands equally with Sardar Dhanna Singh, who, from the weakness of his character, was quite unable to cope with such a stirring leader. Dhanna Singh was, therefore, delighted to hear at this time that the British Government had

taken on itself the protection of all the country south of the Sutlej,\* on which point he was no sooner informed than he addressed Sir D. Ochterlony, the Agent for Sikh affairs, and, in a letter dated 28th March 1809 begged to be admitted under the Company's protection in the same manner as was his relative Bhagwan Singh, of Buria and Jagadhri. A favourable answer was returned, and, by order of Government, a copy of the Proclamation of seven Articles was sent to him, showing that the British Government guaranteed the status of 1808 as it obtained previously to Maharaja Ranjit Singh's irruption. In the year 1811 the Lahore Government deputed an agent to wait on Sir D. Ochterlony, one of the objects of the mission being to obtain sanction for seizing Dhanna Singh's land south of the Sutlej. Sir D. Ochterlony, however, disclaimed the right, stating that Ferozepore had neither been originally given to Ranjit Singh, nor had been conquered by him; and that whatever portion of his territory Dhanna Singh still retained on the adoption of Mr. Metcalfe's treaty, to that he was fully entitled by the British guarantee. Government coincided with Sir D. Ochterlony, and from that time until the late Sardar's death no claim on the territory was made by the Lahore ruler.

In A.D. 1818-19 Sardar Dhanna Singh died, leaving his widow Lachman Kunwar, the daughter of Rāī Singh, of Buria and Jagadhri, heiress of his possessions. The Sardarni having placed her father-in-law, the old Sardar Gurbakhsh Singh, in charge of the territory, proceeded on a pilgrimage to the shrines of Hardwar, Gya, and Jagannath; but during her absence her husband's nephew, Bhagel Singh, the son of Dhanna Singh, gained admittance to the fort under pretence of visiting his grandfather, Gurbakhsh Singh, and, being supported in his usurpation by Sardar Nihal Singh, they two administered and shared the profits of the territory in concert. In 1823 Sardarni Lachman Kunwar returned from her pilgrimage, and appealed to the British authorities against the usurpation of Bhagel Singh. Captain Ross, the Deputy Superintendent of Sikh affairs, represented her case to the Lahore Agent, and the Maharaja immediately recalled his vassal, Bhagel Singh, and allowed that Ferozepore belonged rightfully to the Sardarni as the separated share of her husband given him during the life of Gurbakhsh Singh. The old Sardar died at a very advanced age in Ferozepore in the year 1823, and Bhagel Singh died in the Punjab in 1826. Sardarni Lachman Kunwar died in December 1835, and leaving no children the heritage of her territory fell to the British Government.

The importance of the position of Ferozepore had been pointed out to Government by Captains Ross and Murray; and during the Sardarni's life her often-expressed wish to exchange her turbulent territory for a more peaceful one in the neighbour-

## Chapter II.

### History.

See period.

\* See Gazetteer of Umballa.

**Chapter II.****History.**

*Firs introduction  
of British rule.*

hood of her kinsman of Buria had been explained to the British authorities as offering a good opportunity for taking up a commanding position opposite to, and within 40 miles of, Lahore. But an aversion to enlarge our boundary, or to alarm the Lahore Darbār, deterred the Government from accepting the Sardārī's offer, though it was at the same time notified to the local officers that *as no protest whatever was Banjīt Singh to be permitted to obtain possession of Ferozepore.*

Early in 1836 Lieutenant Mackeson was despatched by Captain Wade to Ferozepore and Lahore to ascertain the limits of the late Sardārī's territory and to adjust our new relations with the Mahrāja. Lieutenant Mackeson soon ascertained that the only undisputed portion of the property was the city and its suburbs with the town-lands, stretching scarcely a mile in any direction, the cultivators of which lived under the walls of the fort, and did not even enjoy their scanty lands without the cover of mud or brick towers, one or more of which protected every well, serving as watch-towers against invaders and as places of refuge against small predatory bands. The remains of many of these buildings still dotted the territory in Sir H. Lawrence's time, and bore good evidence to the former state of the country. Giving up the right of co-partnership in the remote villages, and retaining entire possession of those within a well-defined limit, Lieutenant Mackeson, in communication with the Lahore authorities, settled the boundary of the territory, leaving to it an undisputed area of 86 square miles, divided among 40 villages. So admirably was this delicate task executed that no complaint against that officer or any of his measures was heard of. The local duties were then placed under a confidential agent of Captain Wade, named Sher Ali Khan, who endeavoured to reclaim the people from their lawless habits, and made two or three new locations. Sher Ali Khan died in 1837, and was succeeded by Pir Ibrāhīm Khan, a man of good family and of considerable reputation in the country, as having been long the Prime Minister of the Khan of Mamdot. Under Pir Ibrāhīm some few other locations were made and old wells repaired. A commencement was also made of clearing away the ruins of the ancient town and laying out new and broader streets. Pir Ibrāhīm Khan was relieved by Mr. W. M. Edgeworth in December 1838, whom, owing to the increased importance of the place, it was resolved to make Ferozepore the station of an Assistant Political Agent. Mr. Edgeworth's whole time was occupied by the many duties entailed on him by the presence of the army of the Indus, until, in January 1839, he was relieved by Sir H. Lawrence.

Considerable progress had been already made in the pacification of the newly-acquired territory when the first Sikh war broke out (A.D. 1845). Of that war, the present district was the battle-field. The Sikhs crossed the Satlēj opposite Ferozepore on 16th December 1845. The battles of Mudki, Firuzshah,

Aliwai, and Sobroon\* followed, and the Sikhs again withdrew beyond the river, pursued by the British force, which soon afterwards dictated peace under the walls of Lahore. "Little remains," writes a former Settlement Officer of the district, "to remind the visitor of all the vivid details of these contests, or of the frightful carnage by which they were distinguished. A few gun-dints may still be picked up at Firozshah, and the bones of cattle may still be seen whitening the plain of Mudki, but there is no vestige of the entrenchment about Firozshah, which has long ago given place to the furrows of the plough; and the river flows over the ground on which stood the still stronger entrenchments of Sobroon."<sup>†</sup>

By the result of the war the British Government acquired Khai, Mudki and all the other Lahore territory on the east of the Sutlej. The Ahluwalia Chief was for his disaffection deprived of all dominions south of the river. Kot-Kapura was given to the Farukkot Chief partly as a reward for assistance rendered to the British army and partly in exchange for the pargana of Sultan-Khanwala, a piece of his territory which lay inconveniently across our line of communications.

A short account is here subjoined of each of the *halis*, History of the which were subsequently added in the manner described below <sup>halis, subsequently added to the districts</sup> (pages 28 and 29) to the Ferozepore territory, the history of which has just been narrated. It is taken with verbal adaptations from the Settlement Report of the district, written in 1865, by Mr. E. L. Brandreth.

Khai formed part of the Dogar territory. It was, no doubt, originally included in the old *pargana* of Ferozepore, but was entirely waste when the Dogars took possession of it. The origin of the name is not known. It was the designation of a *thek* or deserted site, near which one of the Dogar Chiefs located the present village of Khai. From this *thek* a sufficient number of bricks were subsequently dug up to make ten miles of road, from which circumstances some idea of the extent of these remains may be formed. When Gurja (Gujar) Singh acquired Ferozepore, Jai Singh, another Sikh Chief, took possession of Khai, but was compelled to give way to Nizam-ul-din, the Pathan Chief of Kairar, whose rise to power will be described in the account of Mumdot. In 1804 Ranjit Singh dispossessed Nizam-ul-din and gave the *halia* in *pargi* to his favourite, Sarilar Nihal Singh Atariwala. It was afterwards transferred to Sarilar Dharm Singh on condition of his furnishing a contingent of fifty horsemen. In 1843 it was incorporated in the Lahore demesne.

## Chapter II.

## History.

First introduction  
of British rule.

\* These battles took place on 18th and 21st December, 2nd January and 10th February, respectively.

† This was written in 1865. Monuments have since been erected on the battle-field in memory of those who fell.

**Chapter II.****History.**

*History of the ilâka subsequently added to the district.*

**Mallârwâla.**

*Ilâka* Mallârwâla was also part of the Dogar territory. The village of Mallârwâla Khas was located by a Dogar Chief named Malla. On the irruption of the Sikhs, about 1760, Jassa Singh Ahîuwâla took possession of it, together with the surrounding villages, which since that time have been known as a separate *ilâka*. The Ahîuwâla family retained possession of this *ilâka*, with the exception of a few villages which were taken from them by Ranjit Singh, until the Sutlej Campaign, when, in consequence of the hostile part taken by them, their estates were confiscated.

**Baghuvâla.**

The *ilâka* of Baghuvâla, with the exception of a few villages in the bed of the river, was originally included in Mallârwâla, but was occupied by Dessa Singh Majithia, who first seized upon the village of Baghuvâla, where he built a small fort. Assisted by Ranjit Singh he afterwards took possession of several of the adjoining villages subject to the Ahîuwâla Chief, and thus formed the present *ilâka*. Dessa Singh was succeeded by his son Lehna Singh, who kept possession of the *ilâka* till it was confiscated after the Sutlej Campaign of 1845-6.

**Mâkhu.**

The *ilâka* of Mâkhu was occupied about 100 years ago by the Naipals, a Mussulmân tribe, resembling the Dogars, who came originally from Sirsa. There is no trace of any former inhabitants, and it was probably an entire waste. The Naipals were originally subjects of the empire; then became virtually independent till Jassa Singh, the Ahîuwâla Chief, took possession, and establishing a *thâna* at Mâkhu created the *ilâka* now known by that name. His successors held it in *jagir* till the Sutlej Campaign, when it was confiscated.

**Zira.**

The neighbourhood of Zira, in which there are many deserted sites, had been for many years a waste, when in A. D. 1808 Saynd Ahmad Shah came from Gugera and founded Zira Khâ. He was driven out by the Sikh Chief, Mehr Singh, Nishânewâla, during whose rule nearly all the villages of this *ilâka* were located. Mehr Singh was in turn driven out by Diwân Mohkam Chand, Ranjit Singh's General, and the *ilâka* was added to the Lahore demesne. It was afterwards divided into two portions, of which the eastern portion, which preserved the name of Zira, was made over to Sarbuland Khan, a servant of the Lahore Government; and the western portion, to which the name of *ilâka* Ambarhar was given, was assigned as an appanage of Sher Singh, son of the Punjab sovereign. At a later date, Sher Singh obtained possession of the whole *ilâka* and abolished the subdivision of Ambarhar.

**Kot Ise Khan.**

The territory now included in the *ilâkas* of Kot Ise Khan, Dharmkot and Fatehgurh is said to have formerly belonged to Rajpûts of the Panwar tribe. Their ruler resided at Janer, which is said to have been founded by one Râja Jan. The present village of Janer stands at the foot of a mound, one of several, composed of bricks and earth, the remains of an ancient city, which cover an area of about 60 acres. This is by far the most extensive deserted site in the district, and from its height

is conspicuous above the surrounding country at a great distance. It is worthy of remark that the affix *er* or *mer* occurs in the name of almost no other village in the district. In the language of Rājpūrā it signifies a hill or mound, and occurs frequently; as, for instance, in Ajmor, Bilkner, Jaisalmēr, and Amber. The Punwārs were supplanted by the Manj Rājpōts, an account of whom is given in Chapter III., Section C.

Net Ahmad Khan, son of Shādi Khan, of that family, who proceeded to the Court of Akbar, there gained great favour by a test of strength, stringing a bow sent by the King of Persia, which had defeated the efforts of all others at the Court. The Emperor conferred on him the title of Nawāb, and in due time he succeeded to possession of the *teypa* of Shādiwāl, which had been conferred upon his father, the limits of which seem to have been the same with the present *khāta* of Kot Ise Khan. About 1740 one of his descendants, Nawāb Ise Khan, after whom the *khāta* has since been named, resisted the imperial authority; but was subdued by a force sent against him, and was killed after displaying prodigies of valour. Notwithstanding his rebellion, his son Mīrzā Khan was permitted to succeed him. His son Kādir Dakhsh Khan was despoiled by the Alikhawāla family, who took possession of the *khāta*.

Tara Singh Dhalewala invaded and subjected this *khāta* in A. D. 1760, and building a fort at Kothpur changed its name to Dharmkot. His son, Jhanda Singh, was compelled to yield to Diwān Mohkam Chand, and the *khāta* was added to the royal *dimarā*.

This tract was also included in the possessions of Tara Singh, who made over the greater portion of it to his cousin, Kaur Singh. It was added, under Diwān Mohkam Chand, to the Lahore *dimarā*.

In Akbar's time this *khāta* probably formed part of the *pargana* of Tibāra in the Sūba of Sirhind. The village of Dasiat-pura in this *khāta* was founded by Domat Khan Manj, grandfather of Nawāb Ise Khan, but most of its villages are, however, of recent location. On the invasion of the Sikhs it was partitioned out among four Chiefs—Sada Singh; Karm Singh, brother of Sada Singh; Dīal Singh, Garchara; and Nāhar Singh Anand-puri. The first two died without direct heirs, and the inheritance fell to a daughter of a third brother, Dīal Singh, who was married to Utam Singh, grandson of Nāhar Singh. Utam Singh thus acquired possession of nearly the whole of the *khāta*. His possessions were forfeited to the British Government in consequence of the defection of his family during the Sutlej War. The descendants of Dīal Singh are still *jagirdārs* of the villages of Salina and Nishānwāla.

The villages now comprising this *khāta* were formerly held by Rāi of Rāskot. They appear to have been part of *pargana* Tibāra. The zamindars are Dhāriwāl Jats. A daughter of one Mehr Mitha of this tribe, was married to the Emperor Akbar. On

## Chapter II.

### History.

History of the *khāta* subsequently added to the district.  
*Kot Ise Khan.*

*Dharmkot.*

*Paisburgh.*

*Sada Singhwāla.*

*Bahadur.*

**Chapter II.****History.**

*History of the Gurdwara subsequently widened in the district.*

**Baddi.**

her father he conferred the title of Mián, and gave him a jútir of 120 villages, of which Kangar was the centre. On the fall of the Empire, the Chiefs of Patiala and Nabha despoiled the Mián family of a great part of their possessions. The remainder, known as *Ikála Badli*, was seized by Ranjit Singh, and given by him to his mother-in-law, Sada Kaur, who was the daughter of a zamindar of Nukki in the same ikála. The descendants of Mehr Mitha, though they were never converted to Muhammadanism, still retain the title of Mián. A few acres of land are all that now remains to them of their former possessions. The fort of Badli was built by Mián Himmat Khan of this family.

**Chakar Chak.**

The villages of this *ikála* were also under the Rāj of Rājkot. Before the irruption of Sikhs the zaminiars had rendered themselves almost independent. They resisted Diwan Mehmān Chand, but were overcome, and their land added to the Lahore *deshmene*. It was then made over to Sodhi Jowābir Singh, whose descendants still hold several villages free of land revenue.

**Chhirak.**

This *ikála* contained originally only one village, Chhirak, which was located by a Jat, named Jhanda, near an old site of that name. He was a subject of the Rāj of Rājkot. The present proprietors of the land are the descendants of Jhanda, but the revenues of the *jigis* are entailed on the eldest son. During the troubled times that occurred on the dissolution of the Empire, the successors of Jhanda put themselves under the protection of the Chief of Knaria, to whom they agreed to pay half the revenue of their estates. This division has continued up to the present day.

*Kot-Kapur,*  
*Mukatsar, Miri and*  
*Mudki.*

These *ikálas*, together with the State of Faridkot, formed originally one territory, having its capital at Kot-Kapur. The zaminiars are Barárs (Sidho) Jats, a tribe which claims a common descent with the Bhattis of Sirsa. It is said that in the regn of Akbar they had a dispute with the Bhattis, which ended in the demarcation of the boundary now recognized between Bhattiána (Sirsa) and this district. Bhallam (the tribal history proceeds to relate), who was at this time Chief of the Barárs, was succeeded by his nephew Kapur, who built the fort which now bears his name, and made himself independent as ruler over all the Barárs. The grandson of Kapur, Jodh Singh, gave the tract, now known as Faridkot, to his brother Hazir Singh, who also became an independent Chief. In 1807 Diwan Mehmān Chand conquered the whole of this territory from Tejh Singh, son of Jodh Singh, and added it to the Lahore *deshmene*. Mehmān Chand established *thana*s at Kot-Kapur, Mukatsar and Miri, and since that time the villages subject to these *thana*s have been known as separate *ikálas*. The historical interest of the tahsil is centred in Mukatsar itself, where Guru Gobind Singh was defeated by the imperial troops in 1705-6. The Guru, who had escaped, "caused the bodies of his slaughtered followers to be burned with the usual rites, and declared that they had all obtained *mukti*, or the final emancipation

of their souls, and that whoever thereafter should bathe at this spot on the anniversary of that day should also inherit the same blessed state; hence the origin of the name *Mukatsar*, or *Muktisar*, the pool of salvation, and of the *mela* on the anniversary of this event.<sup>1</sup>

The Sultan Khanwala *hakka* is so called from the principal village in it, which was founded by Sultan Khan a native of Maiwâl. It was a dismal waste when Pahaw Singh, ruler of Furdikot, took possession of it. It was transferred to the Ferozepore District from Fardikot in 1847 in exchange for a portion of Kot-Kapura.

These *hakkas* are inhabited by another branch of Barars or Sidhu Jats, connected through a remote ancestor with the Barars of Kot-Kapura. The Phulkian family, to which belong the Rajas of Patiala, Jind and Nââha, is of this branch; and within this district it is represented by the Chief of Malsand and Mahrajkhan family, all of whom hold considerable *jigirs*.\*

This was a waste tract between the territories of the Barars and Dogars, and was a constant subject of dispute between them. About 140 years ago, a Sidhi, named Guru Har Sahai, native of Mohammelpur in Kasur, who had fled from his home on the occasion of one of Ahmed Shah's invasions of the country, pitched his tent on this waste. The Dogar Chieftain, Sultan, gave him protection and encouraged him to settle in this place, rightly considering that his presence there would be the best safeguard against the incursions of the Barars and prevent any further disputes between them and the Dogars. The Barars also regarded him with a favourable eye, he being a priest of their own religion. Finally, with the consent of both parties, he was permitted, by riding his horse round the waste land borders, to fix the boundaries of a new *haka*, thenceforth called after his name. The guru was eighth in descent from Guru Ram Das. During the invasion of the Sikhs his title was always respected, and he was confirmed in possession by the British Government.

Mohammelist, which is undoubtedly the present Mamdot, is noted in the *Ayn Akbari* as one of the six *parganas* subordinate to the Sûls of Musitan. The revenue was estimated at 3,492,452 *dams*, equivalent to Rs. 87,311. The modern *haka* forms the south-west portion of the Ferozepore District, and extends for about forty miles along the left bank of the Sutlej, having an average breadth of not more than eight or nine miles. Its area, according to the survey made by Captain Stephenson in 1850, is 371 square miles. In this, as in the other *hakkas* comprised in the Ferozepore District, there are evident traces that it was at one time much better peopled and cultivated than at present. The country had, however, become an entire waste when the Dogars, with the consent of the imperial authorities, took possession of it about 1750 A.D. During the decline of the Empire, the Dogars here, as at Ferozepore, made themselves independent on the

## Chapter II.

### History.

History of the *hakkas* subsequently added to the district.

Kot-Kapura,  
Mukatsar, Mori and  
Malki.

Sultan Khanwala.

Malsand, Bhakhira,  
Kot-Bhoi and  
Jhambia.

Guru Har Sahai.

Mamdot.

\* The Chief of Bimânar is also of the same clan.

**Chapter II.****History.**

*History of the districts subsequently added to the district.*

**Mamdot.**

flight of the Lahore Governor, Kábúl Mál, in 1764. They were for a time subjected by Sardár Sobha Singh, a Sikh Chief, who then rose to temporary power. The Dogars, however, called in the assistance of the Ráí of Bushot, who sent a body of troops, and, dispersing the followers of Sobha Singh, himself assumed the government. But the Dogars were no better contented with the rule of the Ráí than of the Sikhs, and soon after, with the assistance of the two brothers, Nizám-ul-Dín and Kutb-ud-din, who had made themselves supreme at Kasur, they expelled the Ráí, and would probably soon after have expelled their new rulers had not the establishment of the British power over the Cis-Sutlej States confirmed the incumbents and prevented the recurrence of the violent expulsions of former times.

The brothers Nizám-ul-Dín and Kutb-ud-din were Haesauzai Pathans, and are said to have been formerly in the service of the Emperor of Delhi. They afterwards settled at Kasur, and, followed by a band of their fellow-countrymen, took to ploughing the country, until in course of time they were able to establish their supremacy in the whole of the Kasur territory and beyond the Sutlej in Mamdot. They then divided the land, Nizám-ul-Dín fixing his residence at Kasur, and Kutb-ud-din at Khosian; but Nizám-ul-Dín being shortly afterwards murdered Kutb-ud-din established his unlimited authority over the whole estate. He was soon, however, compelled to give way to the growing power of Ranjit Singh,\* who took Kasur from him, but gave him in lieu of it the jágir of Maruf in the Gugera District, and allowed him to retain Mamdot on condition of providing 100 horsemen for service. The Maruf contingent was also fixed at 100 horsemen. Nizám-ul-Dín had left a son, named Fateh Dín, a minor at the time of his father's murder. On coming of age, Fateh Dín appealed to the Mahárája against his uncle's usurpation. The Mahárája put him in possession of Maruf, and ordered Kutb-ud-din to retire across the Sutlej and fix his residence at Mamdot. Shortly afterwards Fateh Dín, secretly encouraged, it is said, by the Mahárája, crossed the Sutlej to attack his uncle, and with the assistance of the Dogars, who were as usual ever ready for a change, drove out Kutb-ud-din and took possession of Mamdot. Kutb-ud-din died soon afterwards of the wounds received in the conflict with his nephew. His son Jamál-ul-din, however, appealed to the Mahárája, who recalled Fateh Dín and installed Jamál-ul-din at Mamdot. A few years later Fateh Dín made another attempt on Mamdot, but the agent of the British Government interfered, and he was in consequence a second time recalled by the Mahárája. Fateh Dín continued, however, to press his claim, and the title to Mamdot was not formally decided till the Sutlej Campaign, when Shah Nawáz Khan, son of Fateh Dín, was killed at Firoozshah fighting on the side of the Sikhs. Jamál-ul-din, on the other hand, allied himself to British interests, and did good service, in reward for which he received the

\* See Gazetteer of Lahore.

title of Nawab, and was allowed to retain sovereign powers in the State,\* his contingent being at the same time reduced from 100 to 50 horsemen. The Nawab always entertained the greatest animosity towards the Dogars on account of their former opposition to his father and himself, and gradually dispossessed most of the powerful families of their lands and drove them out of the country. The Dogars, unable any longer to call in some foreign Chief to their assistance, petitioned the Commissioner of Umballa; and an enquiry was instituted, in the course of which a series of most atrocious acts was brought to light against the Nawab and his two sons. Some cases of actual murder were also, it is believed, proved against the family. After a prolonged and careful inquiry the Nawab, Jamal-ud-din, was deposed and his estates attached to the Ferozepore District. Two-thirds of the revenue was assigned for the support of the family and one-third was appropriated to the State. Jamal-ud-din died in 1803. His brother Jai-al-ud-din, who succeeded him, died in 1875, and was succeeded by his son Nasim-ud-din Khan, the present Chief, who attained his majority in 1888.

The following account of the Fazilka Tahsil is taken from Mr. J. Wilson's Report on the Settlement of the Sirm District written in 1883. This tract in 1800 was almost uninhabited. There was no village where Fazilka now stands. The riverside country was occupied only by 12 small villages of Bodias, Wattis, and Gidials, who had come over from the other side of the river a few years before. It was left for a long time to the Nawabs of Bahawalpur and Mandot, who established some small forts. Their common boundary was ill-defined, but was approximately the same as afterwards became the boundary between parganas Wattu and Bahak. In 1841 the Wattu Pargana, so called from the principal tribe inhabiting it, comprising a strip of land running down from the Damia to the Sutlej, was ceded by the Nawab of Bahawalpur in exchange for a similar tract given to him on the Sindh frontier, and was attached to Bhuttiana. This strip was acquired partly to permit of the extension of the customs line to the river, and partly that a Political Officer might be stationed there to watch the surrounding foreign States of Lahore, Fazilket, Mandot and Bahawalpur. In 1858 pargana Balau, on the Sutlej, lately confiscated from the Nawab of Mandot, was transferred from the Ferozepore District to the Sirm District. It had been settled by Mr. Iramroth in 1837-38 before its transfer. The Fazilka Tahsil was divided in the first Regular Settlement of Sirm into four parganas as follows:—

1. Malaut—129 villages. Consisting of the southern portion of the tahsil, the chief village of which was Malaut, resumed from the Sikh Chiefs in 1837.

## Chapter II.

### History.

History of the districts subsequently added to the district.  
Bamdot.

Fazilka.

**Chapter II.****History.**

History of the districts subsequently added to the district.

**Phulkot.****Faridkot.**

2. *Mohijani*—45 villages. Consisting of the tract immediately south-east of the Danda or old bank of the Sutlej, resumed from the Sikh Chiefs in 1837.

3. *Wattian*—80 villages. Lying north-west of the Danda, down to the Sutlej, ceded by Bahawalpur in 1844.

4. *Bahak*—39 villages. Also between the Danda and the Sutlej above pargana Wattian.

A short notice may be here given of the Native State of Faridkot, the territory of which lies between the main portion of the district and the outlying pargana of Muktsar. It contains an area of 612 square miles, and, according to a census effected in 1881, had in that year a population of 97,034 souls. The territory subject to the Rāja of Faridkot consists of two portions, Faridkot proper, and a jāgir estate of an annual value of Rs. 35,000 conferred on the Rāja for his attachment to the British cause during the Sutlej Campaign. The whole revenue now amounts to about Rs. 3,00,000. Faridkot was originally included in the Kot-Kapura *lokha* under the rule of Sardār Jodh Singh, who gave Faridkot and the adjoining villages to his brother Hamir Singh. Hamir Singh's grandson Charn Singh, was murdered by his uncle Dal Singh; but the usurper was soon after put to death by his subjects, who restored the direct line of succession by the installation of Gulāb Singh, son of Charn Singh. Some years later Gulāb Singh died under suspicious circumstances, and was succeeded by his younger brother, Pahār Singh. Pahār Singh proved himself a wise ruler. He located many new villages and brought large waste tracts for the first time under the plough, attracting immigrants by light rates of assessment and by the good faith with which he kept his promises. He was one of our most faithful allies during the Sutlej Campaign and was rewarded with the jāgir already mentioned and with the title of Rāja. Pahār Singh died in 1849, and was succeeded by his son Wazir Singh, a weak man and an incompetent ruler. The prestige, however, of Pahār Singh's acts still remained, and the natural disposition of the Rāja was not such as to lead him to the commission of acts of tyranny or excess. He died in 1874, and was succeeded by his son Bikrama Singh, who was then about 27 years of age, and for some years before his father's death took an active part in the administration of the State. He is an intelligent prince, and anxious for the welfare of his people, though not highly educated. Since his accession he has set himself vigorously to work to reform the administration on the British model, and borrowed the services of British subordinate revenue officials to settle and assess the territory. He is also engaged in the preparation of improved codes of law for his people.

Gradual formation  
of the present dis-  
trict.

At the close of the campaign of 1846 there were added to the existing district of Ferozepore, as already described, the *lokhas* of Khīl, Baghuwāla, Ambāchar, Zira, and Mudki, together with portions of the following:—Kot-Kapura, Guri Har Sahai, Jhūmba, Kot Bhai, Bhucchobh and Mahrāj. The other acquisi-

tions of the British Government were divided between the districts of Badshah and Ludhiana. In 1847 the Badshah district was broken up, and the following tehsils were added to the Ferozepore district:—Mallanwala, Makhu, Dharmkot, Kot Ise Khan, Badshah, Chohar Chak, Mari, and Sada Singhwala. In the same year Sultan Khanwala was taken from Faridkot in exchange for a portion of Kot-Kapura. The next addition took place in 1852, when a portion of the tehsil of Muktsar and Kot-Kapura, hitherto held in excess of his jagir in the same tehsil by the Raja of Faridkot, was taken under direct management. This was an addition of about 100 square miles. The following figures refer to the old Sikh tehsils, included in the district as they stood in 1855:—

## Chapter II.

## History.

Gradual formation  
of the present dis-  
trict.

Names of tehsils.	Number of villages.	Area in square miles.	Revenue (Rs.)	Total population.	Mussah.			Mussah.			Total.
					Arable land.	Rice-and-maize.	Total.	Arable land.	Rice-and-maize.	Total.	
Ferozepore	55	62,358	24,405	29,150	4,050	8,700	12,750	10,000	11,400	21,400	29,420
Khat	14	52,145	11,000	11,200	600	4,000	4,600	6,000	6,000	12,000	10,420
Badrin Khan-	—	—	—	—	—	—	—	—	—	—	—
wala	21	47,200	13,200	13,400	3,400	7,700	11,100	7,000	7,000	14,000	13,700
Bachawala	20	42,000	11,200	11,400	1,200	3,000	4,200	3,000	3,000	6,000	12,000
Mukhter	24	40,420	10,000	10,200	3,000	5,000	8,000	3,000	3,000	6,000	12,000
Muktsar	122	210,470	52,000	52,200	20,000	5,200	25,200	12,000	12,000	24,000	72,000
Kot Kapura	—	—	—	—	—	—	—	—	—	—	—
Johri	29	60,360	12,400	12,600	3,200	8,000	11,200	7,000	7,000	14,000	22,800
Guru Nanak Dev	14	20,700	5,000	5,200	1,000	2,000	3,000	1,000	1,000	2,000	3,200
Anandpur	19	22,200	5,000	5,200	1,200	2,000	3,200	1,200	1,200	2,000	3,000
Zira	14	21,120	10,000	10,200	3,000	1,000	4,000	3,000	3,000	4,000	7,000
Kot Ise Khan	10	40,110	10,000	10,200	2,000	5,000	7,000	2,000	2,000	4,000	11,200
Dharmkot	20	120,200	20,000	20,200	22,000	7,200	29,200	12,000	12,000	24,000	56,200
Panjabpur	21	22,200	10,000	10,200	2,000	5,000	7,000	2,000	2,000	4,000	10,200
Hajiganj	27	24,200	12,000	12,200	2,000	5,000	7,000	2,000	2,000	4,000	10,200
Makhu	22	20,400	10,000	10,200	2,000	5,000	7,000	2,000	2,000	4,000	9,200
Badiani	20	100,200	20,000	20,200	21,200	6,200	27,200	10,000	10,000	20,000	56,200
Chohar Chak	11	22,200	12,000	12,200	0,000	1,000	1,000	0,000	0,000	1,000	4,000
Mari	12	22,200	12,000	12,200	2,000	5,000	7,000	2,000	2,000	4,000	10,200
Sada Singhwala	10	22,200	12,000	12,200	2,000	5,000	7,000	2,000	2,000	4,000	10,200
Mohinder Singh-	—	—	—	—	—	—	—	—	—	—	—
Chohar Chak	—	—	—	—	—	—	—	—	—	—	—
Total	—	1,000,224	210,200	211,200	161,000	40,000	200,000	84,200	87,200	161,000	—
Def.	—	—	200,000	120,000	60,000	8,000	7,200	11,000	40,000	28,000	77,200
Def.	—	—	400,000	300,000	100,000	10,000	20,000	50,000	20,000	30,000	60,000
Outlying parts	—	—	200,000	100,000	50,000	10,000	20,000	30,000	7,000	7,000	12,000
Total	—	—	1,000,224	1,000,200	500,000	121,000	300,000	180,000	94,200	97,200	300,000

In 1855 the eight villages constituting the tehsil of Chhirah were restored to the Sadar of Kalsia, as the supposition under which they had been brought under British control, that they were shared equally between the Kalan State and Sadar Dera Singh, a British subject, was found to be incorrect. In 1858 the estates of the deposed Nawab of Mumdot were annexed, as has already been related. In 1857 nine villages of the Makhu tehsil were ceded to the Kapurthala State on account of river action, the deep stream having shifted so as to separate them from the Ferozepore bank. Subsequently the stream resumed its old course; but it

**Chapter II.****History.**

*Gradual formation  
of the present dis-  
trict.*

had meanwhile been ruled that the deep stream rule did not affect the boundary in question, and Kapurthala has accordingly retained five villages. In 1858 the village of Sibian, one of those granted in exchange to Fazilka, was taken back on the ground that it was held as a revenue free life-grant by Sudhi Gulab Singh. In November 1881, on the partition of the Sirsa District, the western half, including the whole of the Fazilka Tahsil and about 40 villages of the Daulwali Tahsil was included in the Ferozepore District, the eastern half being attached to Hissar.

**The Mutiny.**

The following account of the events of 1857 is taken from the Panjab Mutiny Report:—"At a court of inquiry assembled some time previous to the Delhi mutiny, a native officer of the 57th Native Infantry at Ferozepore declared that it was the purpose of his regiment to refuse the Enfield cartridge if proffered to them. This raised a strong feeling of suspicion against the corps, but the 45th Native Infantry, which was not on good terms with the 57th, and had openly declared their contempt of the resolution of the 57th, was considered staunch. On the 14th May, as soon as news by express from Lahore of the Delhi disaster reached Brigadier Junes, who had the previous day taken command, he ordered the entrenched arsenal to be immediately garrisoned by part of Her Majesty's 61st Fost and the Artillery. All ladies were also removed thither, and the two Regiments of Native Infantry ordered into camp in positions of about three miles apart. The way of the 45th Native Infantry lay past the entrenchment. As they approached, their column insensibly swerved towards the glacis; the movement had barely been observed when they swarmed up the slope and attacked the position. The Europeans in an instant divined their intent, and rushed to the ramparts with the bayonet. The attack was repulsed; but before the 61st could load the sepoys dashed at the gate, whence they were also flung back, and then with an air of injured innocence they reformed their column and marched quietly with their European officers to the camp. During the night the church, the Roman Catholic chapel, the school-house, 17 officers' houses and other buildings were burnt to the ground by the men of the 45th, but not before the chaplain, the Rev. R. B. Malby, failing to obtain a guard of Europeans, had boldly rushed unattended through the infuriated sepoys and into the blazing church, and had succeeded in rescuing the registers out of it. On the 14th the treasury was moved into the entrenchment, and it was discovered that of the 45th Regiment there only remained 133 men; the rest, with a large part of the 57th, had deserted. The remaining portions of these regiments were subsequently disbanded.

"Danger impended over this district from both north and south. To avert the threatened incursion of the mutinous troops from Lahore, the large ferries on the Sutlej were guarded, and the boats from the small ones sent to Hacriki. To check the approaches of the wild tribes from Sirsa and Bhattian, General Van Cortlandt, in a fortnight, raised a levy of 500 Sikhs—a force

which, subsequently uniting with Râja Jauâhir Singh's troops and other bodies sent down from time to time by the Chief Commissioner, amounted to 5,000 men of all arms, and performed excellent service in Sirsa and Hisar. Major Marsden received information at one time that a *râjârâj*, named Sham Dâs, was collecting followers with a treasonable intent. He promptly moved against the rebel, and coming upon him by surprise attacked and completely defeated him with the loss of several men. Sham Dâs himself was seized and executed. This act of vigour on the part of Major Marsden was a most important step in the preservation of the peace of the district; for at that critical time any show of success for the evil-disposed would have raised the whole region in revolt. In the western division 157 extra men were entertained in the police establishment, and the feudatory Chiefs furnished a body of 200 horse and 40 foot. Every highway robber was executed at once. This display of severity, with the presence of general Van Cortlandt's force, and increased energy on the part of the civil authorities, preserved the peace of the district well. On the 11th July the 10th Light Cavalry was, as a precautionary measure, dismounted and disarmed; but on the 19th August the men made a rush at their horses, cut loose about 50 of them, and seizing every pony or horse they could find in the station, including many officers' chargers, mounted and rode off for Delhi. With the connivance of the native horse-keepers of the Artillery, they also attacked the guns, but were repulsed, though not until they had killed three of the 61st Regiment and wounded three, of whom one was a female. They also cut down Mr. Nelson, the Veterinary Surgeon of their Regiment. Of the 142 mutineers captured 40 were executed, and the remainder, with 25 of the Artillery horse-keepers, transported or imprisoned. In the jail 18 persons, including the Nawâb of Ranâ, who had been captured by Mr. Bickett in the Ludhiana District, were hanged. The siege train was despatched from the arsenal on August 18th, and more than 2,000 cart-loads of munitions of war were sent to Delhi during the siege.<sup>2</sup>

The following account of the events at Fazilka is taken from Mr. Wilson's Settlement Report of Sirsa:—“Mr. Oliver, Assistant Superintendent of Bistâna was in charge of the Fazilka outpost, which he had held since 1848, and had acquired great influence over the people. The troops stationed there were a small detachment of the 57th Native Infantry and some Irregular Cavalry. When a feeling of dissatisfaction appeared among the troops at Perozspore the Fazilka detachment showed some inclination to break out. The customs establishment collected at Fazilka from the outposts were holding their opportunity, willing at any moment to join the disaffected troops, and loudly called for arrears of their pay. Mr. Oliver, though uncertain as to the feelings of the population, called in the most influential headmen, chiefly Bodias and Wattas of the Sutlej, and with their aid was able to disarm the guard of the 57th Native Infantry. Through their influence the neighbouring population was prevented from rising, and the number of matchlock men they collected and entertained

**Chapter II.**

**History.**

**The Mutiny.**

in the service of Government overawed the customs peons and other disaffected parties, and with their assistance Mr. Oliver was enabled to protect the town of Fazilka, and to punish and destroy large villages which were in open rebellion a few days after the first outbreak. General Van Cortlandt crossed the Sutlej with some police and local levies from Gugera and marched towards Sirsa with Captain Robertson, the Superintendent, who joined him at Malaut on the 12th June. Order was then restored in the remainder of the district. Mr. Oliver, with tact and energy, kept down the excited feelings of the people and restrained them from rising again, although they were constantly incited to do so by emissaries from Hariana, and although the troops at his disposal were few in number and the loyalty of some of them at that time very doubtful. Several villages in the Fazilka Rohi, whose Mussalmān owners had distinguished themselves in raids on their Hindu neighbours, were confiscated. Some of these villages were conferred in proprietary right on the more prominent of the Bodis and Wattas, whose services and effective aid had enabled Mr. Oliver to maintain the peace at Fazilka, while revenue free grants were made to a number of them. Mr. Oliver himself received high commendation and exceptional promotion for the manner in which he had maintained order at Fazilka where all around was anarchy and confusion."

District officers. The following is a list of the officers who have held charge of since annexation. the district since it became a British possession :—

*List of District Officers from 1808 to 1883.*

Name.	Officer.	From	To
M. P. Bishopworth	Assistant Political Agent, N.W. Frontier	2-12-39	18-1-29
Capt. J. M. Lawrence	Do. " " " "	17-1-39	29-3-32
Lient. J. D. Cunningham	Do. " " " "	29-3-32	18-6-32
H. Vanburgh	Do. " " " "	17-9-32	20-12-32
Capt. H. M. Lawrence	Do. " " " "	20-12-32	20-4-33
H. M. Greathead	Do. " " " "	20-4-33	20-4-34
Capt. T. Stevenson	Do. " " " "	23-4-34	1-1-35
P. A. Yancey	Do. " " " "	19-5-35	22-1-35
H. C. Parker	Do. " " " "	22-1-35	22-2-35
J. T. Daniel	Do. " " " "	22-2-35	22-2-36
C. H. Bowes	Do. " " " "	22-2-36	22-7-36
E. J. Bradstreet	Do. " " " "	22-7-36	18-11-36
Capt. J. M. Orme	Do. " " " "	18-11-36	22-9-36
Major F. C. Marston	Do. " " " "	22-9-36	23-4-37
Capt. J. M. Orme	Officer-in-Charge Commissioner and Deputy	23-4-37	1-1-38
Colonel G. H. Hall	Deputy Commissioner and Inspector	1-1-38	21-4-38
Capt. J. M. Orme	Deputy Commissioner	21-4-38	1-1-39
Capt. H. M. Bailey	Deputy Commissioner	1-1-39	5-2-39
Capt. R. T. Reid	Deputy Commissioner	5-2-39	21-2-39
Capt. J. M. Orme	Deputy Commissioner	21-2-39	18-1-40
E. W. Thomas	Officer-in-Charge Commissioner	18-1-40	21-4-40
Colonel	Deputy Commissioner	21-4-40	21-6-40
H. G. Marshall	Deputy Commissioner	21-6-40	31-12-40
Capt. F. Martens	Deputy Commissioner	31-12-40	2-1-41
H. W. P. Watts	Officer-in-Charge Commissioner	2-1-41	22-3-41
Major P. Maxwell	Deputy Commissioner	22-3-41	27-12-41
G. E. Wahabzai	Officer-in-Charge Commissioner	27-12-41	31-12-41
Major P. Maxwell	Deputy Commissioner	31-12-41	1-1-42
G. Khan	Deputy Commissioner	1-1-42	2-1-42
G. E. Wahabzai	Officer-in-Charge Commissioner	2-1-42	20-12-42
Major P. Maxwell	Deputy Commissioner	20-12-42	2-1-43
G. Khan	Officer-in-Charge Commissioner	2-1-43	1-6-43

*List of District Officers from 1808 to 1853—continued.*

## Chapter II.

## History.

District officers  
since annexation.

Name.	Title.	From	To
Capt. S. H. T. Maxwell	Officiating Deputy Commissioner	2-6-71	20-6-71
Lieut.-Col. F. Maxwell	Deputy Commissioner	1-7-71	2-8-72
Col. W. Grey	Officiating Deputy Commissioner	2-8-72	1-4-72
H. T. Harvey	Do. " " No.	1-4-72	21-11-72
Lieut.-Col. J. Maxwell	Deputy Commissioner	2-12-72	20-7-73
Col. H. T. Harvey	Officiating Deputy Commissioner	20-7-73	21-8-73
John Col. J. Maxwell	Deputy Commissioner	1-8-73	18-8-74
Capt. L. J. H. Grey	Officiating Deputy Commissioner	1-8-74	13-6-78
J. W. Hartley	Deputy Commissioner	13-6-78	20-11-78
Capt. L. J. H. Grey	Officiating Deputy Commissioner	20-11-78	25-11-78
J. W. Hartley	Deputy Commissioner	25-11-78	10-1-77
Majors L. J. H. Grey	Officiating Deputy Commissioner	10-1-77	20-8-77
J. Pringle	Do. " " Do.	20-8-77	2-9-78
J. Pringle	Deputy Commissioner	2-9-78	21-6-78
H. W. Ward	Officiating Deputy Commissioner	21-6-78	2-1-79
H. G. French	Deputy Commissioner	2-1-79	15-7-79
H. W. Ward	Do. " " Do.	15-7-79	8-8-80
Majors L. J. H. Grey	Deputy Commissioner	8-8-80	18-11-80
J. H. Dernwood	Officiating Deputy Commissioner	18-11-80	1-8-81
Majors L. J. H. Grey	Deputy Commissioner	1-8-81	21-12-81
Capt. H. M. M. Wood	Officiating Deputy Commissioner	21-12-81	28-12-81
Mr. H. C. Brown	Deputy Commissioner	28-12-81	8-3-82
Majors H. M. M. Wood	Officiating Deputy Commissioner	8-3-82	10-3-82
Mr. H. C. Brown	Deputy Commissioner	10-3-82	4-4-83
Majors H. M. M. Wood	Officiating Deputy Commissioner	4-4-83	8-4-83
T. G. Wilkinson	Deputy Commissioner	8-4-83	8-5-83
Mr. F. P. Beauchroft	Deputy Commissioner	8-5-83	20-5-84
Mr. J. C. Brown	Officiating Deputy Commissioner	20-5-84	10-7-84
Mr. F. P. Beauchroft	Deputy Commissioner	10-7-84	21-10-84
Colonel H. C. Corlett	Do. " "	21-10-84	27-10-85
Mr. E. H. Francis	Officiating Deputy Commissioner	27-10-85	28-10-85
Bacon John Beckwith	Deputy Commissioner	28-10-85	2-11-85
Colonel H. C. Corlett	Do. " " Do.	2-11-85	2-12-85
Mr. E. H. Francis	Officiating Deputy Commissioner	2-12-85	2-1-86
Mr. E. H. Francis	Deputy Commissioner	2-1-86	2-2-86
Colonel F. M. Birch	Officiating Deputy Commissioner	2-2-86	1-3-86
Mr. J. C. Brown	Deputy Commissioner	1-3-86	11-3-86
Colonel F. M. Birch	Officiating Deputy Commissioner	11-3-86	11-5-86
Mr. F. P. Beauchroft	Deputy Commissioner	11-5-86	20-5-86
Mr. J. C. Brown	Do. " "	20-5-86	21-10-86
Mr. F. P. Beauchroft	Officiating Deputy Commissioner	21-10-86	28-10-86
Colonel R. A. Corlett	Deputy Commissioner	28-10-86	2-11-86
Mr. E. H. Francis	Officiating Deputy Commissioner	2-11-86	23-8-86
Bacon John Beckwith	Deputy Commissioner	23-8-86	25-8-86
Colonel R. A. Corlett	Do. " " Do.	25-8-86	28-10-86
Mr. E. H. Francis	Officiating Deputy Commissioner	28-10-86	28-10-86
Mr. M. V. Fenton	Deputy Commissioner	1-1-87	8-3-86
Mr. H. C. Brown	Officiating Deputy Commissioner	8-3-86	8-4-87
Colonel F. M. Birch	Deputy Commissioner	8-4-87	14-8-87
Mr. J. C. M. Kenne	Officiating Deputy Commissioner	14-8-87	18-10-87
Colonel F. M. Birch	Deputy Commissioner	18-10-87	...

N.B.—Major F. C. Maxwell made over and Captain J. M. Orton took over charge of the Ferozepore District on the 1st October 1857.

The station of Ferozepore in 1839, when as yet neither the *Development of Punjab* nor Sind had been annexed, was a species of *Ultima Thule*, the furthest limits of our Indian possessions. It was described as a dreary and desert plain, where very little rain was ever known to fall and an almost continual dust-storm was the normal condition of the atmosphere. The rich cultivation assigned by tradition to the period of the Mohammadan Empire, and still evidenced by numerous deserted sites of villages and wells, had long since disappeared. There were a few scattered patches of cultivation; but great wastes covered with low brushwood were the usual characteristics both of the Ferozepore territory and of the neighbouring country. From the first, however, the humanizing influence of security for person and

**Chapter II.****History.**

**Development of  
the district.**

property began to tell upon country and people alike. Cultivation was extended, trees were planted, and no effort was spared to replace the former misrule by an era of quiet and contentment. In 1855 Mr. Brandreth wrote as follows :—

"On the whole, however, I have good reason to think well of the future prospects of the district. The great diminution of all the more serious crimes is very remarkable. Last year there was only one highway robbery recorded, and that occurred in one of the newly annexed portions of the district, and before it had been properly brought under police control. The perpetrators of the crime, however, were apprehended and convicted. Previously to my taking charge, when the district was not more than half its present size, there were never less than from 15 to 20 highway robberies committed every year,—and these not trifling cases like that above referred to, but often accompanied with murder and wounding,—and it was very seldom that any of the offenders were brought to justice. The decrease of this and other heinous crimes, to whatever cause they may be attributed, cannot be regarded as otherwise than highly gratifying. I believe that a good deal is owing to a better organization of the police; but I think also that it must, in part, be set down as the effect of the Settlement, which has given the people a knowledge of their rights and an interest in their property which they never felt before. Some of the principal men among them have acknowledged to me since that the Settlement has had a most beneficial effect on the inhabitants, and taught them that there was a tangible value attached to their property, the proceeds of which were sufficient to afford them every reasonable comfort in life; that it would be the height of folly to risk its loss by any unlawful act; and that crime in general had been very much checked by those considerations. Since the Settlement there has been also a great stir among the Dogras and Naipais, who have been hitherto the greatest thieves of the Et. They now seem determined to make the most of the 30 years' lass that is before them. Great preparation has been made for increasing the number of wells, and there is scarcely a day in which one or more carts, laden either with Persian wheels or cross bars and uprights for supporting them, may not be seen traversing the new Jallander road in the direction of the Et villages."

The immediate effect of a settled government established in close proximity to a border such as that of the Sikhs is well illustrated in the country immediately around Ferozepore. In 1841 Sir H. Lawrence ascertained the population of the town and territory of Ferozepore (inclusively of the cantonment and military bazaars), by a careful enumeration, to be 16,890 souls. Ten years later, in 1851, Mr. Brandreth found the population of the same tract to be 27,357 souls, showing an increase of 10,967, at the rate of 64 per cent. It is not possible to give the population, as ascertained later on, of the same area.

Some conception of the development of the district since it came into our hands may be gathered from Table No. II., which gives some of the leading statistics for five yearly periods, so far as they are available; while most of the other tables appended to this work give comparative figures for the last few years. In the case of Table No. II. it is probable that the figures are not always strictly comparable, their basis not being the same in all cases from one period to another. But the figures may be accepted as showing in general terms the nature and extent of the advance made. The following table compares the revenue

of the district as it stood at four periods separated by intervals of a decade.

*Imperial Revenue 1851-52, 1861-62, 1871-72 and 1881-82.*

## Chapter II.

### History.

Development of  
the District.

Year.	TAXES RECEIVED.			OVERS RECEIVED.				
				RENTS.		Assessed Value.	Assessed Rent.	MISCELLANEOUS.
	Proper.	Tribute.	Post-milling.	Spurts.	Duties.			
1851-52	Ru.	Ru.	Ru.	Ru.	Ru.	Ru.	Ru.	Ru.
1851-52	8,90,445	11,368	23,000	4,326	25,100	—	12,227	8,218
1861-62	1,00,010	—	—	4,051	22,000	—	20,000	—
1871-72	1,00,430	—	—	22,501	22,501	7,727	12,200	—
1881-82	1,00,000	20,941	1,181	21,055	24,800	10,310	10,000	—

## CHAPTER III.

## THE PEOPLE.

## SECTION A.—STATISTICAL

**Chapter III, A.**  
 statistical.  
 Distribution of  
 population.

Table No. V gives separate statistics for each tahsil and for the whole district of the distribution of population over towns and villages, over area, and among houses and families; while the number of houses in each town is shown in Table No. XLIII. The statistics for the district as it stood at the time of the census give the following figures. Further information will be found in Chapter II of the Census Report of 1881. It must be remembered that at that time the Fazilka Tahsil was not included in Ferozepore:—

Percentage of rural population who live in villages	Males	Females	Total
Average rural population per village	—	—	9,725
Average total population per village and town	—	—	9,754
Number of villages per 100 without towns	—	—	404
Average distance from village to village, in miles	—	—	347
Density of population per square mile of			
Total area	—	—	251
Cultivated area	—	—	241
Cultivable area	—	—	228
Cultivated land	—	—	227
Number of resident families per occupied house	Villages	Towns	Total
Number of persons per occupied house	Villages	Towns	Total
Number of persons per resident family	Villages	Towns	Total

The villages are unevenly distributed, but are most thickly congregated in the *Bet*. "In ilaka Fathgarhi," writes Mr. Brandreth, "it is a common saying that a message could be sent from one end of the ilaka to the other by a verbal call from village to village."

Table No. VI shows the principal districts and States with which the district has exchanged population, the number of migrants in each direction, and the distribution of immigrants by tahsils. Further details will be found in Table No. XI and in Supplementary Tables C to H of the Census Report for 1881, while the whole subject is discussed at length in Part II of

Proportion per mile of  
 total population.

	Gains.	Losses.
Persons	104	115
Males	57	51
Females	47	64

Chapter III of the same report. The total gain and loss to the district by migration is shown in the margin. The total number of residents born out of the district is 126,218, of whom 62,366 are males and 63,852 females. The number of people born in the district and living in other parts of the Punjab is

74,740, of whom 32,634 are males and 42,106 females. The figures below show the general distribution of the population by birth-place:—

Chapter III, A.  
statistical.

Migration and  
birth-place of  
population.

Born in	Proportion per mil. of Resident Population.									
	Rural population			Urban population			Total population			
	Males	Females	Persons	Males	Females	Persons	Males	Females	Persons	
The Province	100	78	83	112	91	101	107	79	100	106
India	100	98	100	100	100	100	100	100	100	100
Asia	100	100	100	100	100	100	100	100	100	100

The following remarks on the migration to and from Ferozepore are taken from the Census Report:—

"Ferozepore is an eminently progressive district. Canal irrigation has been largely extended of late years, and it is not surprising to find that the immigration is 70 per cent. in excess of the emigration to Sirsa, which is developing even faster than Ferozepore, and is the only district that takes from it. The emigration is much more largely of the reciprocal type than is the immigration, especially in the case of the districts to the east, where the marriage customs which lead to reciprocal migration prevail. It will be noticed how much larger the proportion of immigration to emigration is in the case of those districts where pressure of population is greater than in that of the less thickly peopled districts. The immigration from the North-Western Provinces is, of course, owing to the presence of large canals."

The figures in the statement below show the population of the district as it stood at the three enumerations of 1855, 1868, and 1881:—

Increase and  
decrease of  
population.

Year	Census,		Persons.	Males.	Females.	Density per square mile.
	1855	1868				
Actual	100	—	47,433	23,704	23,729	130
1855	100	—	47,433	23,704	23,729	130
1868	—	112	63,672	32,339	31,333	209
1881	—	111	63,672	32,339	31,333	208
Total	100	112	111,777	56,372	55,405	130
1855 to 1868	100	112	18,243	9,635	9,638	130
1868 to 1881	100	111	18,000	9,037	9,033	130

Unfortunately the boundaries of the districts have changed so much since the census of 1855 that statistics of sex are no longer available for that enumeration. It will be seen that the annual increase of population per 10,000 since 1868 has been 128 for males, 130 for females, and 131 for persons, at which rate the male population would be doubled in 55·4 years, the female in 51·2 years, and the total population in 58·5 years. Supposing the same

**Chapter III. A.**  
Statistical.

Increase and  
decrease of  
population.

rate of increase to hold good for the next ten years, the population for each year would be, in hundreds—

Time.	Females.	Males.	Females.	Year.	Females.	Males.	Females.
1861	609,2	577,2	202,2	1862	601,2	569,2	201,2
1863	602,2	571,2	207,2	1864	612,2	580,2	209,2
1865	607,2	586,2	201,2	1866	621,2	594,2	210,2
1867	624,2	577,0	204,4	1868	631,2	594,0	210,7
1869	630,2	575,0	200,2	1870	641,2	590,2	201,2
1871	641,2	566,2	203,2	1872	651,2	581,2	203,2

The increase in urban population since 1868 has been much smaller than that in rural population, the numbers living in 1881 for every 100 living in 1868 being 108 for urban and 118 for total population. The populations of individual towns at the respective enumerations are shown under their several headings in Chapter VI.

Within the district the increase of population since 1868 for the various tahsils is shown below. Details of the population of the present tahsils, as it stood at the enumeration of 1855, cannot now be obtained. The figures were then returned as follows for the respective parganas:—Fazsepore, 98,527; Mukatsar, 46,066; Moga, 186,017; Mahrat-Bhusrohpur, 32,183; Zira, 120,816; Bhadaur, 42,015.

Tahsil.	Total population.		Percentage of increase of 1881 on that of 1868.
	1868.	1881.	
Fazsepore.	—	—	—
Zira.	—	—	—
Moga.	—	—	—
Mukatsar.	—	—	—
Total District.	—	—	—
	186,119	200,312	118

\* The figures do not agree with the published figures of the Census Report of 1868 for the whole district. They are taken from the registers in the District Office, and are the best figures now available.

**Births and deaths.**

Table No. XI shows the total number of births and deaths registered in the district for the five years from 1877 to 1881, and the births for 1880 and 1881, the only two years during which births have been recorded in rural districts.

	1880.	1881.
Males	—	—
Females	—	—
Females	—	—

The distribution of the total deaths and of the deaths from fever for these five years over the twelve months of the year is shown in Table Nos. XIA and XIB. The annual birth-rates per milles, calculated on the population of 1868, are shown in the margin.

The figures below show the annual death-rates per milia since 1868, calculated on the population of that year :—

Chapter III, A.  
statistical.

Births and deaths.

	1868	1869	1870	1871	1872	1873	1874	1875	1876	1877	1878	1879	1880	1881	1882	Aver-
Male	11	11	10	10	10	10	10	10	10	10	10	10	10	10	10	age
Females	11	11	10	10	10	10	10	10	10	10	10	10	10	10	10	10
	11	11	10	10	10	10	10	10	10	10	10	10	10	10	10	10

The registration is still imperfect, though it is yearly improving ; but the figures always fall short of the facts, and the fluctuations probably correspond, allowing for a regular increase, due to improved registration, fairly closely with the actual fluctuations in the births and deaths. The historical retrospect, which forms the first part of Chapter III of the Census Report of 1881, and especially the annual chronicle from 1849 to 1881, which will be found at page 56 of that report, throw some light on the fluctuations. Such further details as to birth and death-rates in individual towns as are available will be found in Table No. XLIV, and under the headings of the several towns in Chapter VI.

The figures for age, sex, and civil condition are given in great detail in Tables Nos. IV to VII of the Census Report of 1881, while the numbers of the sexes for each religion will be found in Table No. VII appended to the present work. The age statistics must be taken subject to limitations, which will be found fully discussed in Chapter VII of the Census Report. Their value rapidly diminishes as the numbers dealt with become smaller ; and it is unnecessary here to give actual figures or any statistics for totals. The following figures show the distribution by age of every 10,000 of the population according to the census figures :—

Age, sex, and civil condition.

Persons Male Females	0-1 1-2 2-3 3-4 4-5 5-6 6-10 10-15 15-20										Over 60	
	20-25 25-30 30-35 35-40 40-45 45-50 50-55 55-60 60-65 65-70											
	70-75 75-80 80-85 85-90 90-95 95-100											
Persons Male Females	421	322	224	206	205	182	1,420	1,358	1,149	812		
	320	229	220	221	209	1,259	1,257	1,251	1,251	814		
	622	420	322	214	210	178	1,481	1,351	1,088	814		
	—	—	—	—	—	—	—	—	—	—	—	
	—	—	—	—	—	—	—	—	—	—	—	
	—	—	—	—	—	—	—	—	—	—	—	

The number of males among every 10,000 of both sexes is shown below :—

	Population.	Villages.	Towns.	Totals.
All religions	1,111	—	—	5,686
Muslims	1,111	5,400	5,216	5,686
Hindus	1,111	5,500	5,273	5,686
Christians	1,111	5,322	5,273	5,686
Others	1,111	5,322	5,273	5,686
Christians	1,111	5,322	5,273	5,686

**Chapter III, A.**  
**Statistical.****Age, sex, and civil condition.**

The decrease at each successive enumeration is almost certainly due to greater accuracy of enumeration.

Year of life	All races 1,000s.	Infants	Single	Married
0-1	645	275	368	201
1-2	606	212	241	253
2-3	575	172	188	209
3-4	532	—	—	—
4-5	467	—	—	—

In the census of 1881 the number of females per 1,000 males in the earlier years of life was found to be as shown in the margin.

The figures for civil condition are given in Table No. X, which shows the actual number of single, married, and also the widowed for each sex in each religion, and also the distribution of the total number of each sex in each age-period.

**Infirmities.**

Table No. XII shows the number of insane, blind, deaf-mutes and lepers in the district in each religion. The proportions per 10,000 of either sex for each of these infirmities are shown in the margin. Tables XIV to XVII of the Census Report for 1881 give further details of the age and religion of the infirm.

**European and Eurasian population.**

The figures given below show the composition of the Christian population and the respective numbers who returned their birth-place and their language as European. They are taken from Tables IIIA, IX and XI of the Census Report for 1881:—

Race of Christian population.	Details.		Males.	Females.	Proportion.
	Europeans and Americans	Eurasians			
Native Christians	—	—	1,289	288	4.52
Total Christians	—	—	1,289	288	4.52
					50
Language.	English	Other European Languages	1,282	284	1,000
		Total European Languages	1,282	284	1,000
Birth-place.	British Isles	Other European Countries	790	82	932
		Total European Countries	790	82	932

The Europeans shown in this return consist almost entirely of the British Infantry and Artillery at Ferozepore and of the officials of various departments. The number of troops is given in Chapter V.

## SECTION B.—SOCIAL AND RELIGIOUS LIFE.

In the towns of Petrozspore and Pashilka the houses of the trading classes are generally of burnt brick, two or three storeys high, and often ornamented with gaudy frescoes of historical or mythological scenes and personages. In these towns the well-built houses are numerous enough to form regular streets. In the smaller towns, however, houses and shops of brick are less general. The greater number of the buildings are of unburnt bricks and of one storey only. In the villages a brick house is an uncommon object, and is considered a sign of great wealth. The common dwellings are built of rough lumps of dry mud joined together and plastered over with wet mud. The roofs are of mud laid over beams and joists of roughly hewn timber. In the upland parts of the district, where the people are mostly Sikh Jats, the houses, though rough, are very commodious. The walls are 14 or more feet high, and there are sometimes small upper chambers on the roof. The house is entered by a gateway generally large enough to admit a loaded cart. This leads into a large apartment, which serves as a cart-lodge, tool-lodge, and stable, and also as a lodging for guests who are not sufficiently intimate to be taken into the interior of the house. This lodge is called the *deshki*. Its length is equal to the full width of the house, and its depth about 13 feet. It is difficult to get timber for a wide span, so that the buildings of the villagers are generally long and narrow. If additional width is required brick pillars are introduced to support the roof in the middle. The gateway is often built of brick and covered with stones and frescoes even when the rest of the house is of mud. Mud dwellings are, in fact, the coolest in the hot weather, and the mud stands so well in the dry climate of the uplands that nothing better is needed except for show. The Gil Jats of the Wadra section have a prejudice against *pakka* houses. On the further side of the *deshki*, but not exactly opposite the outer gateway, is a smaller door. This leads into an open court-yard called *rajpas*, round which are huts and cattle stalls. There will be a large hut of one or two rooms, a cattle standing, and a cooking-place for each married member of the family. The huts sometimes have a verandah in front of them. They are not generally very large inside, and are crowded with all sorts of household stuff. Being, moreover, lighted only from the doorway, they are not very inviting except as a refuge from bad weather, and the people prefer to do most of their work when they can in the open yard. Even the cooking, except during rain, is usually carried on in a partly enclosed and sheltered corner of the yard called a *sabit*. In the yard, and also inside the huts, are large barrel-shaped receptacles for grain, called *bharolas*, made of tenacious mud dried out in layers. The huts contain bins and cupboards of the same material, called *buthari* and *gehi*, in which are stored clothing, vessels, and every sort of stuff. The cattle fodder is heaped on the roof or stowed in chambers in the huts. When there is not sufficient room inside the village the remainder is stored in enclosures (*waras*), grounds, or stacked in the fields. At night, in the cold weather, as many of the cattle as possible

**Chapter III, B.**

Social and  
Religious Life.  
Habitations.

are housed in the huts or *deorhi*. The furniture consists of light bedsteads (*manji*) which serve as seats, and also for many of the purposes of a table when wanted, a few stools made of reed, a spinning-wheel for each woman and girl in the family, and the cooking and dairy utensils. The cooking vessels are of brass in a Hindu's house, and of tinned copper in a Musselman's. There is hardly any other visible difference between the dwellings of people of the two religions. The villages in the uplands consist of collections of houses of the above type closely huddled together into groups, divided by narrow and tortuous lanes. The lanes have only one or two openings (*phallā*) by which the village can be entered. The backs of the houses are generally blank walls, which together form a sort of outer wall to the village; but sometimes there are back doors opening into the fields. The village is surrounded by a path (*pheri*), beyond which, on one or more sides, is an open space in which cattle can stand, and where the women sit kneading the cattle dung into cakes for fuel and stacking them in pyramids for future use. There is generally a pond close by for watering the cattle, and on its banks will generally be found some large pipal trees. Most villages have a meeting place, used also as a guest house, known among the Hindus as *dharmashālā*, and among the Musselmen as *lāba*. This is often in the charge of a holy man, and in a Sikh village the *Guru* will generally be kept and read about there. Where the people are wealthy, they sometimes expend a large sum in building a handsome structure for their *dharmashālā*. A large upland village is usually divided into *tars* or *patti*s (quarters), which are again subdivided into *thalas* or sections, distinguished generally by the names of the founders. The houses are often so arranged that there is no means of passage from one *poti* to another except by going outside and entering by the other *phallā*. The divisions are then called *aywār*.

In the Muhammadan villages in the lowlands near the river the houses have generally no *deorhi*; the courtyard is enclosed only by a low wall, so that the inhabitants of one courtyard can see into the next one. The houses are much lower and smaller than in the uplands. The cattle are taken less care of, and are often kept in enclosures outside the village instead of being brought into the houses.

Within the belt of land that is subject to inundation from the river the villages are of a very poor and comfortless type. The mud walls are often replaced by walls of reeds, and the roofs are of thatch. Both men and cattle are insufficiently protected from the weather.

**Dress.**

The ordinary dress of men in the towns is of white cotton, and consists of a jacket (*kurta*), trousers or loin-cloth, and a large turban. In the cold weather the jacket is of woollen cloth or of padded cotton. The villagers wear a thick cotton wrapper (*khas*) folded somewhat like a plaid. This is coloured, and made of superior quality if the wearer is well-to-do. A poor man may not

be able to afford a *khes* at all, and wraps a blanket over his body and head. Trousers are seldom worn by the rustics. The Sikh breeches (*kash*) are almost confined to Nihangs, Bhais, Kukhs and the like.

Money and valuables are carried tied up in a corner of the wrapper, and an idiomatic Punjabi word for "rich" is "one who has a corner to his wrapper." The turban is generally white, but the better class of Sikhs wear an inner *pagri* of a different colour, and turbans of all colours, especially yellow, red and dark-blue are now common. Men of the trading classes sometimes wear small red or pink turbans such as are common among this class further south. Some other differences in the shape, material, or size of the turban may be noticed between different classes by an attentive observer.

**Chapter III, B.**  
Social and Religious Life.  
Dress.

The upper dress of the women is a loose jacket of coloured country cloth and a wrapper (*chaddar* or *chunni*) thrown over their heads to form a sort of hood. The wrapper is sometimes ornamented handsomely with coarse silk embroidery, and is then called *phulkari* or *clap*. The Bagri and Bishnoi women in the east of Faridkot make their *phulkaris* of wool. The Muslim women wear trousers generally of striped stuff of a dark blue or green colour, loose at the top being tight at the ankle. The Hindu Jat women when married wear the same style of trousers, with a petticoat generally of red or madder-brown stuff over the trousers. The young girls wear only the transverses. The old women often wear only the petticoat. All women without exception wear a wrapper over their heads.

Leather shoes are worn by all but the very poorest, but they are often discarded in order to use the feet with greater freedom. The shoes are of two patterns, either with the sole very narrow in the middle, or of the ordinary shape. This distinction is often of great service to trackers.

The food of the common people consists of barley, gram, sometimes wheat, *jowar*, *bajra*, moth, and *mungi*, and clotted milk. The general custom is to take thick cakes, which are eaten in the morning with *tassi*, and in the evening with *dil* (split gram) or *mungi*, or, more commonly, of gram and moth. In the cold weather a dish of boiled moth and *bajra* is substituted for the evening cakes. During the hot season Muhammadans get their bread baked at the common oven; but otherwise it is baked on a *girdia*. Where greens (*seig*) are to be had they often take the place of *dil*, and if a man is well-to-do he uses *dali* or clotted-milk twice a day; as, in the estimation of a Jat, there is no food comparable to it. Salt, chillies, and other condiments are also used. The following note regarding the food of the people was furnished by the district authorities for the Famine Report of 1879:—

\* The staple food-grains are wheat, barley, gram, *jowar*, *bajra*, and Indian corn. Wheat, barley, and gram are sown from the end of September to the end of November, and harvested from the 1st April to the middle of June; *jowar* & *bajra*, and Indian corn are sown from the 15th June to the end of July (*jowar* sometimes even in April and May, should rain

**Chapter III. B.**

Social and Religious Life.  
Food.

(fall in those months), and harvested from 15th October to 1st December. For the spring crops rain is required in April and September to moisten the ground for sowing them, and again in January and February to bring them on. The autumn crops require rain in July, August, and a little in September. Heavy rain is injurious to the farms in April and May, and to the latter in October and November; but unless it be prolonged, wet weather, no great harm is done. The average annual consumption of a family of five souls, including an old person and two children, is for agriculturists 1,225 acres, and for non-agriculturists 1,400 acres. Of the grains mentioned above, the grain eaten varies with the time of year, but wheat is most largely consumed."

Condition of women.

The women in this district are generally fine-looking, but few are handsome. Their part is to guide the house, and, though looked upon as drudges, they still have much influence, and a wife is a highly-prized possession. The standard of morality is, however, low, and the number of suits and criminal prosecutions arising out of love intrigues of a more or less guilty nature is very great. It is almost the universal custom for the parents of girls to receive at the time of betrothal considerable presents, proportioned to the rank of life of the parties. The betrothal takes place at a very early age, and the failure to fulfil such contracts at the appointed time is another frequent cause of litigation. The chief occupations of the women are to cook the food for their husbands and brothers, to take it out to them when at work in the fields, and to spin cotton. They also pick cotton and gather maize and millet heads, but do no harvest field work. The milch cattle are their especial care. They also sweep out the houses and yards every morning, and make the cattle dung into cakes for fuel.

Marriage customs.

It is usual, as already observed, to betroth children in very early life. The negotiation is conducted generally through the village barber or a Brahman or Mirasi. Betrothals and marriages are made the opportunity of feasting and prodigal expense. The ceremonies are performed for Moslems by the Kazi, and for Hindus and others by Brahmans, who read texts from the "Puranas." The Jats, here as well as in Lahore, adhere to the Levitical custom of *Kareesa*, in accordance with which a brother marries his brother's widow. The ceremony is called *chadar dilna*, or "throwing the sheet," and is completed by the man throwing his sheet over the woman's head. In Sikh times this custom used to be enforced even against the woman's consent; and it is to be feared that even now this is sometimes the case. In united communities it is often customary for a man's friends to contribute, each according to his means, towards the expenses of a marriage in his house, on the understanding that when they have the like need he shall contribute the same amount. Strict account is kept of these gifts, and the obligation to repay them when opportunity arises is held to be very stringent, so much so that suits have been brought to enforce it; but it has now been held by the Courts that the debt is not legally recoverable. This custom is called *wakhol*, or *nizenda*. A code of tribal customs observed by the agricultural classes has been prepared during the Settlement in 1859.

Table No. VII shows the numbers in each taluk and in the whole district who follow such religion, as ascertained in the census of 1881, and Table No. XLIII gives similar figures for towns.

Tables Nos. III, IIIA, IIIB of the report of that census give further details on the subject.

Religion	Rural population	Urban population	Total population
Hindus	8,400	4,600	12,000
Muslims	2,000	1,000	3,000
Christians	100	50	150
Mussulman Christians	1,400	4,200	5,600
Others and unclassified	—	50	50

In the classification of Hindus, are fully discussed in Part I, Chapter IV, of the Census Report.

caste	Rural population	Total population
Brahmins	100	100
Kshatriyas	90	90
Vaisyas	90	90
Others and unclassified	300	300

The distribution of every 1,000 of the Mussulman population by sect is shown in the margin. The sects of the Christian population are given in Table No. IIIA of the Census Report; but the figures are, for reasons explained in Part VII, Chapter IV, of the report, so very imperfect that it is not worth while to reproduce them here.

Table No. IX shows the religion of the major castes and tribes of the district, and therefore the distribution by caste of the great majority of the followers of each religion. A brief description of the great religions of the Punjab and of their principal sects will be found in Chapter IV, of the Census Report. The religious practice and belief of the district present no special peculiarities; and it would be out of place to enter here into any disquisition on the general question. The general distribution of religions by taluks can be gathered from the figures of Table No. VII.

The only great annual fair held in the district is that at Muktsar, in connection with which a horse and cattle show was formerly held. The Muktsar fair is held in the middle of January, as the *Makar Sankranti*,—when the sun enters the sign of Capricorn,—and is one of the great Sikh festivals. It lasts three days. On the second day the worshippers bathe in the Sacred Tank; on the third, they repair to the Holy Mount (*Tibbi Sahib*), where the warlike Guru Govind Singh stood and discharged his arrows against the Imperial forces; visits are also made to other holy places, the temple called, like that at Amritsar, the *Baber Sahib*, the *Shahid Ghar* or Martyr's Square, &c. The festival is in commemoration of a battle fought in 1705-6 by Guru Govind Singh, the tenth Sikh Guru, against the passing Imperial forces which overtook him at Muktsar, and cut his followers to pieces. The Guru himself escaped, and had the bodies of his followers buried with the usual rites. He declared that they had all obtained mukti,—the final emancipation of their souls from the ills of

### Chapter III, B.

#### Social and Religious Life.

General statistics and distribution of religion.

Religious gatherings.

**Chapter III. B.**

Social and Religious Life.  
Religious gatherings.

transmigration, that peaceful state which is the goal of the pious Hindu and Sikh alike,—and promised the same blessing to all his followers who should thereafter, on the anniversary of that day, bathe in the Holy Pool, which had been filled by rain from heaven in answer to his prayer for water. On this spot a fine tank was afterwards dug by Ranjit Singh, and called *Muktasar* (the pool of salvation), which was afterwards contracted into Mukatsar, from which the town subsequently built about the tank derives its name. The tank, commenced by Ranjit Singh, was continued by the Maharaja of Patiala, and is now being gradually completed by the British Government. It is bricked all round. Near the temple (Darbar Sahib), which is on the western side, the steps of the tank are adorned by some fine pipal trees. The tank is now usually filled with canal water, and is 606 feet long by 601 broad. The annual attendance at the fair may be estimated at about 50,000 souls. Besides the tank, the other shrines of Mukatsar are, as stated above, the Holy Mound, the Holy Darbar, and Holy Tent, which latter are close together on the western side of the tank. Near the Holy Mound is a second and smaller one, which has been gradually heaped up by handfuls of earth brought from the bottom of the Sacred Tank and thrown on it by the pilgrims, as stones are cast upon emirs in other lands. Another yearly fair, of much smaller dimensions, is held at Dandama, where Guru Govind halted in his flight from Bhindu before the battle of Mukatsar. *Dandama* means a bastion or platform. Several such places used as places of refuge during the Muhammadan persecutions are venerated by the Sikhs.

There is a fair also held in March at Nathiana in honour of a Hindu saint named Kali, reputed founder of the village, who is said to have excavated a large pond with one scoop of his hand, and deposited the earth taken out in a heap close by, where it forms an object of popular veneration. On the second day of the fair, those who attend it go over to bathe in the sacred pond at Ganga, one mile off. As many as 20,000 people gather to the fair annually. Another important gathering is that at the fair and bazaar held yearly in January since 1880 at Jallianwala, the chief town of the Mandot Jagir. There are other local fairs of inferior interest held at Mari, Dhurukot, and other places throughout the district, which are not deserving of more particular mention.

**Ferozepore Mission.**

The following account of the Ferozepore Mission in 1883 was kindly supplied by the Rev. F. J. Newton, the Missionary in charge :

"The Mission at Ferozepore is connected with the American Presbyterian Church, and is a branch of the Laijipura Mission, which is the technical name by which our Mission in the Punjab is known. Ferozepore was occupied by the American Missionaries of Lahore in 1870, and for the ten years following was conducted by native ordained ministers. Since my arrival in the beginning of 1881, one of the main features of the Mission here has been medical work. Patients have been treated during the summer months in a dispensary rented and fitted up for the purpose in the city, as well as in private houses; and during the winter in the villages, either at my own tent, when I am at tour, or in a house leased for the

purpose in a village. Combined with this there has been the usual systematic preaching and teaching. In 1881 I conducted a school for the Muslim children, but was obliged in a few months to abandon it, the people showing no ambition to have their children educated. Of late I have been joined by Dr. C. W. Forman, junior, who has taken charge of the dispensary. With him I still continue to treat patients both here and in their own houses. We find this a decided aid to us in securing a more ready acceptance with the people than we should otherwise obtain. We have working with us two catechists and a soroptimist. Mrs. Newton also frequently visits the zemams of the city, reading the Bible to the women, or teaching them to read. The number of conversions since the Mission was founded has been small. Two or three persons of high rank a few of low caste have made a profession of Christianity and have now for a number of years lived consistently as Christians. We must consider the results of our Mission hitherto as only general and preparatory."

It may now be added that a good Mission Church has recently been built on the Knox Road. The congregation consists of 57 persons. There is a native pastor and 3 catechists. A dispensary building has been erected by subscriptions, and from 60 to 80 outpatients are treated daily. The missionaries state that they believe Christianity to have taken deep root in the city.

Table No. VIII shows the numbers who speak each of the principal languages current in the district separately for each taluk and for the whole district. More detailed information will be found in Chapter V of the Census Report for 1881, while in

### Chapter III, B.

Social and  
Religious Life.  
Ferozepore Mis-  
sion.

Language.	Proportion per 10,000 of population.
Brahmanical	228
Urdu	1
Punjabi	1,223
Pashai	4
All Indian Languages	8,527
All Non-Indian Languages	23

Language.

the several languages are briefly discussed. The figures in the margin give the distribution of every 10,000 of the population by language, omitting small figures.

The vernacular language of the district is the ordinary Punjabi; but, owing to the influence of schools and courts of law, a marked change in the vocabulary of the people has taken place in the last 20 years, Punjabi being gradually thrust out by Urdu. Mr. Johnstone, for some time Assistant Commissioner in the district, writes: "There can be little doubt that unless some organized efforts be soon made to investigate the Punjabi dialect, the opportunity for doing so in this district will be lost." But this is an exaggerated view of the extent to which the change is likely to proceed.

Table No. XIII gives statistics of education as ascertained

Education.

Religion.	Native popula- tion.	Total popula- tion.
Untouchables	48	94
Can read and write	328	361
Untouchables	22	43
Can read and write	24	109

at the census of 1881 for each religion and for the total population of each taluk. The figures for female education are probably very imperfect indeed. The figures in the margin show the number educated among

**Chapter III. B****Social and Religious Life.**  
**Education.**

per mil.	Boys.	Girls.
Protestants and Romanists	—	—
Native Christians	—	—
Brahmins	17.6	27
Moslems	10.7	41
Parsis	1.7	2
Others	2	—
Children of agriculturalists or non-agriculturalists	1,700	22
Others	1,600	21
	Per mil.	Boys.
Ardhi	2	26
Panchari	—	18
Potwari	21	100
Bhole	3	100
Gurmukhi	40	74
Total	64	74

others have small rent-free grants of land. It must be confessed, however, that the number of youths under instruction is small when compared with the number of the population.

**Character and disposition of the people.**

Tables Nos. XL, XLI, and XI.II give statistics of crime; while Table No. XXXV shows the consumption of liquors and narcotic stimulants. The prevailing crime of the district is that of cattle-lifting. Murders are not frequent, being seldom committed except as a consequence of conjugal infidelity. The most common offences are housebreaking and theft. Cattle-theft is especially prevalent among the Dogras and other tribes who live along the river, and in the Mahrat territory, where the facility of escape into foreign States offers an apparently irresistible temptation. This district is notorious also for the number of complaints of abduction of married women, but the great mass of these do not come to trial, the complainant being usually quite satisfied at getting his wife back, and caring little about the punishment of the offender.

**Poverty or wealth of the people.**

It is impossible to form any satisfactory estimate of the wealth of the commercial and industrial classes.

ASSESSMENT.	1875-76.	1876-77.	1877-78.
Class I.—Number taxed—	—	46	267
Amount of tax—	1,037	1,038	2,419
Class II.—Number taxed—	29	39	100
Amount of tax—	1,070	2,000	1,672
Class III.—Number taxed—	24	62	62
Amount of tax—	2,476	3,166	1,268
Class IV.—Number taxed—	226	226	22
Amount of tax—	1,012	6,031	373
Class V.—Number taxed—	—	216	—
Amount of tax—	—	16,001	—
Total.—Number taxed—	—	1,092	422
Amount of tax—	11,867	28,395	6,712

The figures in the margin show the working of the income tax for the only three years for which details are available; and

Table No. XXXIV gives statistics for the license tax for each year since its imposition. In 1872-73 there were 179 persons brought under the operation of the Income Tax Act as enjoying an income in excess of Rs. 750. In the preceding year, all incomes above Rs. 500 being liable, there were 404 persons taxed. Of these, four only were bankers and money-dealers, 86 were general merchants, five dealers in piece-goods, and 13 dealers in grain. Of landed proprietors, 104 persons paid Rs. 1,427. But the numbers affected by these taxes are small. The Jat zamindars carry on the grain trade on their own account, taking the grain away with their own carts and bullocks, hence there are few wealthy traders in the district liable to be taxed. The distribution

	1880-81.		1881-82.	
	Towns.		Villages.	
	Number of Licences.	Amount of Tax.	Number of Licences.	Amount of Tax.
Number of Licences.	211	Rs. 747	242	Rs. 1,010
Amount of Tax.			229	Rs. 1,100
			301	Rs. 2,000

of licences granted and fees collected in 1880-81 and 1881-82 between towns of over, and villages of under, 5,000 souls, is shown in the margin.

The results of the license tax for the year 1882-83 to 1885-86 and of the new income tax for the years 1886-87 to 1888-89 are shown in Statement No. XXXIV A. It may be said generally that a very large proportion of the artisans in the towns are extremely poor, while their fellows in the villages are scarcely less dependent upon the nature of the harvest than are the agriculturists themselves, their fees generally taking the form of a fixed share of the produce; while even where this is not the case the demand for their products necessarily varies with the prosperity of their customers. Perhaps the leather-workers should be excepted, as they derive considerable gains from the hides of the cattle which die in a year of drought. The circumstances of the agricultural classes are discussed at pages 83, 84.

## Chapter III. B.

## Social and Religious Life.

## Poverty or wealth of the people.

## SECTION C.—TRIBES, CASTES, AND LEADING FAMILIES.

## Chapter III, C.

Tribes, Castes  
and Leading  
Families.

Statistics and local  
distribution of tribes  
and castes.

Table No. IX gives the figures for the principal castes and tribes of the district, with details of sex and religion, while Table No. IXA shows the number of the less important castes. It would be out of place to attempt a description of each. Many of them are found all over the Punjab, and most of them in many other districts, and their representatives in Ferozepore are distinguished by no local peculiarities. Some of the leading tribes, and especially those who are important as landowners, or by position and influence, are chiefly noticed in the following section; and each caste will be found described in Chapter VI of the Census Report for 1851.

The census statistics of caste were not compiled for tahsils, at least in their final form. It was found that an enormous number of mere claim or subdivisions had been returned as castes in the schedules, and the classification of these figures under the main heads shown in the caste tables was made for districts only. Thus no statistics showing the local distribution of the tribes and castes are available. But the following figures show the general distribution of the agricultural tribes as ascertained by Mr. Brandreth in 1855:—

*Classification of Tribes (Settlement Census, 1855).*

Name of Caste.	LOCALITY.			
	Bal.	Bal.	Outlying Districts	Total.
Hindus.				
Jat	2,000	74,327	29,793	100,020
Kanthal	442	—	—	442
Bew, Bhatia, Bakkal	4,447	3,758	4,307	10,502
Tirkan and Lohar	466	—	1,543	10,000
Mishtianwala	3,220	10,303	13,000	21,523
Total	31,862	100,000	40,700	180,562
Muslims.				
Jat	6,400	2,107	1,421	10,128
Bairas or Arain	10,000	2,726	600	13,326
Gujar	4,463	2,122	68	7,014
Dowar	2,000	1,000	744	7,744
Bhatti Rajput	6,000	2,000	2,001	10,001
Kamboh	2,112	1,177	—	3,397
Mardhi	2,700	1,074	423	4,197
Panch, Mawal, Pachan	2,000	1,704	224	4,928
Tirkan, Lohar	2,000	1,741	224	5,945
Kumhar	2,100	1,200	206	3,506
Zalana	2,000	1,000	2,000	5,000
Unchianwala	22,000	24,400	6,000	52,400
Total	77,369	30,279	10,048	120,696
Total Hindus and Muslims	100,241	100,279	40,700	241,220

The following figures show some of the principal Jat and Rajput tribes as returned at the census of 1891:—

## Chapter III. C

Tribes, Castes  
and Leading  
Families.Jat and Rajput  
tribes.

## Subdivision of Jats.

Name.	Number.	Name.	Number.	Name.	Number.
Anan	1,222	Asht	—	Bilha	—
Dale	4,222	Bher	—	Birra	—
Bhatti	2,022	Naibat	—	Bote	2,422
Batra	2,002	Mati	—	Bura	2,108
Bhatia	2,007	Majhi	—	Devrai	716
Bomar	1,101	Mohammed	—	Dewar	2,763
Pannar	800	Nawali	—	Dharia	2,022
Chahal	1,711	Mazhar Mulla	—	Vatta	702
Chahal	1,482	Chana	—	Gill	20,102
Ber	1,002	Khatri	—	Chauhan	1,442
Bikaner	2,002	Khalid	—	Meo	2,477
Bur	2,177	Makhdum	—	Virk	1,262
Sawar	2,002	Momin	—	Saxarai	962
Shergi	4,102				

Note.—Of the Beris, 20,102 were shown. Distinguish as follows:—of the Beris 20,102 as Chauhan, Bikaner and Meo; below only sections of the Chauhan. Other smaller numbers also are similarly shown twice over.

Some other well-known clans of Jats are as follows:—

Rungari.	Sirhi.	Bedheba.	Sial.
Malhi.	Kaler.	Jatama.	Dela.
Kloss.	Deval.	Kang.	Minjai.
Bat.	Jumhal	Vains.	Namiri.
Kortana.	Bath.	Kingers.	Aser.
Khalra.	Sokhon.	Hinjan.	Vijjoker.

## Subdivision of Rajputs.

Name.	Number.	Name.	Number.	Name.	Number.
Bhatti	1,002	Bhati	—	Tomal	—
Pawar	2,002	Kachar	—	Vira	—
Dewar	2,002	Mohani	—	Shera	—
Joshi	2,122	Musliman	—	Lewa	—
Chauhan	2,002		477		822

Note.—Of the Rajput, 1,002 are shown as Bhatti also, and other smaller numbers also similarly shown twice over.

Some other clans are Mahär, Variab, Ráwati, Bal.

A strong contrast exists between the inhabitants of the low-  
lands near the riverside, known as the *Bat*, and those of the  
upland plains. "The cultivators of the *Bat*," writes Mr.  
Brandreth, "are almost all Muhammadans; out of a total  
population of 58,022, 48,510 are Muhammadans and only 4,512  
Hindus. The Muhammadans number, therefore, 90 per cent.  
Of the whole agricultural population, the principal castes are the  
Dogras, Bhattis (Naipals), Gujars, Raiens, and Musalmán Jats.  
Very little can be said for their skill as cultivators. The  
Raiens, and some of the Musalmán Jats, are indeed glorious  
exceptions; but the other castes are very far inferior to the  
stout Hindu Jats, who form the staple of the agricultural com-

Agricultural tribes  
of the Bat.

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.**

**Agricultural tribes  
of the *Bet*.**

munity in the *Rohi*. They are utterly devoid of energy, and are the most apathetic, unsatisfactory race of people I ever had anything to do with. They will exert themselves occasionally to go on a cattle-stealing expedition, or to plunder some of the quiet, well-conducted Raions, who live in constant fear of their marauding neighbours ; but their exertions are seldom directed to any better end. They take not the slightest pride or interest in any agricultural pursuit ; their fields are cultivated in the most slovenly manner : you see none of the neatly-kept houses, well-fenced fields, fat bullocks, and walls kept in good repair, which distinguish the industrious castes. The hovels in which they live are generally half in ruins ; no fences ever protect their fields ; their cattle are half starved, and their wells often in the most dilapidated condition ; notwithstanding the quantity of waste land in every direction, they will not, if they can possibly pay their revenue without it, bring a single additional acre of land into cultivation."

The oldest proprietary classes are the Gujars, Naipals, and Dogars. The Dogars occupy the western and the Gujars the eastern portion of the *Bet*, the intermediate portion being the country of the Naipals.


**Gujars.**

The Gujars were the first settlers in the *Bet*. They state that they were originally Puár Rájputs, and came from Dharm-Nágari in the south of India, the exact locality of which is unknown : that first they migrated to Rania in Sirsa, and thence to Kasár. From hence, about A.D. 1800, they moved to the neighbourhood of Makhu, but being driven out from there by the Naipals, who crossed over from Kasár some years later, they finally settled down about Dharmkot, where they are now found. They are divided into two *got*s or clans, the Chár and the Kathána. Originally rather a pastoral than an agricultural race, the Gujars are unwilling cultivators, and much addicted to theft, especially of cattle. Mr. Brandreth says that they were such determined thieves in his time that he was unable to check their depredations in the town of Dharmkot, except by appointing one of their number to be sole watchman. On condition of his receiving all the watchman's dues, he agreed to prevent crimes or to make good the value of the property stolen. At an earlier period the same policy had been followed on the Jallundur side to the length of making a Gujar of Jindra, in this district, Thánadar or Police Officer of Shahkot. At the present time the Gujars have not such a monopoly of the crime of the neighbourhood. Though Musalmáns, they preserve relics of a Hindu origin in many of their customs. Marriages are not contracted between parties belonging to the same *got* or subdivision of the tribe ; and the custom of *kura* prevails. Brahmin *purohit*s also take part in their social and religious ceremonials.

**Manj Rájputs.**

The Manj Rájputs, though not a numerous tribe, were of much importance in the early history of the district ; and the connection between some of the other tribes will be seen from

the pedigree of the Manj Chiefs. It is therefore given below as declared by their hereditary *bhatia*, or heralds :—



## Chapter III, C.

Traces, Castes  
and Leading  
Families.

Manj Rajput.

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.**  
Naip Rajpūts.

According to the Hissar tradition mentioned in para. 448 of Mr. Ibbetson's Census Report, Jaisal was the son of Bhatti, the eponymous hero of the Bhatti tribe, and he had a brother named Dosal, from whom are descended both the great tribe of Barāt Jatis and the Wattis of the Lower Sutlej, as well as various families who are known simply as Bhattis. According to the Sirsa tradition, these tribes are descended from Batern, son of Junhar. But Junhar is made to be a descendant of Salvahan (no doubt the great legendary Rāja of that name, the father of Rāja Rāsālu). Jagpal is called Juipal, and Aclal is said to have had another son named Rājpāl or Rachipal, who was the ancestor of the Wattis.

In the Patiala pedigree given at page 9 of Sir Lepel Griffin's *Rājās of the Panjab*, Salvahan is shown as an elder brother of Rāi Hem or He, then called Hemhel, Jhundar is called Jandra.

All that can be confidently inferred as to the older part of the ancestry of these tribes is that they are believed to have had a common origin in the Bhatti tribe of Rajputs within the period of modern history. The tribe of Naipals is said to have been descended from Rāna Ilmī's son of that name, and the Dogars from Laura, another of his sons.

Sir Lepel Griffin relates of Rāi He (Hemhel) that he sacked Hissar, and overran the country up to the walls of Delhi, but was afterwards taken into favour and made Governor of the Sirsa and Bhatinda country in A. D. 1212. The Manj traditions of this district, however, say that he lived at the villages of Pakurpur and Tehri in the south of Muktsar, and that these villages were at that time named Meshalgarh and Ladhwā. Junhar is said to have ruled at Bhatner. Mohalsi transferred his residence to Miskalliar, now Faridkot, and this was the joint capital of both Jairas and Vairas until Rāo Bhāro left it for Bīaspur, and afterwards founded Hafūr. Khilcha and Tuli Rām were the first of their families to become Muhammadans. The latter took the name of Sheikh Chicho. Of Khilcha's brothers two followed his example, but four remained Hindus. One of the latter was Rutsi, whose descendants founded the village of Ratiān in Moga, almost the only village of Hindu Rajpūts in this district. Rāi Shādi Khan founded the village of Shādiwal in Zira. His son, Not Ahmad Khan, the story is told, went to Delhi, and there strung a bow (which had been presented to the Emperor by the King of Persia), a feat which no other member of the Court had been able to perform, in consequence of which he obtained great favour in the sight of the Delhi Emperor and received the title of Nawāb. Rāi Mansur Khan would seem to be the person mentioned as Mansur Bhatti in the Sidhu story as the antagonist of their ancestor Bhullan, for his granddaughter, the daughter of Nasir, was one of the many wives of the Emperor Akbar. But the pedigree would make Rāi Mansur Khan much older than Bhullan. There may therefore have been another Mansur Bhatti, or the legends may have got mixed. Mansur's descendants live at Talwandī Naubahār. Shahzād settled

at Mahi and Alam, at Talwandi Jalla Khan and Talwandi Mângó Khan. All these places are on the old bank of the river between Zirw and Dharmkot. Darin Khan founded Kot Naurung Khan, now called Masitán, in the reign of Shahjahan, and the descendants of Fath Muhammad founded Kot Sudar Khan. Daulat Khan ruled on behalf of the Emperor over the Mukatsar and Kot-Kapura country. He founded Daulatpura in the Moga Tahsil and Iamwaliáns on the *Sukkar*. His son Ise Khan built the town which is named after him, and brought the power of the Jairéh Manj family to its greatest height. He is represented as having had more than a local reputation, and it is said that he once led an imperial army to Hyderabad in Sindh. During his time Kapura, the Buriá Chist, revolted. Ise Khan, having induced him to come in, treacherously murdered him. In A.D. 1740 the crumbling state of the Moghal Empire encouraged Ise Khan himself to assume independence. He was for a time successful, but was at last subdued by a large force sent against him under the command of Shahzâd Khan. Ise Khan is said to have displayed great valour and to have had a fierce personal encounter with the leader of the opposite force, both mounted on elephants. At length Ise Khan was killed by a chance arrow-shot by his own brother-in-law Umar Khan. This encounter has given rise to a saying, "Ise Khan mārān, Shahzâd jhullâan ki kare Ise Khan poban walián"—meaning that all Ise Khan's blows were parried by Shahzâd Khan, and that his efforts were unavailing against the overwhelming force of the latter. The saying is applied to any unsuccessful undertaking on which great efforts have been wasted. Muso Khan, the son of Ise Khan, was allowed to succeed him after making proper submission, but their family speedily declined. Kâdir Baksh Khan was the last Nawab. He was overpowered by the Sikhs under Târa Singh Gheba and lost nearly all his possessions. The Ahîwâliás shared the riverside villages with Târa Singh, and Mohî Singh, Nishânwâla, took possession of Zirw. The family have now nothing left but one hundred acres of land in Kot Ise Khan. Samand Khan has now been made Zâldâr.

Of the Vairai branch, the first Chiefs of importance were Dâid Khan, who founded Daudhar in the east of the Moga Tahsil, and Feruz Khan, who is said to have built Ferozepore itself. Rao Manj II. and Issat Khan founded Rheetot, which remained their capital as long as they had any political power. Mânakdeo's descendants settled in Kariá, Ferozwâl, Pindori Arain, Bhikam, and Jalalabad. Kariá was built by Rai Issat, and Ferozwâl by Feruz Khan II. Jslâi Khan founded Jâlalabad in 1606 A.D. This is now the principal seat of the family in this district. Ghulâm Nahî Khan of this place has now been made Zâldâr. He possesses a samad given them by the Emperor Shahjahan, affirming the authority of his ancestors over about forty villages in the neighbourhood. The Rheetot branch declined more and more, and their jagirs are now extinct. Kutb Khan founded Kathpura, which is now the town of Dharmkot. Fateh Khan founded Râoli in Moga.

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.**

**Manj Rājpūts.**

**Naipals.**

**The Dogars.**

The Manj hold the whole or parts of only about eight villages, all in the south-east of the Ziru Tahsil. They are well-conducted people, and show little of the misplaced pride and affection so common among the representatives of great families which have fallen into decay. But they are not very good managers of their property, and cannot compete with the Sikh Jats who surround them.

Naipal, the ancestor of this tribe, was one of the numerous sons of Rāma Bhuti (see the Manj pedigree, page 53 *ante*). The Naipals migrated from Sirsa to Pākpatan, thence to Kasur, and from Kasur, with the assistance of Kārdar Adina Beg, to Ferozepore. At the time of their arrival in this district they were still Hindus. Their leaders were Sawand and Saaspāl, sons of Naipal. The descendants of Sawand are now settled to the west of Makha, and the descendants of Saaspāl to the east. At one time they were spread all over the country from Makha westward to Ferozepore, but they were driven eastward by the Dogars and displacing the Gujars, took up their present location. Under the rule of the Ahluwalia Rāja they were virtually independent, and only paid a small revenue in kind occasionally, when the Kārdar happened to be strong enough to enforce it. They are but poor agriculturists and notorious thieves. Marriage within the clan is not prohibited among the Naipals.

The history of the Dogars has been given in Chapter II. Their own account of themselves is that they are Chauhan and Panwar Rājpūts, who migrated from Delhi to the neighbourhood of Pākpatan, spread thence along the banks of the Sutlej, and so entered the Ferozepore District about 1750. They are probably, however, a section of the great Bhatti tribe and closely connected with the Naipals. The Manj traditions say that the Dogars are descended from Lumra, who, like Naipal, was one of the twenty-four sons of Rāma Bhuti. They thrust the Wattūs aside to the west and the Naipals to the east, and they now occupy the riverside almost exclusively from about twenty miles above Ferozepore to an equal distance below it. From their habit of assuming the position of superior proprietors rather than actual cultivators of the soil, and their fondness for distinguishing themselves by the name of *Sardars*, it seems likely that they subjugated instead of ejecting the inferior tribes, Māchhis, Mallahs, &c., of the riverside. The Dogars about Ferozepore are descendants of Mahu. Mahu had two sons, Bahirol and Sahirol. The descendants of the latter live on the Kasur side. From Bahirol proceed four sections, Khanaki, Phaimaki, Ullaki and Kandarki. The Khanaki branch are found about Arif and Mallānwala; the Phaimaki branch hold Khai and its neighbourhood; the Ullakis extend for some six miles below Ferozepore; and the Kandarkis are mostly to be found in Mamdot. Other sections, mostly located in Mamdot, are the Mattar, the Chini, the Rupal, the Dhandi, the Chopra, and the Khamme. The Phaimaki Dogars of Khai are superior to the other sections and will not give their daughters in marriage to those whom they consider inferior branches. Infanticide was formerly common amongst them, but has now ceased to be practised. Sir H. Lawrence has

Sir H. Lawrence has described the Dogars as "tall, handsome, and sinewy, with large aquiline noses; fanciful, violent, and tenacious of what they consider their rights, yet susceptible to kindness, and not wanting in courage."

To this Mr. Brandreth adds:—"The Jewish race which is found among the Dogars, and in which they resemble the Afghans, is very remarkable, and makes it probable that there is very little Christian blood in their veins, notwithstanding the fondness with which they attempt to trace their connection with that ancient family of the Rājputā. Like the Gujars and Naipals, they are great thieves, and prefer pasturing cattle to cultivating. Their favourite crime is cattle-stealing. There are, however, some respectable persons among them, especially in the Perazepore *haka*. It is only within the last few years that the principal Dogurs have begun to wear any covering for the head. Formerly the whole population, as is the case with the poorer classes still, wore their long hair over their shoulders, without any covering either of sheet or turban. Notwithstanding the difference of physiognomy, the Dogurs preserve evident traces of some connection with the Hindus in most of their family customs, in which they resemble the Hindus much more than the orthodox Mithamadans."

The state of anarchy or of divided rule under which the Dogurs lived for nearly a century has no doubt done much to retard their reclamation, and they had a bad start on the road towards an industrial state of existence, and will always be behind their neighbours. But they seem to be trying to improve. They devote more time to agriculture and less to cattle-lifting, and are becoming ashamed of the reputation in the latter line which they were formerly proud of. They are, however, still feeble-minded, vain, careless, thriftless, very self-indulgent, and incapable of steady effort. Most of the principal landowners of this tribe are heavily indebted. Their habit of allowing their ponies and cattle to stray about the fields, and of treating their tenants as menials, deters the better class of tenants from taking land in their villages. Sooner than till the land themselves they will take a lower rate of rent than other tribes would obtain for similar land. They seldom leave their own villages, and know almost nothing of what is going on elsewhere. They have a dislike to any garments, whether jacket or trousers, which confine their limbs, and much prefer a costume consisting of one wrapper tied as a skirt round their waists, and another thrown across their shoulders. Their houses are always of the poorest and untidiest description, and their cattle small and miseraile. But they must keep a pony to ride, even if they have hardly a bullock to plough with. They take pride in their lacquered bed-stands and their elaborate *antkis*, and these two articles they never leave for a longer time than is unavoidable.

One peculiarity which may be classed either as a vice or as a weakness is that they are unapt at fabricating false evidence for the Courts.

Chapter III, C  
Tribes, Castes  
and Leading  
Families.  
The Dogars.

**Chapter III. C.****Tribes, Castes  
and Leading  
Families.****The Dogars.**

In the upland tracts there are a few villages of Dogars, to whom little of the above description applies. These come from a different stock, connected with the Dogars of Tihār. They are almost as industrious and as prosperous as the Jats by whom they are surrounded. This difference must be mainly attributable to the influence of the good and unfailing soil to which they have been transplanted, which rewards every effort at cultivation, but offers no temptation to an irregular pastoral life. The Dogars in the Mukatār Hīthār and also in the canal-irrigated parts of Māmīt are much more thriving than those on the riverside near Ferozepore. In the west of Zīrā, again, there are some Dogar communities who are well off. On the whole, the condition of the tribe in various situations is a good example of the influence of locality in modifying hereditary traits.

**Arains.**

The Arains of this district appear to be all recent immigrants. Those of the Zīrā came over from Jullundur, and those of Ferozepore and Māmīt from Lahore. They have been described in the Jullundur Settlement Report. In this district they have always been in a position of subjection to one or other of the stronger-handed tribes. None of them have ever been *Sardars*, but merely peaceable cultivators. They have usually got some of the best land of the neighbourhood, but their holdings were small to begin with, and they had no surpluses waste lands; so that with the growth of population the average property of each household has got less and less, and is now frequently insufficient to provide them with full means of subsistence. Formerly they were distinguished by frugality and unassuming manners. An Arain's wedding could always be celebrated, it was said, at a cost of Rs. 16. But since the money value of land has risen so much higher than it used to be, some of them have been tempted to borrow money upon their holdings and to spend it extravagantly. They are more indebted than such industrious and skilful husbandmen would be expected to be, and frequently have to make over to their creditors at each harvest a larger proportion of their crop than would be exacted from a tenant-at-will by his landlord. This is particularly the case in the neighbourhood of Dharmkot and near the city of Ferozepore. The Arain, though a good cultivator, is not a shrewd financier, and the women are not to be compared with the Jat housewives for economical management of their resources. Arains are somewhat quarrelsome and apt to dispute about trifles. They increase their difficulties by want of union amongst themselves. Two Arain brothers are frequently found to have started separate wells only a few yards apart, being unable to work the smallest joint holding in harmony. Some members of the tribe who have large properties are now rising to a higher social position than they have hitherto occupied, and two or three have even made *sardars*. Their principal clans are Mānd, Chander, Nāi, Narain, Mullān, Dīlī, and Lālu.

**The Sidhs.**

The Sidhī tribe is the largest of all the sections of the Jats. It occupies the entire west and south of Moga, the Mahraj villages, the greater part of southern Mukatār, and numerous villages in

the sandy tracts of Perozepore and Zira Talukas. Sidhu was the fourth in descent from Barera, whose name has been shown in the Manj genealogy. He had four sons, one of whom, named Bir, was the ancestor of the Barārā. Barerā was eighth in descent from Bir.

It is unnecessary to repeat the whole pedigree, which is given in Sir L. Griffin's *Punjāk Rājās* in the histories of Patialā and of Faridkot. It is sufficient to say that Barārā had two sons, Paor and Dhad, besides three others who became Mussulmans. From Paor were descended the Mahrājikān families. The great-grandson of Mahrāj was Mohan. Mohan with his sons and grandsons came into this district about 1580 A. D., and settled at Mahrāj, a tract to the south of Moga, calling the village by the name of their ancestor. The family of Mohan was as follows :—

MOHAN.



They increased rapidly, and their village threw out offshoots until 22 villages (called the Bālyā, from Bālā = 22) were formed. Phal separated himself off and founded the village of Phal. The ruling families of Patialā, Nāthā and Jind, as well as the Sardars of Bhīdāur and Māhabāl, are descended from Phal, and are hence known as Phalikān families. The remainder of Mohan's posterity are simple cultivators, but, owing to their being so nearly related to the great Gia-Singh Rājās, they came under the exclusive dominion of some of them. Some time before the first Sikh war they agreed to put themselves under British rule, and were allowed to hold their land revenue free in perpetuity.

From Sidhu's son Bir are descended the Kāthāl, Arnauli, Jhambā and Sallīnwāl families. Several villages of Barārā of this branch who style themselves Bhāis, on account of one of their ancestors having been attached to the service of the Sikh Guru, are settled in other villages of the Mahrāj Pargana, known as the Bhāichāo villages. The Bhāi of Arnauli holds six of these villages in pājīt.

The greater part of the Sidhuā outside the Mahrāj Pargana are descendants of Sangar. When they came into this district they seem to have been a wild semi-savage people, living on the spontaneous produce of the jungle and on the milk of their herds, and hardly knowing how to make bread. It seems probable from various indications that the whole of the tribe were not of the same descent, but that a nucleus of leading families had associated with themselves members of jungle tribes not differing very widely from the Bāndās of the present day. These all took to calling themselves Sallīds or Barārā.

Chapter III. C.  
Tribes, Castes and Leading Families.  
The BARRS.


The Barras have always been distinguished for a rough and turbulent temperament, and since their tribe has risen to fame they have naturally added a good deal of pride. They are excessively fond of stating how nearly they are connected by blood with the Rājs and Mahrājs, and they keep up a close connection with the Courts of the Native States. On occasions of great ceremonies the principal Barras of our villages are invited to attend. They present gifts and are given presents in return. The hoir of every Pukhāna monarchy makes it a religious duty to visit Mahrāj at least once in his life, and to perform the function of digging some earth from the pond there known as the Tikkāra. On these occasions liberal largesse is given to the villagers.

The houses of the Barras, though large, are rougher and less tidy than those of the other castes, another indication of their being a wilder people than the rest.

The Barras were formerly addicted to the practice of female infanticide, and in Mahrāj this practice was only given up in the year 1836 through the exertions of Mr. Kirk, the Political Agent of the British Government. They used to have a bad name for cattle stealing and dacoity, and are still somewhat prone to violent crime. Under the rule of the Kol-Kapura Chief they paid only a nominal rate of land revenues, and, owing to the dimilie of our Government to sudden and large enhancement, they are still somewhat under-assessed. The Mahrāj people are greatly addicted to opium; without the aid of this drug they profess themselves unable to get in their harvest. The ill-effects of this habit are not immediate, but it leads to dullness, want of enterprise, carelessness of appearance, and in general weakens the character. The Mahrāj people will not leave their houses. They are extravagant and fond of gambling. Hence, though they have no revenue to pay, debt is more common amongst them than elsewhere in the Moga Taluk.

The following is a sort of pedigree of the principal Barrar communities in the Moga Taluk, showing which were the mother villages and how the offshoots spread and multiplied:—

PARKHĀRAH-JALĀN (OR PARSHAD).



The Barārs generally call themselves Sidhu-Barārs, having rather a preference for the name of Sidhu over that of Barār. In Mukāsar those Barārs who trace their descent to Sangar, often distinguish themselves as Sangars.

There are twenty-four sections or mukhias of Sidhus, which are named as follows:—

Rathnia, Khilris, Mahramia, Darāko, Mahrajke, Hati, Bhali, Hariko, Bandhito, Bhakun, Jaid, Barār, Pakhake, Sarā, Manke, Khokarke, Ugarka, salikas, Arunke, Achal, Aspal, and one or two others. After the Barār and Mahrajke sections, the most important of these are the Jai, Sarā, Mahramia, Darāko, and Hariko. The Sarā intermarry with the other mukhias, showing that the got is practically too large and is beginning to subdivide. This process will probably go further in time, for the Sidhus occupy so large an area of the Cis-Sutlej country that, if they rigorously regarded the whole tribe as a single got, some of them would hardly be able to find a wife within a day's journey of their houses.

The Gils are the only important section of the Jats here who do not trace their origin to a Bhatti stock. They say they come from a Rāja of the Variab clan of Rājpūts who ruled at Gathmāthal. It is not clear where this place was. The name Gil is explained by a story to the effect that the Rāja had no children by his Rājpūti wives, and therefore married a Jat woman. She bore a son, but the other wives, moved by jealousy, exposed it in a marshy spot in the jungle. The infant was accidentally found by the king's minister and called Gil, from the place where he was found, *gil* meaning moisture. Another version is given at page 382 of Sir L. Griffin's *Punjab Chiefs*, according to which the child who was exposed was the son of Gil, and he was found being licked and founfed by a tiger (*shay*), whence he received the name of Shor Gil. The Shor Gil are one section of the Gils. Other large sections are the Wadian Gils and Varri Gils. There are twelve sections altogether. The Wadian Gils say that one of their ancestors was Rāja Biminiyal, who built the fort of Bhatinial.

The Wadian Gils were settled about the beginning of the seventeenth century in the south and west of Moga, the tract now occupied by the Barārs. Their principal towns were Rājiana and Dāmā-Minda, the latter now a mound of ruins near Sekha. The Barārs of the Sangar clan attacked them and took these places, and the Gils were driven further to the north. They then established themselves about Chhurk, Ghal and Moga, as at present. Peace was at last made by a daughter of Sangar being married to one of the Gils, an alliance which at that time was considered to raise the Barārs considerably in the social scale.

Moga and Vega were two brothers and men of importance among the Wadian Gils. Moga had four sons, as follows:—

1. Jusang, whose descendants live in Moga and Landekh.
2. Rops—in Bughipura and Kariāl.

### Chapter III. C.

Traces, Castes  
and Leading  
Families.

The Sidhus.


### The Gils.

**Chapter III, C.**

**Tribes, Castes  
and Leading  
Families.  
The Gila.**

3. *Awan Khair*—in Mahna, Chingawān, and Landeke.
4. *Sandali*—in Kokri and Dunewāla. The leading family among the Wadan Gils is that of the Sardārs of Rāma.

The following statement shows the connection of their principal villages with one another:—



The Sher Gils are mostly to be found in the Maujha and in the south of the Zira and Ferozepore Talukas. They are said to be the descendants of two brothers, Dharo and Raja. Raja had four sons, Dhule, Sone, Augar, and Kink. Their most important member is Sardar Amar Singh, of Mansourwali. The other sections of the tribe are not largely represented in this district.

The Gils are, on the whole, the steadiest and most prosperous cultivators in the district, and possess the largest share of the good qualities by which the Malwi Jat is distinguished. They are quieter and more easily contented than the Barars, and though they have plenty of self-respect, are less self-assertive. The Gils have a sacred place at Rajam, the shrine of Raja Pir, whence is derived the name of Rajana, and they make pilgrimages thither, though the village is now in the hands of the Barars.

The Dhaliwals or Dhariwals were the earliest of the Jat tribes to establish themselves in this district. Their origin is uncertain; all they can tell is that they came from Dharamnagri, which they say was somewhere in the south of India. They are apparently a branch of the great Bhatti tribe. The Raja of Dholpur is of their clan. They occupy the south-east angle of the Moga Taluk, which is hence called the Dhaliwal "tappa." They are divided into two sections, the Udis and the Manis. The principal villages of the Udis are Badini, Lopon, Lohara, Bansil, Salabatpura, and Raoki. Bihaspur, Sejoks, Muchikoti, Dholpur, and Himmatpura belong to the Mani section.

Kangar, now in Patiala territory, a little to the south of the Moga boundary, was the head-quarters of the Dhaliwals before they came to this district. A daughter of Mihr Mitha of Kangar was married to the Emperor Akbar. It is related that the Emperor first saw her at a well in her native village. She had two gharis of water on her head; at the same time she caught a young buffalo which had escaped from its owner, putting her foot on the rope attached to its head, and thus held the headstrong animal without losing her balance until he came up to claim it. The Emperor was so much delighted with this feat of strength and courage that he made her his wife, in the hopes that she would be the mother of children no less courageous than herself. On her father, Mihr Mitha, he conferred the title of Miran and gave him a jagir of one hundred and twenty villages, of which Kangar was the centre.

The descendants of Mihr Mitha, though called Miran, are said not to have been converted to Muhammadanism; but for several generations their leaders, especially at Himmatpura, bore distinctly Muhammadan names, and it is not impossible that they conformed to the religion of the Meghal Emperors until the rise of the Sikh power encouraged them to return to Hinduism. The Dhaliwal villages having been under cultivation from an earlier period than the rest of the rohi country, the population has begun to press upon the land, and the holdings are rather small. The people are consequently not so well off as the Barars and Gils.

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.**

**The Khosa.**

In character they are particularly peaceable and law-abiding. Unfortunately the habit of opium-eating is spreading amongst them, and is having a lowering effect.

The Khosa are a strongly marked tribe, though holding only about a dozen villages mostly near the junction of the three tahsils of Moga, Zira, and Ferozepore. They say that they are Tenwai Rajputs from Doihi, and they have a story, resembling that of the Jats, of their ancestor Handhir having been exposed as an infant, and miraculously preserved; he was sheltered by a kite. The Khosa had formerly a character for crime. They have an independent bearing. As cultivators they do not take a very high place. Their leading families are those of the Sardars of Attari and Basikhali in the Zira Tahsil.

**The Sandhus.**

The Sandhus of this district have mostly come into it from the Mâdhopur. Many were brought over into the Zira Bat by the Akbarwâla Sardars during the time of their rule. Their principal villages are Sarball, Wattoha, Chalba, Bhurâna, and Mamwan. Some other Sandhu villages are found in the south of Ferozepore; their owners own land in Faridkot and in Mukatsar, and are very wealthy.

The following account of some of the tribes of Fazilka is taken from Mr. Wilson's report:—

**Wattas.**

"The chief tribe of Musalmans in the Sutlej valley in Fazilka are the Wattas, who number altogether 3,810. They own twenty-four villages and shares in twenty-eight others. The hards (Mirâsia) trace the descent of the Wattas from Noah through Shem, his son, and then through a long list of famous Râjs, one of whom settled in Sirsa, while another reigned over Arabia. However this may be, they consider themselves Baghubarsi Rajputs, and some importance may be attached to their tradition already mentioned that they are closely connected with the Bhatti Rajputs of Jaisalmir, with the Bhatts of Hania, and with the great clan of Sidhu Barak Singh Jats. This relationship they give us follows:—

MAZA JUNJAR.



Their ancestor Wattu was a great Râj, who ruled at Watali, in the Gurdaspur District. A descendant of his came and settled in this neighbourhood, and his descendants became Musalmans some sixteen generations ago, about the time of Khiwa, who ruled near Hâwell in the Montgomery District, and was succeeded by Lakha Khan, a famous Watta Chieftain (see Montgomery Settlement Report). The Wattas are found chiefly in the Montgomery, Sirsa, and Bahawalpur Districts, and as only 24,695 have been returned for the whole province, it is probable that they are only a comparatively small branch of the great Bhatti clan. They hold the

country along both sides of the Sutlej from about Baggeke, sixteen miles north of Fazilka, to Phalabi, seventy miles south, and are bounded on the north by the Dogars and on the south by the Juiyés. They settled on this side of the Sutlej only four or five generations ago, when Fussl, Ráms, and other ancestors of the present leading men came across from Jhang, near Haweli, and settled near the river in the country which was then unoccupied. They were for a time under the Sikh Bhais of Kaithal, but threw off their yoke after the grandfather of Pir Khan (now one of their leading men) had killed, at his village of Muhammad Pura, the brother-in-law of the ruling Bhai for demanding grazing fees from the holy man of the Wattás. They then placed themselves under the rule of the Nawab of Bahawalpur until, in 1844, the Wattó Pargana was ceded by him to the British. In the Mutiny, the Wattás rallied round Mr. Oliver at Fazilka, and some of them were rewarded with revenue-free grants and the gift of confiscated villages. Several of their leading men—Ahmad Khan of Lailioké, Mokim of Mumzam, Jagá of Ráms, and Ihabim of Salim Shah—have been recently appointed zamídars.

The Bodías claim descent from Abu Daka' Sadik Khalifa, <sup>The Bodías and</sup> Chakha:

and call themselves Shekh Sadiki. According to their tradition, their ancestor Shekh Shahab-ul-din, known as Shahab-ul-Mulk, came from Arabia to India three or four centuries ago, and became a disciple of Khawaja Muhammad Irak Ajami at Moolian. One day that saint told Shahab-ul-Mulk that he was to him Bo-e-dil (heart's fragrance), which is explained to mean that he knew intuitively his preceptor's every thought; hence the descendants of Shahab-ul-Mulk are known as "Bodías." Shahab-ul-Mulk afterwards settled at Khai, near the Sutlej, in what is now Bahawalpur territory, some seventy miles south-west of Fazilka. All Bodías are said to derive their descent from Shahab-ul-Mulk, and their origin from Khai. Two small families of Bodías seem to have come directly from Khai to Fazilka within the last sixty years. One of these holds Ranga on the Ghaggar in the Dabwali Tashil, and the other owns Surawán and four other villages in the Fazilka Rehi. But the chief immigration of Bodías took place some four generations ago, when Mehkam Din came from Khai and settled at Abul, not far from Bahak, where the remains of his town are still to be seen. The country was then uninhabited, and the Bodías kept large herds of cattle, and drove them hither and thither for pasture over the tract of country afterwards known as pargana Bahak, from Bahak, which became their chief village after the destruction of Abul. The Bodías had many contests with the Nawab of Marni, who claimed jurisdiction over their country, and it was not till about 1855 A. D. that they were removed from his control, and the pargana was attached to the Ferozepore District. It was regularly settled soon after, and transferred to the Sirsa District in 1858. The greater part of pargana Bahak was declared to belong to the Bodías in proprietary right, and one-sixteenth of the revenue of the whole pargana

## Chapter III, C.

Tribes, Castes  
and Leading  
Families.

Wattás.

**Chapter III, C.**

**Tribe, Castes  
and Lending  
Families.**

**The Bodlás and  
Chishtis.**

was confirmed to them in jagirs in recognition of their saintly character. Those Bodlás who belong to this pargana still enjoy the allowance, which is divided into complicated shares, founded chiefly on ancestral descent. When the country to the south and east was being colonised thirty-five years ago, some of the Bahak Bodlás acquired villages or shares in villages outside the pargana, and a few of them obtained further grants for good service in the Mutiny. Their claim to a saintly character, and to some sort of precedence, has always been allowed by their neighbours. They are supposed to be able to cure with efficacy, and instances are given in which the evils called down by them on their enemies were fulfilled; but their special gift is the cure of the bites of mad dogs or jackals, which is performed by a species of incantation, and large numbers of all classes, Hindu as well as Mussalman, apply to them in cases of bite, and are said to be cured by their miraculous power. They were until twenty-five years ago essentially a pastoral tribe, and even now a large part of their wealth consists in horses and cattle. They do not cultivate much themselves, and are bad managers, unthrifty and extravagant, leaving much to their agents; and the proprietary rights conferred on them at settlement are fast passing out of their hands into those of Sikh Jats. Their tenants are mostly Mussalmans paying rent in kind, and to an unusual extent under the power of their landlords. The Bodlás are generally large, stout men, with broad flabby faces, large, broad, prominent noses, and thick but not projecting lips, which give their whole mouths a weak appearance; and altogether they look like men accustomed to a lazy life of self-indulgence. Their language and customs are those of the Wattuis and other Punjab Mussalmans among whom they live, and with whom they are closely connected by intermarriage. They have no connection with other Sheiks, and, notwithstanding their proud traditions, are probably, as surmised by Mr. Ollier, who knew them well, really of Wattu descent, or, at all events, of indigenous origin, and distinguished from their neighbours only by the assumption of superior sanctity, and the spirit of exclusiveness it has bred.

**The Chishtis.**

The Chishtis, who are also a holy tribe, claim descent from Umar, the companion of Muhammad, through Sultana of Balkh, Shāfi and Kābul, and call themselves Shāikh Faraki. Their more recent ancestor was Khawāja Farid-ud-din, known as Baba Farid Shakarparanj, who, starting from Multan after a forty days' fast at Sirsa, became the pupil of Kurb-ul-din at Dehi, and finally settled as a Chishti faqir at Chārahlia, now known as Pākpatian, in the Montgomery District, where his shrine and family are still famous. The ancestors of the Sirsa Chishtis crossed the Sutlej from Pākpatian only four generations ago, and settled near the river on lands then uninhabited. They now hold some nine villages in the Sirsa District, all near the Sutlej, south-west of Fazilka. A number of them are found in Montgomery and Bahawalpur. Like the Bodlás, they are considered a holy tribe, and are in consequence very exclusive, and do not give their daughters in marriage out of the tribe, while they

take in marriage only the daughters of high class tribes in the neighbourhood. They have sharper features and a less sensual appearance than the Boddas, but, like them, they are bad managers, and do not themselves cultivate their lands; and their sacred character has enabled them to contract large debts on low interest, so that they are, as a rule, somewhat involved.

The Mahtams in the Fazilka Taluk are found only near the Sutlej. Like the Bawariás with whom they are ranked, they seem to be originally a tribe of hunters, living chiefly on the river banks, and hunting in the tamarisk (*pitschi*) jungle which grows along the river on land subject to inundation. Their traditional mode of hunting is similar to that of the Bawariás, only instead of making their nooses of hide they make them of *muni* rope, and call them *vars*, not *bisier*, and instead of setting them in the open prairies they set them in the tamarisk jungle. They catch all sorts of animals in this way, and say they used to snare wild pigs and even tigers in their nooses. They also sometimes make a long line of low impenetrable hedge by interweaving the branches of bushes together, so that small animals, such as hare and partridge, running through the jungle, are stopped by this hedge and run along it to the gap, near which the hunter lies in wait to get an easy chance of killing them. The Mahtam is very fond of the *sarr* grass, and one of his chief employments is making rope and other articles out of it. They are considered a low caste, and often live apart from the other villagers; but many of them have taken to agriculture, and make very good, industrious cultivators, especially on land subject to inundation. Some villages and parts of villages on the Sutlej are owned by them; their huts are often squat and dirty, but they are, as a rule, prosperous and somewhat quarrelsome. Their dark complexion and general appearance, as well as their hereditary occupation of hunting, seem to argue them an aboriginal tribe. They are classed as Hindu or Sikh. No other tribe intermarries with them.

The Mahtams own several villages in the Mandot Taluk as well as in Fazilka. They are considered much the same as Maibi Sikhs. They rank below Bawariás, for cases are now beginning to occur in which those Bawariás who have become substantial zamindars intermarry to some extent with the Jats.

The only tribe of any size in this district of a distinctly criminal character is that of the Bawariás. Their principal haunts <sup>Criminal tribes:</sup> Biwaria, Hârni, are the villages of Tharâj and Sûkumand; but they are found scattered throughout the district, one or more families residing in nearly every village, where they are entertained principally for their excellence as trackers. Their tradition says that they come from far south, and possibly they are connected with the hunting tribes of Southern India. Their name is taken from the *bawar* or snare with which, as previously mentioned, they capture deer. They call themselves orthodox Hindus, but their worship is confined to that of Kali, or Durga, whom they regard as a goddess of help as well as of vengeance; and their only spontaneous literature (if that

## Chapter III, C.

Tribes, Castes  
and Leading  
Families.

The Chahrias.

The Mahtams.

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.**

**Criminal tribes :  
Bawarias, Barmas,  
and Basias.**

may be so called, which is unwritten) consists in songs and hymns to her praise. They have a language of their own, which is unintelligible to the ordinary villagers, who stigmatise it as an argot or thieves' dialect. They themselves say it is a heritage, which is more likely; it approximates in character to the Sanskratic dialects of more Southern India, with many non-Sanskritic vocables imbedded in it. Their character and morality are very low; but their thefts are generally petty, and their reputation is rather that of gipsies in England than of more dangerously criminal tribes. At present their chief and favourite occupation is that of hunting, and their principal weapon the snare, in the use of which they are very skilful; but gradually they are rising from the hunting to the agricultural stage, and but for the baneful system of caste, which prevents them from intermarriage outside their own tribe, they would doubtless soon be merged in the orderly classes of the community. Physically they are a small, dark race, with broad ugly countenances of a peculiar type. Their women are distinguished by wearing petticoats made of black blanket; but the younger women are abandoning this custom. Their favourite food is a kind of lizard (*sanda*), found plentifully in the waste land of the *roki*. Of their skill in tracking Mr. Brandreth writes—

" The system of tracking is carried on with very great success in this district, and is the principal means by which crimes of all sorts are detected. The Bawarias are the most successful trackers, and every Bawaria has more or less knowledge of the art; but it is also practised by other castes; there are many Jatis who are very good trackers. It appears to me a most wonderful art. In almost every village there are one or more persons who have studied it. When a theft takes place, the sufferer immediately sends for a tracker, with whom he makes an agreement, either to pay him one or two rupees and take his chance of the property being recovered, or to pay him a larger sum in the event only of its being found. It is in the case of cattle-thefts that the tracking system is most successful. I suppose about half the number of stolen cattle are recovered in this manner. It must not be concluded, however, that half the number of thieves are also apprehended, for the pecuniary loss of the cattle-stealer is that he drives the stolen animal as far as he thinks it safe to do so, and then ties it up in some desert spot and leaves it there; after a few hours he returns to the spot; within that period it is decided whether the track has been lost or not. If the trackers are successful, they come to the spot where the animal has been left and carry it back with them, but give themselves no trouble about the thief; if unsuccessful, the thief returns and appropriates it.

" The best trackers, however, do not confine themselves to this species of tracking alone; they are able to recognise a man by his footprints. Where other people would study a person's face with the view of recognising him again, they study the print of his feet. They pay particular attention to the footprints of any known bad characters. I have met with some extraordinary instances of the accuracy of their knowledge in this respect. It is only a few days since that I committed a man to the Sessions for the murder of a child for its ornaments, who was detected solely by the impression of his feet being recognised. The headman of the village went with the tracker to the spot where the murder had been committed. He followed the tracks of the murderer for some distance towards the village and at last said: " These are evidently the footprints of so and so," naming one of the residents of the village. The headman immediately went to the house of the person indicated, and found the ornaments buried in the wall. This man con-

feared his guilt. In taking his evidence I asked the tracker how he was able to recognize the prisoner by his footprints. His reply was that it would have been very strange if he had not seen them every day of his life!"

The Härnis and Sānais are very few in number, and but little information can be collected as to their habits in this district. They are generally regarded as addicted to more serious crime than the Bāwariās, while they certainly are more filthy and degraded in their manners. They are for the most part of nomad habits, and live in rude tents or huts made of reeds (*siris*). There are many other nomad tribes; but they are probably not peculiar to this district, except perhaps the wandering blacksmiths who come from Bikanir and make a home of the small carts in which they carry their property and tools. Rathars are a tribe who live by making ropes from *munj* grass. Encampments of Nais, Bāsīgars, and Kanjars are often seen. Some tribes, instead of the shelters of reeds used by the above, have round tents formed of a patch-work of rags over a bamboo framework. It is unnecessary to mention here the various tribes of wandering fakirs.

Of the Banias of Ferozepore, no fewer than 10,093 return ed themselves as Agarwāl at the census of 1881; of the Aoris, 5,079 returned themselves as Uttarādhi and 3,432 as Dakhana; of the Khatrias, 8,779 as Banjāhi, 474 as Bāhri, and 419 as Sarin.

### Chapter III. C.

Tribe; Castes  
and Leading  
Families.

Criminal tribes;  
Bāwariās, Härnis,  
and Sānais.

### Mercantile castes.

*The Mamdot Nawabs.*—This family of Hassamai Pathans came from Kasur. When Mahārāja Ranjīt Singh ruled the Panjab, Nawab Qutb-ud-din Khan, the grandfather of the present Nawab, held Kasur. The Mahārāja took Kasur, and let Qutb-ud-din Khan take Mamdot. Qutb-ud-din Khan had two sons, Jamal-ud-din Khan and Jalil-ud-din Khan. The former had sovereign powers until he was deposed by the British Government. He died in 1863, leaving two sons, Muhammad Khan and Khan Bahādur Khan, neither of whom succeeded his father; but after a long dispute Jalil-ud-din Khan inherited the family jagir, while his two nephews got an annual allowance. One of them, namely, Khan Bahādur Khan, is now living at Lahore; the other died some time ago. Nawab Jalil-ud-din Khan was made an Honorary Magistrate. He died in 1875, and was succeeded by his son, Nisām-ul-din Khan, the present Nawab, who received charge of his property from the Court of Wards in 1884.

*The Sodhis.*—The Sodhis of Mukabbar own several villages. It is well known that, during the Sikh rule, the Sodhis played a very conspicuous part. According to their account, their ancestor, Kalruj, ruled at Lahore, and his brother, Kalpat, at Kasur. The latter drove out Kalruj, who took refuge with some king in the Deccan, where daughter he married. Their son, Sodhi Rai, reconquered Lahore, and Kalpat in his turn became an exile. He went to Benares and studied the Vedas, on which account he obtained the name of Bedi. All the Sikh Gurus were either Bedis or Sodhis; Guru Nānak belonged to the former, Guru Govind to the latter, family. The most important Sodhi

**Chapter III. C.**

**Tribes, Castes  
and Leading  
Families.  
The leading  
families.**

families in Mukatsur are those of Guru Har Sahai and Mallan. Other Sodhi families, residing at Batal in tahsil Moga, hold several estates in Mukatsur in jagir.

At annexation the Sodhis held *jagirs* of the value of about Rs. 40,000 per annum, of which about Rs. 5,500 were continued in perpetuity, and most of the remainder for one or two lives only.

*The Guru Har Sahai Family* trace their succession in a direct line from Guru Rāmīlā, after whom the great Sikh temple of Amritsar is called. The founder of the family was Guru Jivan Mai, who in Samvat 1909 came from Muhammadāpur in the Chumān Taluk of the Lahore District, and settled at the place now known as Guru Har Sahai, so named by the founder in honour of his son. He was succeeded in order by Guru Ajit Singh, Guru Amir Singh, Guru Golab Singh, Guru Fateh Singh, and Bishan Singh, who is now living. The religious influence of the family was decidedly great up to the time of Guru Golab Singh, not only among the Sikhs of the neighbouring districts and foreign States, but in Sialkot, Rawalpindi, the Derawar, Kohat, and even as far as Kābul; but this influence has been decreasing from Guru Fateh Singh's time, whose family quarrels with his sons continued until his death. Now the family has but little influence, and that, too, within a very limited circle. The late family quarrel between the present Guru Bishan Singh and his brothers has done much harm.

*The Dhillian Sodhis.*—Sodhis Jagat Singh and Bhagat Singh were two brothers, who owned lands in the Moga and Mukatsur Tahsils. Jagat Singh's son is Sodhi Man Singh, who is now an Honorary Assistant Commissioner at Batal in this district. Sodhi Inder Singh is the son of Sodhi Bhagat Singh. He is Honorary Magistrate at Sultankhanwala. His brother, Sodhi Hajiendar Singh, recently deceased, was Honorary Magistrate at Baghopurana.

*The Pir Pathans.*—Pir Abbás Khan, late Honorary Magistrate of Ferozepore, was formerly Government Agent at Palkwalipur, and subsequently a pensioner at Ferozepore, where he acquired some landed property. His son, Pir Ahmad Ali Khan, is on the Board of Honorary Magistrates of the city of Ferozepore. As an account of the family of every person entitled to a seat in Darbār has now been included in the new edition of Sir Lepold Griffin's *Punjab Chiefs*, prepared by Colonel C. F. Massy, it is unnecessary to include any detailed account of them here.

## SECTION D.—VILLAGE COMMUNITIES AND TENURES.

Table No. XV shows the number of villages held in the various forms of tenure, as returned in quinquennial Table No. XXXIII of the Administration Report for 1878-79. But the accuracy of the figures is more than doubtful. It is in many cases simply impossible to class a village satisfactorily under any one of the ordinarily recognised tenures; the primary division of rights between the main subdivisions of the village following one form, while the interior distribution among the several proprietors of each of these subdivisions follows another form, which itself often varies from one subdivision to another. Indeed the nomenclature of this classification was unknown before the time of the Reginar Settlement; and, popularly, the tenures are still distinguished by the names of the tribes among which they are severally prevalent. Thus, the *zamindari* tenure is known as that of the Dogars and Naipals; while the *pattiwal* and *bhamachira* forms are *par excellence* Jat tenures. The following paragraphs are abridged from Mr. Brandreth's Settlement Report:—

The *zamindari* tenure is principally met with in the *het*. The *zamindari* tenure.  
The Dogars and Naipals held the country before the Sikhs acquired dominion over them. Before that time they appear to have been almost independent; they principally pastured cattle, and did not trouble themselves much about cultivation. The Sikhs, however, urged on the cultivation to much greater extent than was before known, and took the rent in kind from both proprietary and non-proprietary cultivators, making over a certain portion (which was generally a third, but sometimes a fourth) of the *hikim-i-hisar*, or rent share, to the proprietors in acknowledgement of their rights. It is a curious thing that it is not by any means all, or nearly all, the resident Dogars who are proprietors. The proprietary rights were confined to certain Chiefs and to their descendants; and there are many Dogar cultivators of near relationship to them who have no proprietary rights whatever, and are only common cultivators. On the other hand, there are few Naipals who are without proprietary rights. It is probably owing to their pastoral habits, and the little value they have hitherto attached to cultivated ground, that these castes, and the Dogars in particular, very seldom divided the village-area in accordance with their shares, but have generally held all the land in common. Hence the record of such villages as *zamindari*.

When the villages owned by these castes came under the dominion of the British Government, the grain payment was commuted into money assessment, and the settlements were all made with the Dogar or Naipal proprietors. These proprietary bodies, however, being altogether unaccustomed to money rates, and unwilling to incur the responsibility of them, frequently attempted to sub-let their villages to Hindu traders on the same terms which they had enjoyed under the Sikh government, the sub-lessees standing in the place of the Sikh Kardar,

## Chapter III D.

Village  
Communities  
and Tenures.  
The ~~minimari~~  
tenure.

paying the Government revenue, and collecting the rents in the manner described above. This method of procedure, however, was forbidden by order of the Punjab Government.

In a village so held, all non-proprietary cultivators paid their rent in kind previous to the Regular Settlement. Even in the case of such crops as tobacco or vegetables, the rents were either paid in kind, or by what is called *bikra* or sale of the crops. The cultivator sold the crop on the ground without dividing it, with the sanction of the proprietor, and then paid him the same share of the price that he would have done of the crop had it been divided. At the time of the Settlement the cultivators with rights of occupancy received permission to commute their former rent in kind for a money payment, the rate of which, including all expenses, was usually fixed at 26*½* per cent.\* on the Government demand. In special cases; as where the cultivator has sunk a well at his own expense, or broken up the waste land at some cost to himself, a lower rate has been fixed, and the same considerations have been held to confer on him rights of occupancy. It has also been agreed in some villages that at any future period either the proprietors or the cultivators shall be permitted to substitute a money payment instead of that in kind, provided that their application for this purpose is preferred in the month of Jeth, i.e., before the rainy season commences, and before any expectations can be formed regarding the nature of the ensuing harvest.

The dues of village servants (*basins*) are deducted from the common stock before the division of the proprietor's share is made. In the same manner is also deducted a quantity, which varies from about two to four *sirs* in the manud, and is called *kharch*. It is taken by the proprietor to cover the expenses to which he is put in guarding and dividing the crop.

The manner in which the division of the crop (*buti*) is usually managed is thus described by Mr. Brandreth:—

"In the first place a small heap is usually set apart for the *basins* kharch, and other dues above referred to. This is not weighed or calculated with any precision to accuracy, but is merely set apart from the rest of the produce as well as the cultivator can judge by his eye of the proportionate quantity that will be required to meet these extra charges. Then, supposing the proprietor's share to be one-fourth (which is the usual amount), the remainder is divided into four equal heaps. One of these heaps is then measured with the *tola*, a wooden measure containing two-and-a-half *sirs*, and the amount due on account of the *kharch*, *basins* dues, &c., is calculated thereon and taken out of the small heap above described. Thus, where the amount of the *kharch* is said, for instance, to be four *sirs* in the manud, this does not mean four *sirs* on every manud of the whole crop, but four *sirs*

\* The items of which this rate is made up may be set down as follows:—

Lambardari's allowance at	...	...	...	...	2	per cent.
Village expenses	...	...	...	...	5	"
Patwari's allowance	...	...	...	...	12	"
Road Rent	...	...	...	...	2	"
Malkana	...	...	...	...	12	"
Total					26 <i>½</i>	per cent.

on every mannd of the fourth share, or what is called the *lakhsāi bisā*, including therefore the deductions on account of *kāshāt*, &c. This amount will be actually less than a *sīr* in the mannd calculated on the whole crop. If there is any grain left in the small heap after paying these dues, and the harvest has been a good one, and both parties are charitably disposed, it is generally distributed to *fākirs*, otherwise it is divided in equal portions among the four heaps. If there is any deficiency it has to be made good in equal portions in the same manner. The proprietor has then his choice of the four heaps, and, having selected one of them, carries it off to his granary without any more weighing or measuring. Besides the share of grain, the proprietor is also entitled to a share of the straw which is left after the grain has been trodden out; this is generally less than his share of the grain. Where his share of the grain is a fourth, his share of the straw is generally a fifth or sixth; but from this there are no deductions on account of extra charges. In some villages the straw is not divided into shares, but what is called a *pāndi*, i.e., a net which holds about a coolie's load, is contributed for each plough. The proceeding here described is that called *bhāshāt*, or *satpāt*, and this is the rule by which the rents are usually paid; but sometimes, with the consent of both parties, the system of *hāshāt*, or appraisement of the crop, is substituted for it. In that case, the proprietor's share is not converted into money at the market price of the grain, as would appear to be the case in some districts, but, the produce of the cultivation having been estimated by the appraisers, this estimate is accepted in lieu of the actual produce, and after the crop has been cut and stored, the cultivator has to pay every item of the rent in the same manner as he would do if the *lātādi* had taken place.

"There are also many other customs," Mr. Brandreth continues, "of greater or less importance connected with this system of payment in kind, which vary very much in different villages. In some villages, for instance, each cultivator of a *jog* (yoke of oxen), or sixth share of a *wāl*, is allowed to feed one pair of bullocks from the green crops on the *wāl* land, and sometimes a few or one other animal besides, without any payment being made to the proprietor. . . . In other villages, again, the cultivator is allowed to cut a certain portion of the crop for his cattle by measurement; in others he may cut as much of the crop as he chooses, but he has to pay for it by appraisement in gram on a calculation of the average produce of the remaining crop. If the cultivator has dug the *wāl* which he works at his own expense, he generally receives a certain portion, as a fifth or a sixth, of the *lakhsāi bisā*, or proprietary share of the crop, in addition to all other privileges. In many villages the proprietor is entitled to cut a certain small portion of the green crop for his own use, or, if he does not do so, to appropriate the whole produce of that portion when it becomes ripe. It must not be cut, however, in the centre of the field, but at the corners or sides: but this custom is also subject to great varieties in different villages."

The nature of the *pāttidāri* and *bhāshātā* tenures Mr. Brandreth explains by describing the manner in which the location of a village first takes place. The Jats did not, like the Dogars and Rājpūts, take violent possession of the country and override every other claim. There are few villages in the district more than sixty or seventy years old, and, therefore, all the circumstances connected with their foundation are very well known. A new village would be usually founded in the following manner:—

"A certain number of *seminiders* . . . would determine on migrating from their native village. One or two of their most influential men would then go to the *Kārdor*, or ruler of the country, and make an agreement with him for acquiring possession of some one of the numerous deserted sites with which the country was covered, and the land attached to it.

## Chapter III, D.

Village  
Communities  
and Tenures.  
The *pāttidāri*  
tenure.

Pāttidāri and  
*bhāshātā* tenures.

## Chapter III. D.

Village  
Communities  
and Tenures.  
Panjabis and  
Brahachira tenures.

The agreement on the part of the zamindars would probably be to pay a certain share of the produce of their fields, generally small at first and increased afterwards; and on the part of the Kauris to grant them a certain quantity of land rent free, either in payment for their services, or in acknowledgment of their proprietary rights, to whichever cause it may be attributed: a marddar or present of a horse or of a sum of money, would be given at the same time by the zamindar to the Kauris. The rent-free land was called *sada*. The Kauris, as far as he was concerned, would probably only confer it on the two or three influential men who appeared in his presence; but among themselves they could agree to divide it in regular shares. Sometimes every one of the original occupants would possess a share; in other instances only a limited number of them, while the light rates fixed for the land they might cultivate would be a sufficient inducement for others to settle in the new village without requiring a share in the *sada*.

"The first thing the new settlers set about is to select a site for their village. They never build their houses on the old deserted site, for this they say, would be very unlucky, the first settlers having long ago taken all the *bikar* (f blessing) out of that spot. The laying the foundation of a village is called, from the ceremony with which it is accompanied, *mari-gidran*. This consists in planting a pole to the north side of the intended habitation; the neighbouring settlers are invited to be witnesses, and presents are distributed among them. To have borne a part in this ceremony is considered the strongest evidence in support of proprietary rights. If the pole should take root, and put out branches and become a tree, this is considered a most auspicious circumstance; the tree is then always called the *suci* tree, and is regarded with great veneration. In the uplands a branch either of the *hara* or of the *pita*-tree is always taken for this *suci*; in the lowlands the *hara* is generally used; it must be always some fruit-bearing tree. The *suci* is generally eight or ten feet high, and is planted about three feet in the ground; beneath it is always buried some rice, betel-nut, gur, and a piece of red cloth. They next build a well, in the expense of which all the new settlers join, and pay for it in the proportion of their shares in the village.

"The next process is to divide the village land by lot in accordance with the ancestral shares of the different castes or families who have founded the village, or with any other system of shares on which they may have agreed to distribute their proprietary rights. For this purpose the whole area is first marked off into two or more primary divisions called *teras*. The *teras* are then subdivided again into two or more sections called *panjis*, and the *panjis* again into *bars*. There are not, however, always as many subdivisions as those here referred to: the number depends upon the size of the village, the castes, the families, the party feelings, and such like circumstances. Sometimes there are three orders of subdivision, sometimes four; sometimes one; often no primary subdivision at all, just as the circumstances of the case may require.

"The last subdivision, whatever it may be, after demarcating, if necessary, a sufficient quantity of land to be held common, for grazing purposes or for cultivation by non-proprietary residents, is then apportioned in separate shares. These shares, as being the most convenient size, are usually made to represent the quantity of land which can be cultivated by a plough, which is generally about thirty *gahons*, but which varies with reference to the nature of the soil, the breed of cattle used in ploughing, &c., &c. The shares are consequently always called *ploughs*, but they have no necessary connection with the quantity of land capable of cultivation by a plough. Where the fractional shares have in the course of time become too minute for the comprehension of the villagers, I have known them solve their difficulties by doubling the number of ploughs without making any increase to the cultivated area. In other instances, I have known the proprietors dividing the lands reserved for their own cultivation into larger ploughs, and then apportioned to non-proprietary cultivators into smaller. Thus both proprietary and non-proprietary cultivators

paid by blocks, nominally at the same rate, but in reality the latter were assessed much higher.

" The distribution of *patti* and ploughs by lot usually took place in the following manner.—Balls made of cow-dung were used for the lots, in which each shareholder placed his mark, either a piece of cloth or pottery, or a ring, or anything else by which he might be known. The order in which the lands were to be taken was fixed beforehand. A little boy or ignorant person was then called to take up the lots, and whosoever's lot came out first did not get his choice of the lands, but took the first number on the list as previously fixed, and so on with the rest of the lots. The primary subdivisions, or *farafs*, were, of course, first fixed, and in this the whole village was concerned. Then the members of *sabads* or *castes* for the *patti*; the members of each *patti* for the *hats*; and, lastly, the members of each *faraf* for the separate shares or ploughs.

" After a few years of grain-payments, and when a village had acquired stability, it was usual for the Sikh Government to fix a money assessment. At the same time the land *taka* in possession of the headman was usually resumed, and a money allowance given instead of it. The resumption amounted to 20 or 40 per cent. on the revenue demand, and was never less than 10 per cent. The headmen, in their turn, were obliged to make their own bargain with the other shareholders; they could not keep the whole of the *taka* for themselves, though they of course took care to retain the lion's share.

" In some villages the distribution by lot, which was made at the commencement, has lasted to the present day. This is the case particularly in the *Mari* *Hikas*, where the revenue has always been very light. But, as a general rule, under the Sikh administration, many subsequent distributions have taken place in order more easily to meet the Government demand and so tilt up shares which had been diminished in consequence of its heavy pressure. In these distributions all traces of the original shares have usually been lost, the original proprietors retaining in their possession only so much land as it was worth their while to cultivate, and making the remainder over to new cultivators whose *status* in time came to resemble their own.

" At the Summary Settlement no change was introduced in the mode of distributing the revenue demand, which still continued to be paid by a rate (blocks) on ploughs or other shares recognized by the people. As to the *taka*, great diversity of practice prevailed prior to the Regular Settlement, when, owing to the complexity of accounts, which would have been involved by the registration of claims, now infinitesimally subdivided, and hence practically valueless, a general resumption took place, special allowance being made during the lifetime of certain individuals."

The Moga-Tahsil is the only one unaffected by river action. *Riparian customs, regulating property,*  
In the remaining tahsils the deep-stream rule generally determines the boundaries of jurisdictions, but it does not apply to land capable of identification carried away *en masse* to or from the Maudot Jigat or the Kapurthala State. Land thrown up by the stream is assigned to the village contiguous to which it appears, except when the quantity is so large as to be beyond the farming powers of the village. In such case a Government *chak* is formed. Disputes as to alluvial land between villages on the same side of the deepstream are disposed of in the same way as boundary disputes. In the event of an entire village area being washed away, subsequent accretions in the same place are made over to the proprietary body of the extinguished village. If land of which the revenue is free or assigned be carried away, the assignment is treated as resumed and land incapable of identifi-

**Chapter III, D.**

Village  
Communities  
and Tenures.

Riparian customs  
regulating property.

Proprietary tenures.

cation subsequently thrown up is made over to the village and not to the previous assignee. Accretions to revenue-free or assigned land follow the assignment. Land, capable of identification, carried away bodily to another jurisdiction changes its jurisdiction only and not its character, i.e., revenue paying land continues to pay revenue in the new district, *mâds* or *jagirs* retain their original character. Land carried away and restored during the same year returns to the original owners.

Table No. XV shows the number of proprietors and shareholders and the gross area held in property under each of the main forms of tenure, and also gives details for large estates and for Government grant and similar tenures. The figures are taken from the quinquennial table prepared for the Administration Report of 1887-88. The accuracy of the figures is, however, doubtful; indeed, land tenures assume so many and such complex forms in the Punjab that it is impossible to classify them successfully under a few general headings. The growth of proprietary rights, and the forms which they have now assumed, have been fully discussed in the preceding pages.

**Tenures in the Mukatsar chaks.**

Two questions of some importance—one connected with the Mukatsar *chaks*, the other with the Mamdot *chaks*—had to be decided at the Settlement of 1872. The Mukatsar *chaks* formed Mr. Brandreth's 33rd assessment circle, of which he says that it "comprises those waste lands of *idâka* Mukatsar which have been separately marked off for settlement with other parties, as no reasonable expectation could be entertained of the proprietors ever being able to cultivate them. A *biswâdari* allowance of 5 per cent. on the *jama*, however, has been fixed for them." The points to be decided were the *status* of the lessees, and the persons with whom settlement was to be made. The conditions made at last Settlement were:—(1). The lessees were to bring one-twentieth of the waste land under cultivation each year till the next Settlement; which means that in 10 years they were to cultivate half the land of the *chak*. (2). They were not, without the leave of the Government officers, to induce tenants of Mukatsar to settle in the *chaks*. (3). They were to pay 5 per cent. on the *jama* to the original proprietors as *militana*. (4). If the above conditions were not fulfilled, Government might resume the land and give it to whom it pleased. In 25 cases conditional proprietary rights had been thus bestowed. As it appeared that the conditions had been fairly fulfilled, except in one case, the lessees were recorded as sub-proprietors unconditionally, and the settlement was made with them. The old *taisudâri* allowances was maintained. In one case (that of *chak* Tâmkot) the former conditions were repeated. Three of the *chaks* had, subsequent to last Settlement, reverted to the original proprietors, who in several other cases had retained possession of portions of the new grants.

**Tenures in the Mamdot chaks.**

The questions connected with the Mamdot *chaks* were not so simple. While in Mukatsar a few desultory petitions were the sole sign that the lessees knew their position was in dispute, in Mamdot

close on 40 regular suits were introduced for the purpose of having the right of proprietorship in these blocks of land decided. The facts of the case seem to have been these:—Nawâb Jamâl-ud-din Khan would take *nazarâna* from a man and put him in possession of another man's village. This system did not conduce to the spread of cultivation, and led to the weakening of the Nawâb's authority. So, while the land was almost all waste, certain enterprising individuals squatted in the Nawâb's jungle. This was the state of things found when the Government took charge of the *dâla*. At the Settlement these squatters got possession of 15 villages; but as they had no apparent proprietary rights, the column "owner's name" in the settlement record, remained blank. These villages were called *mauzâhs*. After the Settlement, the Deputy Commissioner formed 70 blocks out of the waste lands of Mamdot. These were called *chaks*. Of these 70 blocks, 20 were reserved for grass and fuel preserves; 3 more were subsequently added to these; 8 came into possession of the Nawâb; in three cases the occupants subsequently got decrees of court declaring their ownership; and one *chak* was washed away by the Suriej. There remained 35 *chaks*. As regards the *mauzâhs* the squatters got decrees in three instances. The other *mauzâhs* remained in dispute. The questions concerning the Mamdot *chaks* referred then to 12 *mauzâhs* and 35 *chaks* proper. As regards the 35 *chaks* proper, 26 were sold by auction by the Deputy Commissioner, and 9 were given away on payment of a slight *nazarâna*, or without any such payment. On this being reported to the Commissioner, he replied that he had no objection to locate *bendî fide* ousted zamindars (ousted by the Nawâb's revenue system) in convenient localities, and to give them cultivating leases. But to no other parties was he anxious to give up the land. Now there was scarcely one ousted zamindar among the lessees; and the matter went up to the Financial Commissioner, who sanctioned while disapproving of the cultivating leases. But he said: "No sale or transfer of proprietary right is sanctioned." On this the Commissioner directed that leases conferring proprietary rights were to be cancelled; and again that the *nazarâna* should be returned, and the lease should be purely for cultivation for ten years. Finally, the Government recognized the proprietary right of the Nawâb in all the waste land of Mamdot. The Deputy Commissioner cancelled the auction-sales, but did not cancel the leases in the other cases. At the recent Settlement, the Nawâb instituted a number of suits to be declared proprietor of these blocks. These suits were decided on the principle that, as Government had acknowledged the Nawâb to be proprietor of the waste lands of Mamdot, and as the action of the Deputy Commissioner in transferring this proprietary right had been repudiated by his superiors, the Nawâb was entitled to a decree, unless the occupants could show some valid title other than the Deputy Commissioner's lease, such as adverse possession beyond the period of limitation. In most cases the Nawâb got decrees. But as it was manifestly unjust, the people who, relying on the proceedings of Government officials, and trusting to its liberal

**Chapter III, D.**

Village  
Communities  
and Tenure.

Tenures in the  
Mamdot chaks.

**Chapter III. B.**

Village  
Communities  
and Tenures.  
Tenants in the  
Manning chakas.

intentions, had expended considerable sums in bringing the land under cultivation, should be ejected, or left at the mercy of the Nawâb, the matter was referred to Government as the manager of the jîzgî. The orders given, contained in Secretary to Government's No. 981, dated 13th July 1872, to Secretary to the Financial Commissioner, amounted to this:—The occupants of the manzals were to be recorded sub-proprietors and to pay to the Nawâb 15 per cent. on the *jama* as *talukdari* allowance. The payment of extra cesses was to be proportionately divisible between the *talukdar* and the sub-proprietors. Where the terms of the original lease had not been fairly carried out, and the waste largely exceeded the area under cultivation, a reasonable proportion of the waste was to be cut off and restored to the Nawâb. As regards the *chak*, sold by auction, the lessors were to be recorded hereditary tenants of the *chak*, if they had improved largely; and of the cultivated land with a reasonable proportion of waste, if the improvement had been moderate. But all these leases were got rid of between 1873 and 1880 after a series of law suits. Where the improvement was incalculable, they were liable to eviction. In the remaining nine cases, the lessees were to be recorded sub-proprietors, subject to payment of 25 per cent. on the *jama* as *talukdari* allowance to the Nawâb. The extra cesses were to be paid in equal shares by them and him. Where the terms of location had been fairly fulfilled, the sub-proprietors were to retain the whole *chak*; where the fulfilment had been only partial, they were to be allowed a reasonable amount of waste land, in addition to their cultivation. Where the conditions had been altogether neglected, the grants were to be resumed. These orders, while securing substantial advantages to the Nawâb, were most liberal to the lessors. It is difficult to say whether they or the Nawâb had the least right to the land. The orders were carried out. Where the Nawâb got any portion of the land of a *chak*, the revenue and cesses payable by him and the other occupants were carefully recorded. The rent due from the hereditary tenants was also fixed. After considering the matter, the customary rate of 12 per cent. on the revenue over and above the *jama* and cesses seemed a fair rent to allow. The lessees who were considered to have no rights were recorded as non-hereditary tenants; and the Nawâb was left to eject them if he saw fit. The sub-proprietors were allowed an amount of waste land about equal to the area they had cultivated; the hereditary tenants got half that amount.

In the Fâsilka Tahsil there were 83 villages which were held directly under Government by farmers. These persons had been given large grants of waste land chiefly in the neighbourhood of Alohar, which they were to bring into cultivation under certain conditions. At the Settlement of 1882 most of the farmers having that time substantially fulfilled the conditions of their grants, they were in 67 villages granted the proprietary right, care being taken to have rights of occupancy first conferred upon their sub-tenants who were the parties in

whom the labour of reclaiming the land had really fallen. The remaining villages were kept in farm for a further term of five years.

Table No. XVI shows the number of tenancy holdings and the gross area held under each of the main forms of tenancy, as they stood in 1887-88; while Table No. XXI gives the current rent-rates of various kinds of land as returned in 1884-85. But the accuracy of both sets of figures is probably doubtful: indeed, it is impossible to state general rent-rates which shall even approximately represent the letting value of land throughout a whole district. And, throughout a great part of the district, cash rents, as distinguished from revenue and ceases, are unknown. The status of tenants in the *amandir* (Dogar) villages of the Bet has been described above in some detail (pages 71—73).

In the Jat villages already described, much difficulty was found at the time of Settlement in drawing the distinction between tenants and land-owners, owing to the confusion caused by the creation of new shares under the pressure of a heavy land tax. Usually the original proprietary body, while making little objection to the enrolling of other Jats as proprietors, objected strenuously to the same privilege being conferred upon those whom they looked upon as belonging to non-cultivating classes. Such persons were, therefore, (generally with their own consent,) classed as non-proprietary cultivators; but a right of occupancy was given them in all cases—(1) where they could prove undisturbed possession for 12 years before British rule, and (2) where it was found that they had from the first, like the proprietors, paid nothing but the Government revenue on their land. The only practical distinction understood at the time of Settlement to remain between such tenants and the proprietors was that the former were not permitted either to sell or to mortgage their land.

The following figures show the result of Mr. Brandreth's investigation:—

*Distribution of Cultivated Area, 1852-53.*

Localities.	Area (in acres) cultivated.			
	by prop- rietors.	by heredi- tary culti- vators.	by non- hereditary cultivators.	Total.
In the Bet	—	—	—	—
In the Zabi	—	—	—	—
In the enclaving Dishes	—	—	—	—
	61,700 303,004 160,002	31,407 100,139 98,731	21,577 28,000 14,362	100,241 400,139 233,362
Total	—	—	—	610,644

## Chapter III, D.

Village  
Communities  
and Tenures.

## Village officers.

According to the return for 1887-88 the total cultivated area of the district consisted of 1,963,772 acres.

The figures in the margin show the number of headmen

in the four tahsils of this district. During the Settlement of 1852, no *zaildars* or chief headmen were appointed anywhere; but during the last Settlement of tahsil Muktsar and the *pargana* of Mandot of Ferozepore, three *zaildars* and 126 chief headmen in the latter and 15 *zaildars* and 351 chief headmen in the former were appointed in 1872. These

appointments were mostly made by Mr. Saunders, Settlement Officer, who preceded Mr. Purser.

In the revision of Settlement of the northern part of the district, which was made in the years 1884—89, the question of the appointment of *zaildars* was determined as follows:—Colonel Grey, when Deputy Commissioner of the district, had made informal appointments by election in 1882 in the tahsils of Moga and Ferozepore, in order, as he recorded, to avoid the evils incident on such appointments being deferred until re-settlement. The *zaildars* elect had been allowed to carry on the ordinary duties of the post, though they received no remuneration. It was decided by Government that they should therefore be confirmed in their appointments unless there were, in any case, such a ground of objection to the nominee as would have sufficed to ensure the rejection or dismissal of a formally appointed *zaildar*. Some few modifications were made in the boundaries of the *zaildars* in order to bring them into coincidence with the limits of *patwari*'s circles and of police jurisdictions. But the existing holders were all confirmed under the above orders. In Zira where no elections had been held by Colonel Grey new appointments had to be made, and under the orders of Government these were made, not by election, but by nomination. The *zaildars* receive one per cent. upon the revenue collections of their circles. In the northern part of the district and in Faridkot this charge is a deduction from the sum payable to Government, but in Muktsar and Mandot it is at present collected as an additional cess like the chief headman's allowance.

The head-quarters of the *mills* together with the prevailing tribes in each are shown on next page:—

Tahsil.	Zaildars	Chief headmen	Village headmen
Ferozepore	12	194	520
Zira	17	—	221
Moga	25	—	600
Muktsar	15	172	279
Faridkot	30	—	323
Total	105	429	3,626

## Ferozepore District.]

## CHAP. III.—THE PEOPLE.

81

*List of suits in the District of Ferozepore as they stood in 1888-89.*

Chapter III, D.

Taluk	Name of suit.	Number of villages	Annual land revenue	Prevailing castes of proprietors.	Village Communities and Tenants.
					Village officers.
Khanna	Khalid.	12	Rs. 13,411	Jat.	
	Sardar.		Rs. 15,480	De.	
	Katra Choor Pinday Singh.		Rs. 12,227	De.	
	Dalal.		Rs. 12,679	Pahala, Jat, An.	
	Khal.		Rs. 2,251	Dugar.	
	Ghulam Hussainwala.		Rs. 7,191	De.	
	Katra.		Rs. 3,014	Anan, Dugar, An.	
	Hussain.		Rs. 1,500	De, De, and Jat.	
	Bugga Pipli.		Rs. 12,074	De, De, De.	
Mirali	Munshi.	12	Rs. 12,002	Pahala and Dugar.	
	Jalal Kalan.		Rs. 2,120	Anan.	
	John Tuli Singh.		Rs. 3,001	Jat.	
	Waziria.		Rs. 3,598	De.	
Mirali	Mohammed.	12	Rs. 12,319	Jat and Khatri.	
	Mohammed Jit Singh.		Rs. 2,240	Jat.	
	Mohammed Mahtab Singh.		Rs. 2,001	De.	
	Kirkat Kalan.		Rs. 2,001	De.	
	Mohammed.		Rs. 10,479	De.	
	Dalal.		Rs. 18,850	De.	
	Dale.		Rs. 1,177	De.	
	Dare.		Rs. 1,254	De.	
	Lassor.		Rs. 10,987	De.	
	Lamberton Khan.		Rs. 10,514	De.	
	Hussain.		Rs. 11,218	De.	
	Khatri.		Rs. 10,172	De.	
	Ram Singh.		Rs. 10,377	De.	
	Sohna Khan.		Rs. 7,001	De.	
	Sohna Khan.		Rs. 7,001	De.	
	Sohna Singhwala.		Rs. 2,601	De.	
	Sohna.		Rs. 14,007	De.	
	Sohna.		Rs. 11,802	De.	
	Khan Achha.		Rs. 11,000	De.	
	Hussain Khan.		Rs. 12,000	De.	
	Mohammed.		Rs. 11,001	De.	
	Tongwall.		Rs. 12,784	De.	
	Lakha Mithabhai.		Rs. 12,307	De.	
Mirali	Mohammed.	12	Rs. 10,745	Jat and Dugar.	
	Khus Dali Singh.		Rs. 2,207	Jat.	
	Sohna.		Rs. 11,457	De, Hala, and Dugar.	
	Mohammed.		Rs. 10,460	Jat.	
	Wara Waram Singh.		Rs. 22,007	De.	
	Dalal.		Rs. 12,000	De, and Arain.	
	Lalland.		Rs. 1,200	De.	
	Mohammed.		Rs. 1,200	De.	
	Mohammed Khan.		Rs. 1,200	De, and Nagari.	
	Kutla Khan.		Rs. 1,200	De.	
	Hussain.		Rs. 1,200	Hajeri and Arain.	
	Mohammed Jit Singh.		Rs. 1,200	Arain.	
	Mohammed.		Rs. 1,200	De, and Jat.	
	Mohammed.		Rs. 1,200	Jat and Dugar.	
	Dalawali Nigdian.		Rs. 1,200	Hajeri and Arain.	
	Kimder.		Rs. 1,200	Jat and Arain.	
	Mohammed Hisham.		Rs. 1,200	De.	
Mirali	Guru Dala Sabha.	18	Rs. 1,112	Hilala, Khatri, Japp, An.	
	Kanekwala.		Rs. 1,000	De.	
	Gulabwala.		Rs. 1,000	De.	
	Mohammed.		Rs. 1,000	Hilala, Khatri and Jat.	
	Mohammedwala.		Rs. 1,000	Khatri and Jat.	
	Mohammed.		Rs. 1,000	De.	
	Mohammed.		Rs. 1,000	De.	
	Dalal.		Rs. 1,000	Dugar.	
	Zor Bal.		Rs. 1,000	De.	
	Mohammed.		Rs. 1,000	De.	
	Mohammed.		Rs. 1,000	De.	
	Khatma.		Rs. 1,000	De.	
	Bugga.		Rs. 1,000	De.	
	Himayat.		Rs. 1,000	Walia.	
	Pangjani.		Rs. 1,000	Hilala and Dugar.	

## Chapter III. D.

*List of villages in the District of Ferozepore as they stood in 1888-89—concluded.*

Village  
Communities  
and Tenures.  
Village officers.

Tablet.	Name of village.	Number of villages.	Average land revenue.	Possessing cases of proprietors.
	Lahore.	1	Rs. 1,120	Dugar Musselman, Waria.
	Sohar.	1	Rs. 1,270	Do.
	Batra.	1	Rs. 1,080	Do.
	Hira.	1	Rs. 1,280	Hajrat Musselman, Waria.
	Gallanwala.	1	Rs. 1,170	Do.
	Mohammed.	1	Rs. 1,000	Do.
	Guru Nanak.	1	Rs. 1,120	Do.
	Khanda.	1	Rs. 1,000	Do.
	Khalidkot.	1	Rs. 1,000	Do.
	Khan.	1	Rs. 1,000	Do.
	Qayam.	1	Rs. 1,000	Do.
	Jandial.	1	Rs. 1,000	Do.
	Kasur.	1	Rs. 1,000	Do.
	Tarwala.	1	Rs. 1,000	Do.
	Zaujan.	1	Rs. 1,000	Do.
	Mohammed.	1	Rs. 1,000	Do.
	Waria.	1	Rs. 1,000	Do.
	Malik.	1	Rs. 1,000	Do.
	Abdullah.	1	Rs. 1,000	Do.
	Imdad Khan.	1	Rs. 1,000	Do.
	Khanum Khan.	1	Rs. 1,000	Do.
	Khawaja.	1	Rs. 1,000	Do.
	Khurram.	1	Rs. 1,000	Do.
	Abdul.	1	Rs. 1,000	Do.
	Cow.	1	Rs. 1,000	Do.
	Khuda wali.	1	Rs. 1,000	Do.
	Khadwala.	1	Rs. 1,000	Do.
	Waria Khan.	1	Rs. 1,000	Hajrat Musselman.
	Omar.	1	Rs. 1,000	Do.
	Jandial.	1	Rs. 1,000	Do.
	Patta Khan.	1	Rs. 1,000	Do.
	Gullwala.	1	Rs. 1,000	Do.
	Lahor.	1	Rs. 1,000	Do.
	Waria.	1	Rs. 1,000	Do.
	Haider.	1	Rs. 1,000	Do.

## Village dues.

The village dues are dues paid by the non-agriculturists to the *sunshades* for the privilege of drawing water out of the village wells and cutting wood and grass in the village lands; the usual rate is from about eight annas to two rupees for each shop. This tax is assessed principally on the baniyas, the khatrias, the jutahars, mochis, &c.; the lowest caste as the sweepers, hawarials, &c., are exempt. Such other extra taxes, as the marriage fees in the Dugar villages, were often a subject of great dispute. All the other castes in the village pay a fee to the Dugar proprietors whenever a marriage procession comes to any of their houses; but the Dugars were often in the habit of exacting larger sums than they were properly entitled to if the parties married were able to afford it, and they would call their brethren together and pestle the procession and prevent the celebration of the marriage until their demand was paid.

On the well-irrigated villages the *laminis* are the *tarkha* (carpenter), *tumbir* (potter), *wâr* (blacksmith), and *chûcha* (sweeper). Elsewhere the potter is not considered a *kâmia*. The

carpenter has to make and keep in repair the plough and yoke, the rakes, *whipā* (harrow), and handles of all sorts. In well-villages he has besides to repair the wood-work of the well. He has also everywhere to mend the bedstead, the spinning-wheel, the chairs, and the churning-staff. He is paid two *manū* (*tapa manū*) per well each harvest, or, where there are no wells 2½ *manū* per plough each harvest, if the outturn is not less than 100 *manū*. If it is, he gets one *śir* in the *manū* produced. The *kumhār* is paid as the *tarkhan*. He has to supply the pots of the well, and a few dishes and cups and milking-pots, twice a year. The blacksmith makes and repairs the ploughshare, the trowel, reaping hook and hatchet. He also repairs the shawl-mattock. He is paid by the tenant at one-half the rate of the carpenter's pay. The *chukra* has no fixed duties, nor is his pay fixed. He has to make himself generally useful and do his master's *bāgar* labour. He is paid according to the amount of the harvest. In case of dispute, his wages are calculated at five per cent. of the outturn. Besides these dues and the owner's *mālikdar* or *malba*, a deduction at varying rates, calculated on the proprietor's share, is made from the produce before division on account of the *dharīmī* or weighman, and also on account of the *maħazzī* or watchman. The deduction made before division of the produce amounts approximately to 10 per cent., varying from 9½ to 10½. The *kumhār* are usually paid in grain after it has been separated from the straw in the manner before described, with the exception of the *lōkīwāls* or reapers, who cannot of course wait so long, as they often come from a distance merely to do the reaping work. Their remuneration is generally a certain number of *sheaf*s, of which each reaper gets about 24 for a day's work; a *sheaf* or *phāṭī* is the quantity tied up with a single straw. For reaping pulse or such crops as are not sheathed, he gets a *lāḍī* or heap of a certain weight; sometimes, however, he gets previously stored grain of a quantity equal in value to about two annas a day. In some villages the cultivator is not allowed any reapers for the autumn harvest, but is obliged to sent it himself. In cotton fields, the blacksmiths, the carpenters and the potters are remunerated by their wives being allowed to pick as much cotton as they are able in one day. In some estates the cultivator may put on as many reapers as he pleases; in others he is restricted to a certain number for each plough.

The subject of the employment of field labour, other than that of the proprietors or tenants themselves, was thus noticed in answers furnished by the District Officer and inserted in the Famine Report of 1879 (page 717):—

"Field labourers are employed for ploughing, sowing, reaping, threshing, and winnowing. They are more employed in the high-unirrigated tracts of the district, where holdings are large, than in the *īr* or khadar lands near the river, where holdings are small and the agriculturists not so well-to-do; but, as a rule, throughout the whole district they are generally employed. They consist of the menial classes, chiefly *chātrīs*, &c., and are paid both in cash and in grain, more commonly in grain. When they are paid in cash, they receive Rs. 2 a month and their food.

## Chapter III D.

Village  
Communities  
and Tenures.

Kasias; their  
duties and duties.

Agricultural  
labourers.

**Chapter III, D.**

Village  
Communities  
and Tenures.

Agricultural  
labourers.

Petty village  
grantees.

When in grain, they receive from one-fourth to one-fifth of the produce of the field on which they work. When field labour is not required, they work on canals, roads, &c. A few of them are of the artisan classes, such as weavers, and fall back on their domestic trade; but, as a rule, the grain payment received by field labourers is enough to support them and their families for the whole year. They hold their grain in hand, and do not make it over to the village bazaar, who would be unwilling to give them credit, and in this district their condition is distinctly inferior to that of the poorer agriculturists. Estimated number about 1½ per cent. of the population."

The wages of labour prevailing at different periods are shown in Table No. XXVII, though the figures refer to the labour market of towns rather than to that of villages.

The last two lines of Table No. XVI show the number of persons holding service grants from the village and the area so held. But the figures refer only to land held free of revenue, which is by no means the only form which these grants assume. Sometimes the land is leased to the grantee at a favourable rent, or on condition of payment of revenue only; sometimes the owner cultivates and pays the revenue, making over the produce to the grantee; while occasionally the grant consists of the rights of property in the land, which, subject to the usual incidents, such as responsibility for revenue and the like, vest in the person performing certain specified services at such times and for so long as he performs them. These grants are most commonly made to village menials and watchmen on condition of, or in payment for, services rendered to attendants at temples, mosques, shrines, or village rest-houses, so long as they perform the duties of the post, and for maintenance of monasteries, holy men, teachers at religious schools, and the like.

Poverty or wealth  
of the proprietors.

Table No. XXXII gives statistics of sales and mortgages of land; Tables Nos. XXXIII and XXXIIIA show the operations of the Registration Department, and Table No. XXIX the extent of civil litigation. But the statistics of transfers of land are exceedingly imperfect; the prices quoted are very generally fictitious; and any figures which we possess afford but little real indication of the economical position of the land-holders of the district.

The income of the population, whether agricultural or commercial, is steadily increasing. The general prosperity of the district is great, and the price of land constantly rising. Owing to the coparcenary family system it is difficult to fix the ordinary income of an agriculturist. One, however, whose share amounts to 10 *ghumiat* (= 9 acres) of average land is certainly in comfortable circumstances, and lives quite as well as a small shop-keeper in a town. The average expenses of an ordinary agriculturist in ordinary times may be put at from Rs. 2-8-0 to Rs. 3 per month. The food is of the simplest, girdle cakes (*chappatis*) of meal, buttermilk and greens; and the drink, water. On occasions of festing, for betrothal, marriage, funerals, or other religious and social gatherings, sugar (*gur*) and sweetsmeats are lavishly distributed. These, indeed, are the chief, or only,

extraordinary expenses of the peasantry ; but by pernicious custom they are often so heavy as to plunge them into debt, and even lead them, when once in the hands of the money-lender, to utter ruin. A peasant who has an account with the village money-lender is, owing to the want of education, very much at his mercy. At the same time, probably only a small percentage of the agricultural population is helpless involved. The money-lending business of the riverside tract is concentrated in the hands of a few wealthy merchants living in the towns, but in the upland tracts the money-lenders are as often as not of the agricultural class themselves. The usual rate of interest for cash loans is about 24 per cent., but 37½ per cent. is a common rate, and occasionally as much as 75 per cent. is taken. It is a common practice to stipulate that the money lent may be repaid without interest within six months ; but in these cases a deduction is generally made at the time of the loan. Debts are to a large extent secured under the Registration Law. In loans of grain the interest charged is higher ; and the money-lender almost always makes a large extra profit by crediting payments in kind at a much lower rate than that at which he calculates the loan. When ornaments are pledged, 12 per cent. is the current rate of interest ; when land is mortgaged, a share of the produce is commonly taken in lieu of interest. The mortgagee generally stipulates for the right to arrange for the cultivation as he pleases, but in practice the owner usually retains possession.

Chapter III, D.

Village  
Communities  
and Tenures,Poverty or wealth  
of the proprietors.

## CHAPTER IV.

## PRODUCTION AND DISTRIBUTION.

## SECTION A.—AGRICULTURE AND LIVE-STOCK.

## Chapter IV. A.

Agriculture  
and  
Live-stock.

**General statistics  
of agriculture.**

**The seasons : Rain-  
fall.**

Table No. XIV gives general figures for cultivation and irrigation and for Government waste land; while the rainfall is shown in Tables Nos. III, IIIA and B. Table No. XVII shows statistics of Government estates. Table No. XX gives the areas under the principal staples, and Table No. XXI the average yield of each. Statistics of live-stock will be found in Table No. XXII. Further statistics are given under their various headings in the subsequent paragraphs of this chapter. Land tenures, tenants, and the employment of field labour have already been noticed in Chapter III, Section D.

The total annual fall of rain and the manner in which it is distributed throughout the year are shown in Tables II, IIIA, IIIB.

The subjoined table gives the dates of sowing and reaping or picking the principal articles of produce:—

Agricultural Seasons.

Name in English.	Name in Vernacular.	Time for sowing.	Time for reaping or picking.
Wheat.	Kank.	October.	April.
Barley.	Jor.	September.	March.
Gram.	Chana or chola.	Do.	Do.
Poony.	Puri.	Do.	Do.
Tobacco.	Foska.	December.	May.
Linseed.	Ali.	October.	April.
Mustard.	Narm or aram.	Do.	March.
Simpao grass.	Tundia.	September.	Do.
Rice.	Khira or nargi.	April.	November.
Great millet.	Jando or jorai.	June.	December.
Spurred R.	Jalai.	Do.	December.
India corn.	Methi or muthi.	Do.	November.
The cereal commellinae.	Muthi.	Do.	December.
Do. radish.	Muthi or muthi.	July.	November.
Do. mungo.	Mury or mury.	Do.	Do.
Bermuda.	Til.	June.	December.
Cotton.	Kapda or kapdi.	April.	Do.

## Irrigation.

Table No. XVI gives details of irrigation. Further information will be found at pages 177 to 203 of Major Waca's Famine Report, compiled in 1878. At that time 3 per cent. of the cultivation was irrigated from canals, 11 per cent. from wells, 3 per cent. was flooded, and the remaining 83 per cent. was wholly dependent upon rain. The following statement shows

the number of wells then existing in the district, with certain statistics regarding them:—

Number of wells	Depth to water in feet.		Cult in acres—		Bullocks per wheel or trotter.		Rate per acre	Days irrigated per wheel or trotter.	
	From	To	Masonry	Without masonry	Number of pairs	Cult in rapese		Spring	Autumn
300	20	25	12	12	12	120	12	2	2
4,000	20	30	12	12	12	120	12	12	12
1,200	30	35	12	12	12	120	12	12	12
911	30	35	12	12	12	120	12	12	12
62	30	35	12	12	12	120	12	12	12
4	Above	35	12	12	12	120	12	12	12

In this *het* the Persian wheel is always the apparatus used for lifting water from wells for irrigation, while in the uplands the wheel is never used, its place being taken by the pulley and leather bag. These two methods of working and the apparatus employed are too well known to require description. The bag and pulley is certainly more mechanically efficient than the wheel—that is to say, it lifts much more water for a given expenditure of power, unless the lift is very short, in which case the time lost in fixing and unfixing the drawrope counterbalances the more advantageous application of the power. But there are two reasons against the use of the bag in the *het* besides that of the lift being short. One is that it requires more men and animals to work a well continuously on the pulley system, and that the work is much harder for the men employed. The second is that the wells in the *het* will not generally stand the wear and tear caused by the working of the leather bag. They are mostly founded on a bed of sand, and the suction of the bag as it is withdrawn from the water brings in sand with the water from under the foot of the steering, thus undermining the well. The Persian wheel can hardly be used when the lift exceeds 10 feet, as is generally the case in the *het*. A good sized well may have as many as four pulleys to work at the same time. A pulley is called *ridh*, and a well is described as *do-ridh*, *char-ridh*, &c., according to the number which it mounts. Or it may be fitted with two Persian wheels, all the tackle of each set of wheels being quite distinct, and the two chains of pots working about a yard apart in the middle of the well. A well with two sets of wheels is called *dohartsa* or *dohatta*. It may be mentioned that the name of the large cross beam (*kājan*), to the middle of which the upright spindle of the driving wheel is attached, is in rural language often put for the whole well. Thus the well assessment is often spoken of as so much on each *kājan*. In the *roki* a single pulley requires 6 pairs of good bullocks and 6 men to work it for the 24 hours continuously. In that time it will water about 10 *kandis*, or a little more than an acre, with a lift of 40 feet. The Persian wheel requires 3 pairs of ordinary bullocks and 2 or 3 men, and will water in 24 hours with a lift of 18 feet about 8 *kandis*, but not more than 5 or 6 *kandis* are generally accomplished in the day.

## Chapter IV. A.

Agriculture  
and  
Live-stock.  
Irrigation.

**Chapter IV. A.**

**Agriculture  
and  
Live-stock.  
Inundation  
canals.**

The method of irrigation on the inundation canals, which have been fully described at pages 5 and 6, is almost by flow. The water is distributed by small water-courses made by the people themselves, the openings in the canal or branch canal being arranged by irrigation establishment. There is no regular system of major and minor distributaries.

A small proportion of the acreage is irrigated by lift, i.e., *jhallars* or *jhatta*. The latter means, however, is very seldom adopted. The *jhallar* is merely a Persian wheel of small lift working in the canal instead of in a well. *Jhatta* is lifting the water by means of a scoop which is swung by two men. These canals run for about five months in the year, i.e., from May to September, and give sufficient water for maturing the kharif crops and sowing the rabi, and it requires only a shower or two in the cold weather to ripen the latter.

**Soils.**

Natural soils are distinguished from one another in this district merely by the greater or less proportion of sand which they contain. In the Kot-Kapura plateau the firmest loam contains at least 50 per cent. of sand. This soil is called *karrar*, meaning *hard*. Where there is more sand, say 75 per cent., the soil becomes lighter in colour and more friable. It is then called *dair*. A clod of *karrar* in the *rohi* will generally break when trod upon; a lump of *dair* will hardly feel muddy when wet, and when dry will break up into dust if dropped on the ground. If the sand has so little clay mixed with it that it does not form lumps at all when ploughed it is called *tibbi*. Land with a surface of *tibbi* is sometimes very fertile if it has a harder stratum below. Such land is called *doshah* or *dorukha*, but these terms are sometimes applied as meaning merely an intermediate sort of soil. Almost pure sand will grow gram, and even a little wheat, and the more sandy the soil the less it suffers from drought. In the driest season the sand will be found to be moist at a foot or so below the surface. Apparently the more coarsely divided sand having less power of capillary attraction than fine clay, the water it contains is not all passed up to the surface as it is in the case of clay when the surface dries, and so it escapes evaporation. The coarser sands, however, are unsuited to the growth of plant roots. In the *bet* the stiff clay is called *karrar* as in the *rohi*, but the *bet karrar* contains only 10 per cent. of sand. It is very soft when wet, and extremely hard when dry, so much so that the cloots will resist even the tread of a horse. A mixture of sand greatly improves the physical quality of such soil, making it much easier to work, less quick in drying, and less at the mercy of the weather, and it does not perceptibly detract from its fertility until the proportion of sand reaches about 40 per cent. Such soil is called *gassi* or *gassa*. It corresponds to the *rausli* of the Delhi Division, as the *karrar* soil does to the *Dihli dhaisar*. The sand of the *bet* is, however, sterile in itself, having had all its soluble parts washed out of it by the river. A decidedly sandy soil (*re*) in this tract has

therefore little value. The worst soil, however, is formed by a layer of a few inches of hard clay resting on a bed of sand below. Such soil is hard to work, and returns a scanty yield. Being very quick to dry, it is only in the most favourable season, when showers fall just as they are wanted, that it repays its cultivator.

The agricultural system of this district may be divided into two parts, viz.:—

Chapter IV. A.  
Agriculture  
and  
Live-Stock.  
Soils.

*1st*, simple cultivation, such as can be carried on by means of the annual rainfall only; and

*2nd*, superior cultivation, requiring a regular artificial supply of water.

Superior cultivation has hitherto been almost confined to well lands in the western part of the Zira Bet, to a few wells in north-eastern Moga, and to the immediate neighbourhood of Ferozepore. But the introduction of perennial irrigation from the Sirhind Canal in the Moga and Mukatsar tahsils is introducing a certain extent of superior cultivation into some of the richer villages of the upper zohi.

The simple agriculture consists, broadly speaking, in preparing the ground by several ploughings to receive the autumn rains, and sowing in October wheat or barley, mixed with gram, and, if possible, some oilseeds. This crop is sustained by the rain which usually falls about Christmas. After reaping it in April the stubble is ploughed, and as soon as the second autumn's rains begin a crop of millet mixed with lentils is sown, which ripens in October. This completes the course. The agricultural year runs from June to June, and the process would re-commence by ploughing in the third summer and autumn for a spring crop in the third cold season. Thus in every period of two years the land is in the first year (commencing from June) for five months in a state of preparation and for seven months under a spring crop, and in the second year it is for five months under an autumn crop and seven months lying fallow. The spring crop is called *Hari* (*Rabi* in Persian) because it is cut in the month of *Hár*, and the autumn crop is called *Sawan* (*Kharif* in Persian) because it is sown in the month of *Sawan*. The cultivator will not put his whole land under a spring crop in one year, and the whole of it under an autumn crop in the second year, for he requires some of the produce of both crops for the food of himself and his cattle. The autumn crop furnishes a large stock of fodder in the leaves and stalks of the *jowar* (*Sorghum vulgare*), which is the kind of millet most grown, and the seed of the *jowar* forms with the pulse accompanying it the principal food of the cultivator during the cold season. He must, therefore, put about a third of his land under kharif crop in order to supply his immediate wants. The rabi crop produces more marketable grain than the kharif, and it is on this crop that the cultivator mainly relies to bring in the money for such demands as have to be paid in cash. The fodder also of the rabi crop, consisting of the pounded

two-year  
course, rabi and  
kharif.

**Chapter IV, A.** straw of the cereals and grain, is good though not so plentiful as that of the late kharif crops, so the cultivator will reserve two-thirds of his land for rabi. On harvesting this rabi he will of course sow only half the stubble (one-third of his entire holding) with kharif, and will plough the remainder thoroughly for a rabi crop to be sown after the rains.

**Agriculture  
and  
Live-Stock.**

The two-year  
course, rabi and  
kharif.

This system of working the land is to be seen to perfection in the northern and eastern parts of the Moga-Taluk, and also on most of the lands irrigated by the inundation canals. In the south-west of Moga and in the Muktsar uplands, where the climate is less propitious, the kind of crop sown depends less upon the needs of the animals, or the preceding cropping, and more on the vicissitudes of the season. If there is no good rain between August and October the ground will hurriedly have moisture enough for the reception of the rabi seed, and it will therefore lie fallow for that season. If the next rainy season commences early the cultivator will then sow more than his usual area of kharif to make up for the deficiency of the past year, rather than reserve so much for rabi. If, on the other hand, the rains have been bad and the kharif has failed, but good showers fall later in the autumn, he will put in all the rabi seed that he can as long as there is a chance of its having time to produce grain. In the extreme south of the district it is here the practice to wait for a rabi crop. As soon as the rain falls in July they hasten to sow as much as possible with kharif, not venturing to let go this opportunity in the hope of a more valuable crop in the cold season. This feeling is probably justified by great uncertainty on the occurrence of the winter rains, which are essential to rabi cultivation. Among the Bagri inhabitants of the adjoining parts of Hissar the practice of growing rabi has only recently been introduced, and in Bikaner it is still unknown. Thirty years ago Moga was in the same stage in this respect as Faridkot is now. The kharif crop then occupied twice the area of the rabi. The gradual extension of rabi cultivation is a decided gain. It is this which has enabled Ferozepore to become a great grain-exporting district, for the kharif grains do not store well and are in no demand in Europe. As the distance from the hills increases the proportion of wheat tends to decrease, its place being taken by barley. Jowar is also gradually displaced by bajra (*Pennisetum typhoides*). In the sandier parts of the tract below the greater bank the soil is not firm enough to support the heavy stalks of the millets, and no kharif can be grown except moth (*Phascolus acutifolius*). Barley does not thrive well in this soil, and it will not grow rape. Hence the rabi is mainly wheat and gram or gram alone. Owing to the insufficiency of the kharif fodder a good deal of the rabi crop has to be cut green for the support of the cattle in the spring. The cultivators generally treat land which has been flooded by inundation canals just as they would treat ordinary land after a heavy rainy season. Two-thirds of it

is reserved for a rabi, and the remaining third is usually sown with *jowar* and lentils. The superior cultivation is not distinguished from the simple cultivation so much by the use of artificial irrigation as by the use of manure. Land under simple tillage is very seldom manured. Except on the north-east, where the rainfall is heaviest, manure would not be beneficial, as it would have too heating an effect. The crops ordinarily produced are not so heavy as to exhaust the soil, and it may be cultivated on the two-year course, with occasionally an involuntary fallow caused by want of rain, for an almost unlimited length of time. It is doubtful whether it will retain its fertility long if well watered and cropped regularly without putting on manure, but probably no harm will be done until the attempt is made to grow two crops in the year. All irrigated lands are not highly farmed, not even all well lands. In the north-east of the district rainfall is sufficient for ordinary tillage, and a well is a luxury. The land under it is carefully manured, and is devoted to growing superior crops. But in the west of the Zira Tahsil and in the whole of the Ferozepore Tahsil the hard clay soil of the *bet* requires water to enable it to grow even ordinary crops in dry years. The well becomes a necessity instead of a luxury. Its water is spread over as large an area as possible, and one well is sometimes found to have as much as 40 or 50 acres of wheat dependent on it. Of course only one or two waterings in the season can be given. Manure cannot be provided for so large a surface. The crop is hardly heavier than is produced on good land in the Moga plateau by means of the natural rainfall. This is, in fact, the ordinary simple cultivation, with only this difference that a well is employed to make up for the want of rain. The light upland soils, however, of these two tahsils, Zira and Ferozepore, can do very well with the quantity of rain they ordinarily receive, for they retain moisture much better than the clay, and are always in a workable condition. In their ability to resist drought, the soils of the lower *roki*, or Mukti plain, have an advantage even over the better soil of the Kali-Kapura plateau. In Mandot the rainfall is less than in the Ferozepore *bet*, and there are few years when a crop worth laying could be raised in that tract without other aid than rain. But the Mukatsar *roki* is secure in two years out of three. In Fazilka there is no unirrigated cultivation whatever in the *bet*. In the *roki*, droughts are common, and in the extreme south-west cultivation without water is so precarious that the land can hardly support its own population, and yields but a nominal rate of revenue. It may be said, as a rough generalisation, that the drought-resisting power of the *roki* soils, as compared with that of the *bet*, gives it no much security as would be obtained in the *bet* by an approach of about 20 miles towards the hills, and this is equivalent to about 4 additional inches of rainfall. In the drier parts of the uplands the rainfall is so small that it is necessary to collect the water which falls on two acres in, order to grow a crop in one acre. Therefore, the agriculturist reserves, if possible, a plot of waste with a firm unbroken surface at the head of his

**Chapter IV. A.****Agriculture  
and  
Live-Stock.**

The two-year  
course, rabi and  
kharif.

**Chapter IV. A.****Agriculture  
and  
Live-Stock**

The two-year  
course, rabi and  
kharif.

cultivated land, and leads the water by small banks and cuts into the lower fields. In 1850, when Mr. Brandreth wrote, this practice prevailed in the Māri pargana and in the southern part of Mukatsar. It was deemed so essential by that officer that he left unassessed in every village an area of waste land equal to the area of the cultivation. Since his time, however, the waste land in Māri has all been brought under the plough. In Mukatsar, Mr. Purser, in 1872, found that half the waste area of Mr. Brandreth's Settlement had been broken up, and that about three-fifths of the whole pargana was cultivated. He himself thought that the extension of cultivation had reached its limit. But in the past 17 years the waste land has been again reduced by one-half, and is now only one-fifth of the whole area.

**Superior cultivation.**

Superior cultivation may be said to begin with the growth of maize, which introduces the double-cropping system. Maize is always heavily manured, otherwise it will not send well. It also receives some amount of after-tillage, viz., hoeing and weeding, which processes are never thought necessary in the simple agriculture of the unirrigated plains. The maize is sown off the ground than most other kharif crops, and the ground is left with a stock of fertility upon which further demands may be made. Wheat can, therefore, be sown immediately after it in the same agricultural year, and by means of irrigation can be brought to fruition by the same time as other wheat. This is the only form of double cropping which is practised in the uplands. It must not be supposed that the whole of the land irrigated is doubly cropped. On the walls in Moga, the maize crop covers only about 40 per cent. of the irrigated area. In the remainder, the land is fallowed and ploughed in the kharif season in preparation for a better crop of wheat in the rabi. The crop which follows a fallow is called *sānai*. The wheat grown on the kharif stubble (*wādhi*) is called *wādhi*. Its value is diminished by the partial exhaustion of the land by the maize, by the want of sufficient tillage between the two crops and by the lateness of its sowing time, and it is generally said that the one crop of *sānai* wheat is equal to the maize and the *wādhi* wheat taken together. The maize is not always grown in the same plot, but is shifted round the whole irrigated area, and thus each part in turn gets the benefit of manure. This resembles the English practice of manuring heavily for a "green-straw" crop, viz., roots, potatoes, mustard, and following with a "white-straw" crop, viz., wheat or barley. A part of the rabi area is generally sown with barley, which is cut green to feed the wall bullocks, and as this part is cleared soonest it is generally arranged that it shall precede the maize. The maize is at times partially replaced by *jauar*, as the latter yields much better cattle-fodder than maize.

The maize-wheat course is adopted to some extent on the inundation canals, where the supply of water is fairly constant. But as the inundated lands are too extensive to be thoroughly manured, and are never properly weeded, the maize is mostly

poor, and the wheat also. It is indeed seldom worth while to sow wheat; *sesji* (trichoi) for fodder does better for the second crop. When there is a superabundant supply of canal water rice is grown. This crop is cut before the land is quite dry, and so it is possible to follow it with a rain crop. But the preparation has to be very hasty, and the soil, coming up in large lumps after it has been puddled by the rice cultivation, cannot be got fine enough for a good crop of wheat. Gram is the proper grain to follow rice. But as neither rice nor gram furnish fodder for the cattle, wheat has often to be grown, whether the soil be fit or not. On the wells in the eastern part of the Zira *bed* a more varied tillage is seen. Cotton is grown and chillies, also small patches of sugar-cane, and in some places onions and other vegetables. Tobacco is grown by the Mosalmans (though not by the Sikhs) as a late stubb crop.

The manure used is the village sweepings and ordinary farm-yard manure; some of the cattle dung, however, being set apart for fuel. The people have not yet learnt to take proper care of their manure. They allow it to be scattered about the outskirts of the village to dry up in the sun, and to be blown about by the wind until more than half of it is lost or spoiled. In the south of the district, where irrigation is only of very recent introduction, many of the villages are partly built upon accumulations of their own sweepings several feet in thickness. Bones are quite neglected. Large quantities of bones have in the last two or three years been sold for export to Europe to the advantage of the sweepers, who are the only caste that will touch a bone. Far more farm-yard manure might be collected if the cattle were regularly littered with waste grass, &c., &c. But they are usually allowed to lie on the bare ground, so that the liquid manure soaks into the floor of the yard. Land near the village habitations naturally receives a fairly plentiful supply of night-soil, but here again waste occurs by this valuable manure being dropped on uncultivated ground close to the houses, where it is a nuisance instead of a source of profit.

The plough used throughout almost the whole of this district is the *mansas*. A drawing of this plough is given at page 36 of Mr. E. L. Braundreth's Settlement Report of 1855, but the edges are shown as too square, and the *mansas* itself, the upright stock of the plough, as somewhat too heavy. Moreover, the whole stock up to the handle is not formed of one piece of wood, the thin upper part or shaft is separate from the thick lower part which bears the strain of the work. The sole of the plough is a movable wedge called *chasi*, and to the upper surface of this the coulter (*plaili*) is attached by rings, and projects at the point of the wedge sufficiently to enter the ground. The plough does not invert the soil like the mould-beard of the English plough, nor would it be an improvement if it did, for the agriculturist here wishes merely to pulverize his land without exposing it more than he need to the drying influence of the air. The *hal*, properly so called, which is also shown in

**Chapter IV. A.****Agriculture  
and  
Live-Stock.  
Ploughing.**

Mr. Braudreth's drawing, is used only by Mussalmān cultivators in the new alluvial land of the riverside villages. The bullocks pull by a yoke, to which the front end of the plough beam is tied. It is this beam to which the name *hal* specially belongs. *Hal* is also used as a generic term even where the form in invariably used is the *manna*. Ploughing is sometimes done in bonds, up and down the field, as in England, the plough always returning on a furrow at a sufficient interval from the one by which it went to give the bullocks room to turn. But sometimes the ploughman begins with a furrow all round the edge of the field, and on completing the circuit makes another just within the first, and so on, working inwards until he has sited up the whole space. The points at which he turned his plough, forming four diagonal strips called *chund*, have not been ploughed so deep as the parts where the plough was going straight, and so he ploughs up and down these strips a second time. The whole, when done by a good ploughman, has a very neat appearance. This style of ploughing, called *ghera*, is always adopted at the last ploughing when the seed is sown, so that none of the ground should be gone over twice.

**Other agricultural  
operations.**

After ploughing, the clods are broken and the surface smoothed by drawing over it a flat beam, called *sahda* or *swiga*. This is pulled by two pairs of oxen, and is weighted by the drivers standing on it. Land retains moisture much better after it has been smoothed by the *swiga*, but it is not advisable to leave the land long in this state after finishing the ploughing, and before sowing it, for if rain were to fall it would cause the surface to cake, so that a further ploughing would be needed. The proverb says that one application of the *sahda* is equal to 100 ploughings. Stiff soil cannot be ploughed until it is in a moderately moist condition called *matar*. When quite dry it is too hard to be broken up by the ordinary implements and average cattle. It gets into the proper state in the second or third day after a heavy rain or an artificial flooding. If touched sooner it will form into hard clods like bricks, which will resist all attempts to pulverize them. If the seed is not put in before this moderate degree of moisture has disappeared it will not germinate. The stiff soils dry quickly, more especially if they have a sandy stratum below. In such lands, a cultivator who has an insufficient staff of men and animals, or who is impeded by illness or other interruptions to his work, will often be unable to get all his land sown before the propitious time has slipped by. Sowing is done either by hand, broadcast, or by drill. The drill is a single hollow bamboo with a cup-shaped enlargement at its upper end. This is tied to the stock of the plough, the lower end just in the ground, and the cup end at the level of the driver's hand. He carries the seed in a cloth strung round his body, and drops it into the cup, making each handful go to a certain number of paces, according to the nature of the seed. More seed is sown when the ground is dry than when it is moist, and more when the sowing is late than when it is done at

the best season. Less seed is sown in sandy soil than in firm land. Occasionally the seed is thrown broadcast on the surface of the ground before ploughing, and is afterwards ploughed in. When sowing with the drill a stick is sometimes dragged behind the drill for the purpose of covering the seed. But this is not always necessary.

In dry soil a shower of rain after the land has been sown, and before the young plants have emerged from the ground, often does considerable damage. The surface of the land dries into a sort of crust which prevents the seedlings coming up. Barley suffers most from this cause and wheat less, while gram, having a large seed and a strong shoot, is generally able to burst its way through. This incrustation is called *barand*. The people have no suitable implement like a harrow with which to break up the surface, and generally resort to raking the land, which is of course a serious expense. To form land into compartments for irrigation the soil is collected into ridges by means of a rake (*jhandra*), which is pulled by one man by means of a cord while it is pushed by another. The compartments are formed after the seed is sown. For well irrigation they are generally not more than one-tenth of an acre in extent, and even smaller where the surface is uneven, for no compartment should have a difference of level or more than three or four inches within its limits.

For irrigation from the Sirhind Canal compartments of about a quarter of an acre are required by rule before water is supplied. On the inundation canals this matter is seldom attended to. Lands which depend on rainfall are laid out in still larger blocks of, perhaps, an acre to ten acres, according to the slope. Hoeing is done with a spud (*rumba*, *thurpi* or *khurpi*) with a short handle. It is used in a squatting position, the labourer moving along without rising.

The instrument for cutting crops of all sorts is the sickle (*libriti*), which resembles the English sickle in shape, but is serrated like a saw, the teeth bending backwards. The sickle is the only substitute for a knife which the rustic possesses, and any surgical operation which he requires to perform on his cattle is generally executed with a sickle, its want of keenness being remedied by making the metal red hot. For cutting up fodder a heavy chopper is used called a *gandara*.

Small wood for fuel or other purposes is cut with the *kohiri*, which is a very small axe on a long handle. For all traction work which has to be done by bullocks, a yoke (*penjidi*) is used, consisting of two bars about 6 feet long joined together by four cross bars about 1½ feet long, which form two loopholes. The two outer bars pull out to admit the bullocks' necks into their proper loops, and are then tied in their places by ropes or strings.

For levelling ground and also for digging shallow canals, a bullock-shovel (*karai*) is used. The ground being first ploughed up, the edge of this shovel is thrust down into the earth, and takes up a load of it when the bullocks pull.

**Chapter IV. A.****Agriculture  
and  
Live-Stock.**Other agricultural  
operations.

Ordinary digging is done with the shovel-mattock, as it has sometime been called, which is merely a large hoe. It is called *taki* or *kassi*. For grubbing up roots a stronger mattock, with a narrower blade called *kodili*, is used. The pitchfork (*sarrang*)—if with more than two prongs called *trangali*—is used to move thorns, to gather up corn on the threshing-floor, and also to beat out grain, *muth* and some other grains which do not need treading by bullocks.

Winnowing is done roughly with the pitchfork, and afterwards finished with the *chajj* or *chajti*, a shallow scoop made of bits of reed fixed side by side.

Thinning is done in any ordinary vessel by means of a churing stick called *mallana*. This has two small cross pieces of wood at the lower end; the upper end is secured in an upright position by a loop of string tied to any handy support, and is twirled by another string which is wound round it.

**Carts.**

The uplands of this district are famous for their bullock carts. The ordinary work of the agricultural year under the simple system of agriculture does not occupy the upland peasantry for the whole twelve months. As soon as they have done their harvest work they and their cattle are free for three months. They therefore frequently go out on trading expeditions to distant markets. Their carts consist of a long triangular framework, about twelve feet long and four feet wide behind, but tapering to a point in front. This is supported upon two triangular inverted brackets, the lower points of which form the bearings in which the wheel axles turn. The load lies between the wheels, and is not raised above them as in the Jullundur pattern of cart. The triangular framework is made with great care of many pieces of picked wood, and is generally strengthened in every possible place by plates of iron. Sometimes it is ornamented with brass work, and may cost as much as Rs. 300. No extra trouble or cost however is bestowed upon the wheels. They are only expected to wear for a limited time. The yoke is tied on the projecting back of the cart-body by thongs of raw hide. An ordinary cart with a pair of fair bullocks will carry about 16 maunds. A third bullock is often attached in front by tape traces. A large cart with four bullocks, viz., two under the yoke and two leaders pulling from a loose yoke, will carry as much as 40 maunds. To hold a load of loose stuff such as grain a number of uprights are fixed into the edge of the framework, and a wall of sacking is stretched all round it. Sometimes curved bars are fixed to the tops of the uprights, and a cover is fitted over the whole. There are few carts in the bet, though Arains generally have some. The roads are muddy for great part of the year, the people are poor, and their cattle are not strong enough to draw a cart. The following are the chief staples of the district with the mode of cultivating them.

**Sugar-cane.**

Only about 1,000 acres of sugar-cane are grown in this district. The cane is of two kinds: one for crushing for sugar-making, and the other grown for eating in its natural state. The

former is usually of the kind called *chun*. It has hitherto been grown only on the wells in the eastern part of the Zira Bet, but is now being introduced in the lands irrigated by the Sirhind Canal. The eating cane (*pem* or *pandu*) is grown near Ferozepore and other towns. Cane occupies the ground from February to December. The preceding kharif season is spent in preparing for it, and it is too late to grow a rabi after it; so it takes up two agricultural years. As it requires a steady supply of water, it cannot be grown on waterings from the inundation canals unless with the additional aid of wells. The mode of planting and cultivating the cane, and the processes of crushing and of boiling, have often been described, and need not be detailed here, since they form no important feature of the agriculture of the district. The sugar produced is of inferior colour and texture, and does not fetch a good price. Good *pem* near Ferozepore sells as it stands for about Rs. 200 per acre.

Chapter IV, A.  
Agriculture  
and  
Live-Stock.  
Sugar-cane.

Rice is grown to a considerable extent in the tracts watered by the inundation canals. It takes more water than can be got from a well alone, though an auxiliary well-watering is often employed when the canal water fails. There are two or more kinds of rice grown, but none is of the highest quality. The best is called *sangji*. It has a long white grain. An inferior kind, with a dark grey husk and red kernel, is known as *dhevin*. The stunted kind called *kherse*, which is distinguished by the ear never emerging from the sheath which encloses it, is sown on new alluvial lands in the river bed which are too wet for any other crop. The best rice is sown in a nursery bed, and transplanted to the field when the seedlings are about nine inches high. The nurseries being prepared before the canals begin running are watered from a well. The coarser rice is harvested somewhat earlier than the finer kinds. The grain is usually separated out by knocking the heads of the sheaves against the sides of a hole in the ground. But if there is a large area to deal with it is sometimes trodden out like wheat or barley by the feet of cattle.

Rice.

Maize is of two kinds, white and yellow. The latter gives a somewhat heavier yield, but the advantage of the white kind is that it can be sown later in the season. It seems to be a recent importation from America, whence all the maize originally came, and great heat does not suit it. It is most grown in the Bet. The cultivation of maize has been already described.

Maize.

Cotton is grown on wells in the riverside tract, and on canal lands in Moga and Mukatsar. It requires a moderate but regular supply of water. On the inundation canals it is not very successful. The agriculturists of this district are not sufficiently careful farmers to grow cotton well, for it requires much weeding as well as good tillage. In former times much cotton seems to have been grown without irrigation in Moga. This is hardly ever the case now. Probably cotton was grown in places where the rain water from the large areas of waste

Cotton.

## Chapter IV. A.

Agriculture  
and  
Live-Stock.

## Cotton.

## Juir or jowar.

land collected in a field below. The cotton grown is to a large extent used for home consumption. The members of the peasant's family find an occupation in ginning the cotton, and then in spinning the fibre into thread, while the seed when separated from the fibre forms the best of all food for milk buffaloes.

*It is unnecessary to describe the hand-gin (*bela*), the spinning-wheel, and the loom, as they are the same as in other districts.*

*Juir* is the great staple kharif crop of the country. It is grown in all soils except the sandiest. In the northern and eastern parts of the district it is not considered necessary to water it. But much *juir* is grown on the lands irrigated by inundation canals near the river, and on lands irrigated by the Sirhind Canal in Mukatgar and the south and west of Moga. Some pulses are always sown along with *juir*. The commonest is *moth*. *Juir* is usually grown in land that has borne a rabi crop in the spring. It is sown after a single ploughing, and receives no further attention. As the heads do not ripen all at once the earliest are often picked by hand. The *juir* straw is the main cattle fodder of the country. In some cases, especially on the north side of the district, it is usual, when the *juir* is wanted for fodder (*chari*) only, to sow the seed very thick, so that the stalks may be thin and the fodder fine. Twelve sars or more will be sown instead of about three sars. Much less grain is then produced than if the seed had been sown sparsely. In the south of the district the distinction between *chari* and ordinary *juir* is hardly known; the people do not set apart any portion of their land for the growth of mere fodder, but always endeavour to secure both grain and straw. On the walls *chari* is often sown early in the summer, and is fed green.

The *juir* heads are subject to a sort of "smut" called *kungidari*, in which the contents of the grain are displaced by a fungoid growth of black dust.

## Bajra.

*Bajra* takes the place of *juir* to a great extent in Mukatgar and Fazilka on unirrigated lands. It requires less rain. The grain is preferred to *juir* for food by the people of these parts, and it always sells at a higher price. It keeps for a longer time than any of the other kharif grains. But the straw is of very little value for cattle food. The ears are generally picked off as soon as they are ripe, and the straw is sometimes left in the field. Like *juir*, *bajra* is always grown with a pulse, generally *moth* mixed with it. *Bajra* is subject to a disease in which the kernels degenerate into long threads forming a tuft.

## Moth, &amp;c.

*Moth* is the principal pulse crop of the uplands. It is not generally irrigated. The straw, called *misa* or *sikhi*, is much valued for cattle fodder. The grain forms with *bajra* and *juir* the main support of the people in the cold season.

Mung serves much the same purpose as moth, but the straw is not so good. Moch takes the place of moth on the riverside. It requires very little tillage, and will grow well on lands that are only half cleared and unweeded.

Guira is a grain grown chiefly for cattle fodder in the southern uplands.

Til or *sesamum* is grown to a considerable extent in various parts of the district, both with and without irrigation.

Attempts have been made to grow indigo, but so far the cultivation has not become popular. Hindus have an objection to touching indigo, which, for some reason or other, they say is the *chukra* among plants. They do not like clothes dyed with it.

Wheat is the staple produce of the riverside lands. It is also grown irrigated and unirrigated over nearly all the Moga Tahsil. In Makarsar and Fazlizai wheat is not much grown without irrigation. Its place is taken by barley, or if the land is too dry for barley, then by gram. When grown without irrigation gram is always sown along with the wheat. This mixture is called *bejhar*. The two are reaped together, and generally sold together, and for home consumption they are ground and eaten together; but if the wheat is to be sold separately, the dealer, or sometimes the grower, sifts out the gram. The wheat usually grown is a soft red. On well lands the wheat is never mixed with gram. On canal lands it is more often mixed than not, especially on the inundation canals. In the Zira Tahsil, and occasionally in Perozspore, white wheat is grown on well lands. One sort is a beardless wheat (*mundari*) with a red chaff, though the grain is white. Another is that known as *pammus* or *calicut*. This is a valuable wheat, but it is rare. In the south of the district a peculiar sort of wheat is grown on canal lands, the upper part of the ear of which has the kernels much more closely set than the lower part, so that it takes a club shape.

For wheat the land is prepared as carefully as the agriculturist's resources permit. It is generally ploughed three or four times in the rainy season preceding the crop, and if possible before this, that is to say, immediately after the Christmas rains. The earth is also pulverized by the use of the *soediga*, or clod-crusher, which has been described above.

To separate the grain from the straw and chaff the whole is trodden to pieces by the feet of bullocks. In the well lands, where the wheat is grown without gram, the action of the bullocks is assisted by making them drag behind them a sort of hurdle laid flat and weighted down. The cattle are tethered in the centre of the heap of sheaves, and turn round in a small circle. When the stuff is thoroughly broken up so that it all looks like chaff, it is roughly winnowed, and the grain mixed with broken bits of the ear containing grain (*ghundi*) falls apart from the lighter parts. The former is then trodden again, and

## Chapter IV. A.

Agriculture  
and  
Live-Stock.

Mela.  
Gohra.

Til or *sesamum*.

Indigo.

Wheat.

## Chapter IV. A.

Agriculture  
and  
Live-Stock.  
Wheat.

then finally winnowed. By this process the grain can be turned out very fairly clean if the soil on which it is trodden is not too loose. Usually a firm piece of ground is kept for several years for the purpose of a threshing-floor, and becomes very hard and smooth. The straw and chaff is left in a state in which it is readily eaten by the cattle. It is called white *bhaisa*.

Wheat is stored either in ordinary huts (*bathis*) or in large earthen bins and barrels (*kothi* and *charola*) built up of layers of mud, which stand outside the house. It is not often buried in pits in this district.

## Barley.

Barley, rather than wheat, is the staple cereal of the central and southern parts of this district. It requires less moisture at sowing time than is necessary for wheat, and is more hardy altogether. It is always grown with gram when unirrigated, and generally when irrigated. Some barley is grown by itself in well lands for use as green fodder. If the land is too dry for sowing in October, but rain should happen to fall in December, late barley, called *kansuji*, is sometimes sown without gram. A mixture of gram and barley is called *burrax*. In the south of the district, where barley is much eaten, it is usual to remove the husk before grinding it. This is done by soaking it for some hours and then pounding it in the same way as for husking rice.

## Gram.

Gram occupies a larger area of the land than any other crop. As above stated, it almost always forms a part of the crop when wheat and barley are grown on unirrigated land. It is also grown by itself on hard canal lands after rice and maize, and again on sandy lands in the Modki plain, and in the south of the district where cereals would not be successful. It forms more than anything else the food of the people during the hot season. The young leaves in the spring are cooked as greens. Gram requires much less tillage than wheat and barley. Its seeds being large and the germ strong it will make its way through the clods and spread about above them no matter how hard and rough they may be. There is a proverb regarding this peculiarity of gram, and the somewhat similar habit of moh—

"*Chhola ki jāne vīh;*  
"*Mūl ki jāne gho;*  
"*Jatt ki jāne vīh;*"

that is to say, gram does not thank you for tillage, moh takes no heed of weeds, and a Jat does not care whether he has or has not a roadway to travel on.

Gram is subject to but few chances of injury, but sharp frost frequently withers it very extensively. It storms well.

Raps is almost entirely confined to unirrigated land. When grown on watered land it does not seed well, and is usually plucked green for cattle fodder or for use as a vegetable.

It is usually sown in cross rows at intervals of three or four yards in fields of wheat or barley mixed (as above mentioned) with gram. It rises above the gram, &c., and spreads out, doing better so than if sown singly. But owing to the very high price at which raps has been selling in late years (considerably dearer than raw sugar) the agriculturists have been tempted to grow it more frequently unmixed. It is liable to blight and to injury by wind while the seed is forming, and in some years great areas of it are destroyed by caterpillars.

*Masur* is a pulse grown on the riverside in the cold season. It comes up and ripens very quickly, and requires little tillage, so it can be grown on land from which the annual inundation does not subside early enough for the cultivation of cereals. It thus takes in the cold season the place which is taken in the hot season on these lands by *misa*. On slightly higher lands it is replaced by gram, then by barley, and on firmly established lands which are only flooded for a short time, by wheat. *Masur* is well known in Europe under the name of Egyptian lentils.

*Melons* are grown to a considerable extent as a late rabi crop on lands near the river. They are frequently sown together with cotton in February, and come to perfection while the cotton is still small. Both water-melons and musk-melons are grown. They sell very cheap in the season, and being bulky to carry do not bring in much profit to the grower except near a town.

*Gairons* are grown as a field crop by Arains in the Zirra Bet, and are very productive, but sell cheap. Onions and chillies are often carried by the Arains into the Moga country, and there exchanged for grain.

*Tobacco* is not largely grown in this district. It is almost confined to well lands in the riverain tracts. A little is grown by Mussahans cultivators in the northern parts of the uplands, but the prejudices of the Sikhs, who form the bulk of the inhabitants of the uplands, prevents them having anything to do with tobacco, as smoking is forbidden to them. Two kinds are grown, the ordinary kind with a long smooth leaf and a pink flower, and another kind called *gobi tamiku*, which seems to be the same as the Syrian variety (*Nicotiana agrestis*). This has a crumpled leaf and a bunch of closely set yellow flowers. The flowers of this kind are sold along with the leaf, and it fetches a slightly higher price than the ordinary kind. Tobacco needs better tillage than the Mussahans cultivators can usually bestow on it, and consequently a good crop is a rather rare sight in Ferozepore. No improved means of curing it have been tried.

Table No. XX shows the areas under each of the principal crops.

Table No. XXI shows the estimated average yield in pounds per acre of each of the principal staples as shown in the Administration Report of 1887-88.

## Chapter IV, A.

Agriculture  
and  
Live-Stock.  
Rapse.*Masur.**Melons.**Onions.**Tobacco.*

**Chapter IV, A.****Agriculture  
and  
Live-Stock.**

**Average yield  
Production and  
consumption of  
food-grains.**

The average consumption of food per head has already been noticed at page 43. The total consumption of food-grains by the population of the district, as estimated in 1878 for the purposes of the Famine Report, is shown in maunds below:—

	Gram.	Administration.	New-agriculturists.	Total.
Wheat	—	1,000,000	604,471	1,604,471
Inferior grains	—	1,000,000	704,300	1,704,300
Pulses	—	300,000	100,070	400,070
Total	—	2,300,000	1,318,841	4,618,841

The figures are based upon an estimated population of 540,253 souls, which of course does not include the Fazilka Tahsil. On the other hand, the average consumption per head is believed to have been over-estimated. A rough estimate of the total production, exports and imports, of food-grains was also framed at the same time; and it was stated (page 152, Famine Report) that only one-fifth of the food-grains produced in the district were consumed on the spot, the remainder, aggregating some 65 lakhs of maunds, being exported, in the absence of any special demand in other quarters, to Karachi, Bombay, and Calcutta.

**Arboriculture and  
Forests.**

There are no forests in the Ferozepore District, nor is any portion of the area under the management of the Forest Department.

**Cattle.**

Table No. XXXII shows the number of live-stock in the district as returned for the Administration Report. The breed of cattle along the river bank and in the *Bet* generally is inferior; but that in the high lands of the district is very fine. Carts drawn by oxen and buffaloes are generally used for transport, and the manufacture of wheels for country-carts is a flourishing industry in the city of Ferozepore. In the smaller portions of the district camels are much used for burden. The camels bred in the district are good, the average price for a riding camel being about Rs. 120; that of camels for burden varies considerably, according to their size and power. Donkeys are used for burden to a considerable extent in the villages, but are of very small size. Mule breeding is beginning to be recognized by the owners of inferior pony mares as their best chance of a good profit. There are two distinct varieties of horses bred in the district—the one small but very wiry, bred principally by the Dogars of the *Bet*; the latter, bred inland, of considerable size, mares being occasionally found of 15-3 in height. Encouragement is being given to breeding by the annual horse fair at Jalalabad; but here, as elsewhere, difficulty arises from the poverty of the breeders, who are unable to bear the expense of rearing the colts well. Goats and sheep are reared in considerable number in the interior of the district. The sheep are kept principally for their wool, the goats for their milk; for the animals themselves there is no ready market. Goat hair is used for making sacks.

Strange as it may appear, Mukatsar was once rather a good place for cattle. If not within the celebrated Lacky jungle, it must have been very near it, if the military " Memoir of George Thomas" (page 182) can be relied on. But it probably cannot. Before the introduction of English rule the jungles of Mukatsar were extensive, and the people depended more on cattle-keeping than on agriculture. Now the land has been cleared of trees, and the profits of cultivation have caused the *amis-dars* to give up their pastoral habits. A series of bad years has exerted an influence in the same direction : as the people are obliged, as a matter of course, to send their cattle to the river tracts or into Bahawalpur or Bikaner in search of food. However, even now the people have enough cattle to supply themselves with plough-hallocks, and can even occasionally dispose of some animals, besides procuring *ghi* and butter-milk for themselves. Many villages keep a few camels, but only for carriage ; as, except in parts of Fazilka, it is considered disgraceful to plough with them. Sheep are fairly numerous. They are shorn twice a year, in *Aas* and *Chetar*. The average weight of a fleece is about 1*t chittak*. After supplying local wants, about 1,000 maunds of wool remain available for export. The wool of the Bugar country between Fazilka and Bikaner is of very superior quality, being long, soft and white. It is largely exported. The cattle to the south of the Danda are superior to those to the north of it. The average price of stock may be taken as follows :—

Cow	...	Rs. 25		Sheep	...	Rs. 2
Female buffalo	...	50		Bullock	...	50
Camel	...	25		Male buffalo	...	25
Goat	...	2				

Taluk.	Horses.	Donkeys.
Ferozepore	2	1
Moga	2	2
Dera	2	2
Muzaffarpur	1	2
Fazilka	1	1
Total	7	9

Horse-breeding operations were first systematically commenced in the district in February 1882, when 6 horses and 4 donkeys were distributed by the Horse-breeding Department. At the present time there are 7 horses and 8 donkeys located as below, with particulars as to breed, &c. :—

Government breeding operations, and horses and cattle fair.

	Zemargan	Moga	Dera	Muzaffarpur	Fazilka			
	No.	Breed.	No.	Breed.	No.	Breed.	No.	Breed.
Horses	1	Norfolk Trotter	1	Thoroughbred Arab	1	Norfolk Trotter	1	Norfolk Trotter
	1	Thoroughbred Arab						
Donkeys	1	Arab Punjabi	1	Pakist. Punjabi	2	Balki	2	Balki

#### Chapter IV. A.

Agriculture  
and  
Live-Stock.  
Cattle.

## Chapter IV, A.

**Agriculture  
and  
Live-Stock.**  
Government breeding operations, and horses and cattle fairs.

Year.	Horses.				Donkeys.			
	Mares.		Horses.		Males.		Females.	
	M.	F.	H.	F.	M.	F.	D.	F.
1862-63	—	45	22	108	19	11	—	49
1863-64	—	61	22	79	27	21	—	43
1864-65	79	22	129	22	22	22	—	26
1865-66	89	22	127	22	30	22	—	26
1866-67	107	22	112	22	30	22	—	26
1867-68	29	22	112	22	16	22	—	26
Total	322	337	866	206	307	207	—	146

The young stock produced from Government stallions is shown in a table in the margin. The department of horse-breeding operations has branded 947 mares. Mares for horse-breeding are not branded for mule breeding, as all unbranded mares may be served by donkey stallions.

An important cattle fair, established in 1865, used to be held annually

at Mukatsar on the occasion of the great Sikh festival in the month of January. At this fair, prizes were distributed for sheep and horned cattle, and until 1874 were offered also for horses. As a cattle fair the institution was most successful, and year by year increased in importance. Many of the cattle exhibited were of very good quality, and the prizes attracted exhibitors from a distance, whereby new blood was constantly imported into the district. For horses also, so long as prizes were given, the fair promised well. Many horses of excellent quality were shown, both from this and the neighbouring districts, and on more than one occasion considerable purchases for Light Cavalry remounts were made. On the last occasion of the fair, however (in 1875), the show of horses was disappointing, both as regards number and quality, while the prices asked for horses suitable for military purposes were excessive. The principal reason for this falling off was undoubtedly the discontinuance of the Government prizes to which the breeders are said to have attached more importance than was due to their intrinsic value. The breeders also complained that they could command better prices in the down country markets—an advantage which, in the absence of the local inducement afforded by the prizes, they did not care to forego. The prizes for horses were, therefore, discontinued; but the cattle fair continued to be held at Mukatsar till 1882, when it was abandoned in favour of the fair at Jalaisbad in the Mamdot State.

The Nawâb of Mamdot held his horse and cattle fair at Jalaisbad for the first time in January 1882, and the prizes given by him are shown in the margin. Prizes were also given to owners of cattle, and, as the fair was a success, an annual horse show was established at Jalaisbad,

the time for which is fixed to follow the Mukatsar fair by a few days. Jalaisbad is a new town in the Mamdot State, about 18 miles from Mukatsar.

The fair ground belongs to the Nawâb of Mamdot, who takes fees on the sale of horses, but gives in prizes a sum usually equal to the amount of the Government grant. The Govern-

To 8 mares	—	—	221
— 8 horses	—	—	20
— 2 geese*	—	—	6
— 1 mule	—	—	4
TOTAL	—	—	230

**Persepolis District.]**

CHAP. IV.—PRODUCTION AND DISTRIBUTION.

105

ment prize list amounted to Rs. 350 in 1883, but it has been gradually raised to Rs. 1,000. The subjoined statement shows the progress of the fair up to 1888 :—

Year	Number of horses stock present.	Number competing for prizes.	Number of animals sold,	
			To British service.	To Bengal Cavalry.
1882	111	111	—	—
1883	111	111	—	—
1884	111	111	—	—
1885	111	111	—	—
1886	111	111	—	—
1887	111	111	—	—
1888	111	111	—	—

**Chapter IV. A.**

**Agriculture  
and  
Live-stock.**

Government breeding operations, and horse and cattle fairs.

The Government system has not been established sufficiently long for much progress to have been made by breeders in raising their young stock on sound principles. Three *salutris* have now been appointed, and many colts have been geld by this agency.

The Nawâb's prizes are open to classes of animals which are not eligible for the Government's prizes. The show is attended by about 60,000 persons.

The bulls that have been sent from Hissar to this district for breeding purposes have been distributed as shown in the following statement, which gives the number of their produce up to the year 1888-89 :—

District	Number of bulls sent	NUMBER OF PRODUCE:			OF WHICH BULLS:		
		For pri- vate use 75 per cent.	For public use 25 per cent.	Total	For pri- vate use 75 per cent.	For public use 25 per cent.	Total
Ferozepur	10	2,621	334	2,955	—	54	54
Moga	4	5,612	665	6,277	1,307	62	1,369
Zira	16	544	104	1,037	358	56	414
Muktsar	8	901	68	969	149	30	179
Patiala	17	1,948	435	2,383	362	301	663
Total	47	10,088	1,807	11,895	2,002	301	2,303

Six rams were obtained from Hissar for breeding purposes from the year 1874 to 1880, but they have all died. None have since been obtained.

## Chapter IV, B.

## SECTION II.—OCCUPATIONS, INDUSTRIES, COMMERCE AND COMMUNICATIONS.

Occupations, Industries, Commerce, and Communications.

Occupations of the people.

Table No. XXIII shows the principal occupations followed by males of over 15 years of age as returned at the census of 1881. But the figures are perhaps the least satisfactory of all the census statistics, for reasons explained fully in the Census Report; and they must be taken subject to limitations which are given in some detail in Part II, Chapter VIII, of the same report. The figures in Table No. XXIII refer only

Population	Towns	Villages
Agricultural — —	11,125	381,333
Non-agricultural — —	11,375	230,268
Total — —	22,500	611,601

to the population of 15 years of age and over. The figures in the margin show the distribution of the whole population into agricultural and non-agricultural, calculated on the assumption that the number of

women and children dependent upon each male of over 15 years of age is the same, whatever his occupation. These figures, however, include as agricultural only such part of the population as are agriculturists pure and simple; and exclude not only the considerable number who combine agriculture with other occupations, but also the much larger number who depend in great measure for their livelihood upon the yield of agricultural operations. More detailed figures for the occupations of both males and females will be found at pages 115 to 123 of Table No. XIIA and in Table No. XIIIB of the Census Report of 1881. The figures for female occupations, however, are exceedingly incomplete. None of these figures include the Fazilka Taluk, which did not form part of this district in 1881.

Principal industries and manufactures.

Table No. XXIV gives statistics of the manufactures of the district as they stood in 1881-82. The manufactures of the district are of the humblest kind, and are confined entirely to the supply of local wants. Coarse cloths and blankets are woven in the villages from home-grown cotton and wool, the produce of the village flocks. The cloth is of two kinds—the coarser, called *khudar*, and the finer, which is worn by villagers of the better class, *thar*. The latter is double threaded, and when ornamented by the insertion of coloured threads in warp and web, producing a sort of check pattern, is known as *dobba biss*.

Mr. Lockwood Kipling, Principal of the Lahore School of Art, has kindly furnished the following note on some of the special industries of the district :—

"Ferozepore is not noted as the seat of any artistic industry. The usual cotton weaving is, perhaps, more extensively wrought here than in some other districts; and as it is a place of considerable trade in coco, do, more country carts are made than elsewhere. Lac turnery is practised in most parts of the Punjab; but a workman of Ferozepore has almost raised it to the dignity of a fine art by his skill in pattern scratching. He uses the wood of the *farash* (see his name), and not, as elsewhere, the *shisham* or the *poplar*. This wood, though hard in Sindh, where wood of any kind is scarce, is seldom touched by the Punjab workman. It is soft,

colonists; non-resinous and not liable to be attacked by insects. It is curious that Sariq-ud-din has material at Farozspore. His work has been sent to various exhibitions, and is the best of its kind in the province. But it is altogether exceptional that it is scarcely fair to credit Farozspore with lac-tumery as a local industry. A certificate and a medal were awarded to him at the Calcutta International Exhibition of 1883-84."

The chief articles of trade in this district are wheat and other grains—i.e., gram, wheat, barley, mung, moth, jowar, maize, and milch grain. In addition, the following are also articles of trade:—cotton, raw and cleaned, cotton-seed, oil-seed and oil. Recently the system of producing *gur*, khanda and *shakkar* from both ponda and *kálha* sugar-cane has been introduced to a small degree. The shopkeepers store up gram, chaffy grain and wheat, sometimes for years. The zamindars of the district, with the exception of those of the *kithár*, or low-lying lands, trade in grain and export it to Ludhiana, Amritsar, Lahore, Bahawalpur, Jullundur and Hoshiarpur. In return they bring from Amritsar, salt, rice and *sugath*; and from Jullundur, Hoshiarpur and Ludhiana, *gur* and sugar of every kind; and from Bahawalpur, barilla.

The trade is carried only chiefly by means of donkeys and carts, and to a small extent by camels, bullocks and mules. The zamindars employ their carts and camels, and the kunkars, donkeys, oxen and mules. When there is a heavy demand for conveyance carts are supplied by the minjha portion of the Kasur Tahsil and its neighbourhood. The village *bunias*, who have small means, keep ponies for the purpose of conveyance; but this is not the case in large towns.

Besides Farozspore City, there are the following towns where trade is carried on to some extent:—Fazilka, Dharmkot, Zira, Kot Iss Khan, Mukatpur, Jhalilabad, Moga, Mudki, and Mamdot. In all these towns there are Municipalities, with the exception of Mamdot, Jhalilabad, and Kot Iss Khan. The chief mart, however, is Farozspore City itself. In all Municipalities, octroi is levied. The following are the chief imports:—from Hoshiarpur and Jullundur, *gur*, sugar of every sort, matting, safflower and flax; from Patiala, cotton and sesamum; from Karachi and Bombay, iron, copper, zinc and lead; from Calcutta and Bombay, cloth (of European manufacture) and gunny-bags; from Bahawalpur, barilla; from Multan, Lashkar, and Patials, indigo; from Hissar, sal ammoniac; from the North-Western Provinces, tobacco; from the hill districts, wood; from Khurasán, madder and fruits; from Lahore and Amritsar, salt, rice and spices. The opening of the railway has very much diminished the river trade. Nothing is now sent to Sukkur by river. Charcoal is sometimes sent to Bahawalpur by river, but only to a small extent. The fare of a boat to Bahawalpur is three annas a manul. Desular, pine, bamboo and other kinds of wood are brought down by river.

#### Chapter IV, B.

Occupations,  
Industries,  
Commerce, and  
Communications.

Principal industries  
and manufactures.

Course and nature  
of trade.

**Chapter IV. E.**

Occupations,  
Industries,  
Commerce, and  
Communications.

Course and nature  
of trade.

In 1882 the following were the imports and exports for Ferozepore City :—

*Imports.*

Ra.

Articles that have paid octroi.	Value	... ...	26,53,940
Articles that are exempt from octroi	...	...	3,73,584
		Total	... 30,27,510
		Exports	... 11,57,927

The table on the next page, compiled from figures supplied by the Deputy Commissioner, show the trade in the principal staples in 1882-83. The imports for 1887-88 and 1888-89 are shown at the end of Chapter VI.

Table No. XXVI gives the retail barir prices of commodities for the last twenty years. The wages of labour are shown in Table No. XXVII, and rent-rates in Table No. XXI; but both sets of figures are probably of doubtful value. To the latter table has been added a column showing the rates of yield assumed in the assessment work of the northern part of the district in 1886-87.

The figures of Table No. XXXII give the average values of

Period.	Sale.	Mortgage.
	Ra. a.	Rs. a.
1868-69 to 1872-73	15 2	8 12
1874-75 to 1877-78	14 10	11 12
1878-79 to 1881-82	22 9	22 12
1882-83 to 1887-88	28 7	32 9

land in rupees per acre, as shown in the margin, for sale and mortgage; but the quality of land varies so enormously, and the value returned is so often fictitious, that but little reliance can be placed upon the figures.

Prices in Ferozepore have not risen so much as in other parts of the province. This is due partly to the great extension of cultivation that has been going on for thirty years; partly to the low value of the staple crops, rendering the cost of carriage a formidable objection to export; and partly to the system of emigration in bad years, which, by diminishing the demand for food, tends to keep prices down. The charges in the price of barley, wheat, and gram, bajra, jowar and moth, during six periods from 1841—1871 in the Mukatser Tahsil are shown on page 110, and the prices ascertained to have been current in the northern part of the district for three subsequent quinquennial periods are added :—

## TRADE IN THE PRINCIPAL STAPLES.

Imports Exports	Principals Gums		Principals Tonic.		Medicinal		Skins Tonic.		Beverages Tonic.	
	Imports	Exports	Imports		Exports		Imports		Exports	
			Medicinal Tonic	Confectionary	Medicinal Tonic	Confectionary	Medicinal Tonic	Confectionary	Medicinal Tonic	Confectionary
Gum	300,000	2,60,000	100,000	100,000	100,000	100,000	20,000	20,000	100,000	100,000
Wheat	150,000	2,30,000	80,000	120,000	80,000	120,000	20,000	20,000	80,000	120,000
Tea	72,000	1,75,000	177,000	45,000	177,000	45,000	22,000	22,000	177,000	32,000
Rice	40,000	1,00,000	—	—	40,000	—	20,000	20,000	40,000	100,000
Flax	7,200	1,25,000	2,000	22,122	12,000	12,000	1,000	1,000	2,000	10,000
Cotton	100,000	1,00,000	607	1,000	20,000	20,000	6,000	6,000	100,000	100,000
Oil	100,000	1,00,000	—	—	100,000	—	—	—	100,000	—
Powder	100,000	1,00,000	—	—	100,000	—	—	—	100,000	—
Oil	9,400	1,00,000	602	4,000	60,000	60,000	2,000	2,000	60,000	60,000
Liquor & Spiritus	—	—	—	—	—	—	—	—	—	—
Oil cake	—	—	—	—	—	—	—	—	—	—
Tea	3,000	1,00,000	815	45,000	800	16,000	200	14,000	1,000	25,000
Powder	6,000	1,25,000	—	—	—	—	—	—	100,000	100,000
Wood	—	—	—	—	—	—	—	—	100,000	100,000
Bal	—	—	—	—	—	—	—	—	100,000	100,000

Faroeports District.]

CHAP. IV.—PRODUCTION AND DISTRIBUTION.

109

## Chapter IV, B.

Occupations,  
Industries,  
Commerce, and  
Communications.Course and nature  
of trade.

## Chapter IV, B.

Occupations,  
Industries,  
Commerce, and  
Communications.Prices, wages, rents,  
rates, interest.

	Period.	Average rate per rupee of					
		Bailey.	Wheat.	Gram.	Rijha.	Jowar.	Mothi.
	1841—1849	1.32 12	0.32 0	1.22 0	1.31 0	1.38 7	1.7 9
	1849—1850	1.2 0	0.28 0	0.28 0	1.0 0	0.37 0	1.1 8
	1851—1853	2.0 10	1.20 0	1.27 0	1.00 0	2.4 8	1.31 0
	1853—1859	2.29 12	1.2 0	2.27 0	1.2 0	2.98 2	2.22 4
	1860—1862	1.29 10	0.32 00	1.22 0	0.32 00	1.21 0	1.8 22
	1866—1871	1.21 0	0.28 0	0.28 12	0.22 0	0.37 12	0.38 10
	1841—1869 (18 years)	1.27 0	0.36 2	1.22 10	1.22 0	1.38 12	1.7 2
	1869—1871 (3 years)	1.29 7	0.37 0	0.21 0	1.8 12	2.38 12	2.16 14
	1871—1877	1.22 0	0.26 0	0.22 0	0.22 0	0.38 0	—
	1877—1892	1.20 0	0.26 0	0.22 0	0.22 0	0.38 0	—
	1892—1897	1.2 0	0.22 0	0.27 0	0.22 0	0.38 0	—
Average of 13 years from 1871 to 1877		1.26 0	0.26 0	0.22 0	0.22 0	0.32 0	—

The decade 1851—1860 shows a remarkably low range of prices, due in a considerable measure to uncommonly good harvests. The average rates of the years subsequent to 1871, however, show corn to be much dearer now than formerly. These prices are not the bazar prices, but those fixed by the *banis* twice a year, on the 1st of *Jeth* and the 1st of *Kaliak*, and according to which their transactions with the *samindars* are conducted.

Weights and mea-  
sures: Land mea-  
sure.

The measure for land in use in this district is the *ghumla* or the *Bārī*: *Dohā* = about  $\frac{1}{2}$  acres. The unit is the *Karam* or *Ādam*, for which, under Mr. Branderth's orders, a fixed value of 5 feet 1 inch was adopted at the time of the Settlement, but strictly the length should have been about 5 feet 1 inch in order to make the *ghumla* equal to  $\frac{1}{10}$ th of an acre. The units are—

1 karam square	...	...	=	1 sarabbi.
9 sarabbis	...	...	=	1 marla.
20 marlas	...	...	=	1 kanal.
8 kanals	...	...	=	1 ghasia.

The value of the *karam* (= 3 cubits) was formerly fixed arbitrarily for almost every village from the measurement of the arm, from the elbow to the tip of the fingers, of some prominent member of the community. In Sikh times the measurements of the fields for the yearly assessments were made by the assessor riding round the fields, counting his horse's paces; and it is said that he rode a large or small horse, according as he was well or ill-disposed to the villagers. The *kadam* has now (1884—85) been

made exactly 60 inches. Thus the *mazla* is 25 square yards, the *bandi* is 300 square yards, and the *ghumda* is 4,000 square yards, and 121 *ghumdas* are equal to 100 acres.

The scale of weights and measures in use among the agricultural population of the district is different only in its subordinate denominations from those of the imperial standard. The following is the scale:—

8 poppy-seeds	...	...	...	...	—	1 <i>ratli</i> ,
8 <i>rattis</i>	...	...	...	...	—	1 <i>meda</i> ,
12 <i>mashdis</i>	...	...	...	...	—	1 <i>tola</i> ,
2 <i>tolas</i>	...	...	...	...	—	1 <i>scrupl.</i> ,
16 <i>scrupl.</i>	...	...	...	...	—	1 <i>sh.</i>

and thereafter the imperial scale, with several compendious names or intermediate weights—e.g., *dhatteri* for  $\frac{1}{2}$  *sh.*

Traders dealing with the outside world, and in large villages like Mamdot, use the Government *sar* in their transactions. But ~~say~~ among the people a local *maund* and *sar* are used. These are called *kacha* weights. The *kacha* *maund* is equal to 16 Government *sars* in the *Hahi*, and to 16 *sars* in the *Bet*. In the *Bet*, however, measures of capacity, and not of weight, are commonly employed. These measures are the *parop* and *topa*. Four *parops* make one *topa*, four *topas* one *pai*, four *pais* one *man*. Two *topas* are in use: the Dogar's *topa*, which contains from 3*½* to 4 *sars* of wheat; and the Wattu's *topa* which contains only 3 *sars* of wheat. A *topa* *man* is thus about one and a half Government *maunds*. The *topa* is a cylindrical measure of wood. The Dogar's *topa* is about 24 inches in diameter and 3*½* inches deep. It is heaped up like the English bushel measure.

The figures in the margin show the communications of the

districts as returned in quinquennial Table I of the Administration Report for 1888-89,

while Table XLV shows the distance from place to place as authoritatively fixed for the purpose of calculating travelling allowances. Table No. XIX gives the area taken up by Government for communications in the district.

The Sutlej is navigable for oonkey craft throughout its course within the district, but through traffic between Karachi and Ferozepore is confined to the portion below Ferozepore. The principal traffic on this river, as stated in the Punjab Famine Report (1879), is shown in Table No. XXV. The ferries and the distances between them are shown below, following the downward course of the river.

The river Bala joins the Sutlej opposite to the Hariki Ferry, on the northern border of the district.

#### Chapter IV, B.

Occupations,  
Industries,  
Commerce, and  
Communications.  
Weights.

Communications	Miles
Maritime river	228
Railways	107
Metalled roads	41
Unmetalled roads	63

Communications.

Rivers.

**Chapter IV. B.**

**Occupations,  
Industries,  
Commerce, and  
Communications.**

**River.**

River.	Stations (or names of Towns).	Mileage in miles.	Description.
Kanwa	—	—	
Miani	—	—	
Indira	—	—	
Bhera	—	—	
Bawali	—	—	
Talli	—	—	
Nagpur	—	—	
Ferozepore	—	—	
Kandla	—	—	
Mohatta	—	—	
Wazirabad	—	—	
Balochiwala	—	—	
Piplapuram	—	—	
Singhpur	—	—	
Jodha	—	—	
Khiva	—	—	
Ghurka	—	—	
Muzaffarnagar	—	—	
Phagwara	—	—	

At this point the Ravi joins the Sutlej.

**Railways.**

The Rewari-Ferozepore (Rajputana Malwa) Railway (narrow-gauge) runs through the district, but its stations are all in native territory. A branch runs from Kot-Kapura to Mukatsar and Fazilka, with intermediate stations at Barnwali, Lakhewali and Chak Pakhowala. The North-Western Railway (broad-gauge) by which Ferozepore is connected, *via* Raiwind, with Lahore and Multan, meets the narrow-gauge line at Ferozepore. The Sutlej is crossed by the North-Western Railway by means of a bridge of 27 spans, 4,000 feet in length.

**Roads, rest-houses,  
and encamping  
grounds.**

The following table shows the principal roads of the district, together with the halting places on them and the conveniences for travellers to be found at each:—

Road.	Halting place.	Mileage (miles)	Railways.
From Ferozepore to Johri, Moga, and Makran on Grand Trunk Road	Ghal Dugra Moga Makran	12 14 4 4	Encamping ground, police station, and single bungalow allotted to public road. Encamping ground, single bungalow, police station, and road bungalow. Single, police bungalow, tahsil, police station. Encamping ground, public road, and single bungalow allotted.
Ferozepore to Fazilka	Bawaliwala	23	No encamping ground. This public road ends at Fazilka.
Lahore to Ferozepore	Nih	8	Metalled. Ferozepore, 16 miles and on to Ganda Singhwindi in the Lahore District.
Ferozepore to Fazilka	Naya Killi Mohatta Jalandhar Fazilka	12 12 7 27	Unmetalled, encamping ground, police road, and single bungalow. Do. do. do. Do. do. do. Do. do. do. Encamping ground, police bungalow, single bungalow, tahsil, police station, road.
Old road from Karnal to Ferozepore	Inderkot Begharpurkot	19 21	Unmetalled, encamping ground, police road, and single bungalow. Do. do. do.

Route.	Holding place,	Distance in miles	Remarks.	Chapter IV, B. Occupations, Industries, Commerce, and Communications.
Old road, Ferozepore to Ludhiana.	Kaligard	10	Furnished, sumptuous ground, and a small bungalow, belonging to the district court and its servants.	Houls, rest-houses, and encamping grounds.
	Zira	14	Furnished, sumptuous ground, seats, and racing bungalows, called 'old police bungalows.'	
	Kotla Khan	9	Furnished, sumptuous ground, police seats, and a grounds.	
	Dhankot	8	Do. Do. Do.	
Ferozepore to Jallianwala	Mukhatsar	30	Furnished, sumptuous ground, police seats, and racing bungalows.	
	Makha	12	Do. Do. Do.	
From Phata to Sircilla	Aryavaria	—	Saddi, simple bungalows, and walls at each holding place.	Post offices.
	Makhat	—		
	Lambi	—		

There are also unmetalled roads from Ferozepore to Mukhatsar, 35 miles, and Lohura to Harike, 26 miles, on which there are no fixed halting-places. The *dāk* bungalow at the Ferozepore Cantonment is completely furnished and provided with servants. The staging bungalows at Fazilka, Ghul, Dagrū, and Makha, have furniture, crockery, and cooking utensils, and a servant. Other staging bungalows, with *surasis* on unmetalled roads, have furniture, &c., as above, but no servant.

A horse-*dāk* and bullock train ply along the Grand Trunk Road from Ferozepore to Ludhiana.

Besides the head office in the cantonment of Ferozepore, there are Imperial Post Offices at Ferozepore City, Baghapatrāns, Dhankot, Ghul, Jallianwala, Makha, Māmīot, Moga, Mukhatsar, Nathana, Nihāl Singhwāls, Butar, Mallanwāls, Malaut and Zira, and a District Post Office at Kot Bhāi. They are all money order and savings bank post offices. The Ferozepore Post Office is the disbursing office for Jagrión in the Ludhiana District.

There is a second-class Imperial Telegraph Station in the cantonment. A line connects Ferozepore with Ludhiana, in addition to the two Railway telegraph lines.

Post offices.

Telegraph stations.

## CHAPTER V.

### ADMINISTRATION AND FINANCE.

**Chapter V.**  
**Administration**  
**and**  
**Finance.**  
**Executive and**  
**Judicial.**

The Ferozepore District is under the control of the Commissioner of Jalandhar. The ordinary head-quarters staff of the district consists of a Deputy Commissioner, a District Judge, two Extra Assistant Commissioners, and another in special charge of the irrigation canals of this district.

Each tahsil is in charge of a *tahsildar* assisted by a *nabbi*.

Tahsil.	Kisanas.	Farmers and cultivators.	Bhilliars and Kisanas.
Ferozepore	2	10	2
Moga	2	10	2
Zira	2	11	2
Muktsar	2	11	2
Panika	2	11	2
Total District	10	101	11

there is no *munsiyā* at Muktsar or at Panika.

**Criminal, Police**  
**and Jails.**

The Police force is controlled by a District Superintendent and occasionally one assistant. The strength of the force, as given in Table I of the Police Report for 1883, is shown in the margin.

Class of Police.	Total strength.	Institutions.	
		Standing gurdi.	Provisional and auxiliary.
District (Imperial)	497	79	411
Centenarian	22	—	22
Municipal	22	—	22
Ferry	22	7	15
Total	541	79	462

village watchmen are entertained, and some are paid by a cess on the revenue of the village, others receive payment in kind at each harvest.

The Police stations and outposts are distributed as follows—

*Tahsil Ferozepore.*—Police stations Ferozepore City, Ferozepore, Ghial, Nawa Killi and Ferozepore Cantonment.

*Tahsil Zira.*—Police stations Zira, Dhormkot, and Makho; outpost Mallianwala subordinate to Zira Police station.

*Tahsil Moga.*—Police stations Moga, Bagharpurāna, Nihāl Singhwala and Nathānī.

*Taluk Muktasar.*—Police stations Muktasar, Kot Bhai, and Jalalabad, and outpost Mohanki subordinate to Jhalawali Police station.

*Taluk Fazilka.*—Police stations Fazilka, Abohar, and Malaut; outposts Ummi Khera and Lambi subordinate to Police stations Abohar and Malaut, and the road-post of Arsiwala subordinate to Police station Fazilka.

Besides these, there are the following road-posts along the Grand Trunk Road towards Ludhiana for night patrolling:—

Malaut 2 constables, Piarana 2 constables, Kaliawala 2 constables, Lalla 2 constables, Talwandi 2 constables, Darapur 2 constables, Jorewala 2 constables, Dagni 2 constables, Ghal Kalan 2 constables, Bagepura 2 constables, Mahua 2 constables, and Killi 2 constables.

There is a cattle-pound at each police station and outpost, (with the exception of outpost Lambi), also at Butiar and Sultan-khanwala, and the cantonment cattle-pound is under the management of the bazar sergeant.

The district lies within the Umballa Police Circle under the control of the Deputy Inspector-General of Police at Umballa.

Statement No. XLII gives statistics of police inquiries for the year 1882 to 1888, inclusive.

The Bawarisahs are proclaimed under the Criminal Tribes Act, and the number on the register in 1888 was 781. Male adults, during 1888, 30 Bawarisahs were convicted of criminal offences, viz., 13 for theft, 12 for house-breaking, 3 for possessing stolen property and 2 for other offences. The Bawarisahs of this district are not addicted to the systematic commission of non-bailable offences. They have taken to agriculture, and are mostly found in the police stations of Muktasar, Jalalabad and Moga.

The District Jail at head-quarters contains accommodation for 432 prisoners.

The gross revenue collections of the district for the last 14 years, so far as they are made by the Financial Commissioner, are shown in Table No. XXXVIII, while Tables Nos. XXIX, XXXV, XXXIV and XXXIII give further details for land revenue, excise, license and income-tax, and stamps, respectively. Table No. XXXIIIA shows the number and situation of registration offices. The central distilleries for the manufacture of country liquor are situated at Ferozepore and Moga. The cultivation of poppy is allowed in this district. Land revenue is separately noticed below.

Table No. XXXVI gives the income and expenditure from district funds, which are controlled by a District Board consisting of the Deputy Commissioner as President, the Civil Surgeon, the Executive Engineer, Sihind Canal, the senior Assistant Commissioner, the Extra Assistant Commissioner in charge of the inundation canals, and the District Inspector of Schools as *ex-officio* members, with 15 nominated and 13 elected members.

Chapter V.  
Administration  
and  
Finance.  
Criminal, Police  
and Jail.

Revenue, Taxation  
and Registration.

Chapter V.  
Administration  
and  
Finance.  
Revenue, Taxation  
and Registration.

from among the rural notables. There are also Local Boards, consisting partly of nominated and partly of elected members in each tahsil. Table No. XLV gives statistics for municipal taxation, while the municipalities themselves are noticed in Chapter VI. The income from provincial properties for the last five years is shown in the following statement:—

Particulars.	TAKES.						
	RS. LAKHS						
Tenants with house-edges	—	—	—	—	—	—	—
Farmers without "do."	20,000	2,000	27,000	2,000	20,000	2,000	20,000
Making houses	20,000	2,000	20,000	2,000	20,000	2,000	20,000
Encamping-estates	—	—	—	—	—	—	—
Cattle-pounds	—	—	—	—	—	—	—
Bazil Buildings	—	—	—	—	—	—	—
Total	60,000	4,000	61,000	2,000	60,000	2,000	60,000

The following statement shows the sums expended by the District Board in each year since its formation in 1884-85 upon the maintenance of schools, dispensaries, roads, bridges and arboriculture:—

Year.	SCHOOLS.		DISPENSARIES.		ROADS.		Arboriculture.
	Government.	Private and Voluntary.	Dispensaries.	Buildings and works.	Buildings and works.	Roads.	
1884-85	Rs. 18,700	Rs. 14,100	Rs. 1,600	Rs. 2,000	Rs. 2,000	Rs. 1,000	Rs. 1,700
1885-86	18,400	14,000	2,200	2,000	2,000	1,000	1,200
1886-87	18,200	14,000	2,200	2,000	2,000	1,000	1,200
1887-88	18,000	14,000	2,200	2,000	2,000	1,000	1,200

The ferries, bungalows, and encamping grounds have already been noticed at pages 112 and 118, and the cattle-pounds at page 115. The only *basil* properties consist of 14 shops attached to the *zamzai* at Moga, a house for the *tahsildar* at the same place, a small stable in front of the tahsil at Zira, and in Phailka 14 plots of land containing buildings of various sorts. A rent of Rs. 116 per annum is derived from the shops. Figures for other Government estates are given in Table No. XVII, and they and their proceeds are noticed in the succeeding section of this Chapter, in which the land-revenue administration of the district is treated of.

Table No. XXXVII gives figures for the Government and Aided, Middle, and Primary schools of the district. There is one High school in the city of Ferozepore maintained by the Municipal Committee; there are seven Middle schools for boys;

one (Aided) in the Cantonment Sade Bazar and one at Fazilka, both Anglo-Vernacular; five Vernacular Middle schools at Moga, Buttar, Mahrāj, Zira, and Dharmkot. The Primary schools for boys are situated at Khai, Lakkhok, Alfoki, Mumdot, Phairaya Mal (*alias* Bhāla), Sultānkhanwala, Ghal Kherd, Mudki, Rattikhera, Pherushaher and Taiwanī Blāhi in the Ferozepore Taluk; at Nathana, Bhuncho Kalān, Laudah, Langitānah, Bighapurāna, Samādh Blāhi, Pato, Hira Singh, Bania, Badhni, Dhadimur, Chahrechak, Ghollia Kalān, Kokri, Lepor, Salim, Daroli, Chand Naya and Ghal Kalān, in the Moga Taluk; at Jaisainbad, Kishanpur, Sherpur, Kot Sadar Khān, Kot Iso Khan, Makhu, Fatehgarh, Bharsen, Talwandi, Mallawala, Bhindar Kalān and Jindhra in the Zirā Taluk; at Hariki, Bhuttiwala, Chaksohawala, Kānyanwala, Mukatsar\*<sup>1</sup>, Jalālabad and Guru Harsahāi in the Mukatsar Taluk; and at Munzgam, Abolar, Situganno, Seraman, Jian and Ladhunki in the Fazilka Taluk. A Hindi (Lande Mahājani) school is attached to the Middle school at Fazilka, and the Situganno school in the Fazilka Taluk is a Nāgri school. Besides these there are Gicis' Primary schools, two in the city of Ferozepore, one at Zira, one at Dharmkot, one at Sherpur and one at Fazilka, and an aided one in the cantonment. There is also a large number of indigenous schools, most of which either teach some scriptures by rote or Hindi (Lande Mahājani), the former being chiefly maintained and attended by Musalmāns, the latter by Hindūs. The number of boys attending the schools under the management of the Deputy Commissioner amount to 841 and 2,175 in the Middle and Primary schools, respectively, with average daily attendance of about 698 and 1,757 respectively.

The Indigenous schools above mentioned are supported by voluntary contribution, the fees being very small; and the boys who attend the Indigenous schools are chiefly sons of cultivators.

This school was founded in 1855. It was at first a Hindi school, but gradually Persian was introduced. In 1875 it became a Government Anglo-Vernacular Middle school, and subsequently, in 1884, it was raised to the status of a High school. It consists of two large buildings, one for the Middle and Primary Departments, and the other for the High Department.

The former is situated outside the Delhi Gate of the Ferozepore city, and consists of two large halls, separated by a covered passage, with a verandah all round. There is a small garden attached to it.

The latter is a two-storeyed building situated to the south of the Middle school building, and consists of four large rooms. Behind it is a small cricket ground.

Not far from it, and in the same compound, stands a small boarding-house, which accommodates some 25 boarders; some of the boarders are lodged in a separate rented house near the Government *sarāi*.

\* To the Mukatsar Primary school is attached a Gurukkhi School.

**Chapter V.****Administration  
and  
Finance.****The District School.**

There are three branches attached to the Main school :—  
 a. City Branch school, which meets in a public building ; a Hindi Branch, which meets in a rented house ; and a Jubilee Branch, which was newly created in 1887, also meets in a rented house.

There are two departments in the school, Secondary and Primary ; these being again subdivided into High and Middle, Upper and Lower Primary Departments.

The school is managed by a Head Master and three assistants, who are borne on the Graded Provincial List, and 18 other teachers attached to the Middle and Primary Departments.

The following comparative table shows the figures representing—

- (a) the amount of expenditure ;
- (b) the number of pupils ;
- (c) results of examinations during the last six school years, beginning from the 1st November 1883, ending 30th October 1889.

Balances showing Expenditure, Number of Pupils, and Results of Examinations from 1882-83 to 1886-87 at the District School, Ferozepore.

Year.	Expenditure.	Results of Exams.	Balances.									
			Expenditure	Number of Pupils								
1882-83	—	Dr. & Cr.	1,119 10 9	1,221 7 8	441 6 8	30 15 9	100 11 11	—	100	104	—	—
1883-84	—		1,721 10 4	1,600 11 9	129 9 8	89 14 3	100 10 8	10	27	128	204	1
1884-85	—		3,002 0 11	4,275 15 4	554 11 3	77 14 8	1,012 11 2	31	107	602	146	—
1885-86	—		3,000 14 9	4,258 17 4	107 1 3	122 11 3	112 10 9	26	46	126	279	14
1886-87	—		3,002 0 14	4,260 18 7	126 8 0	119 1 0	112 12 0	47	27	116	207	18
1887-88	—		4,327 1 2	4,211 7 11	129 14 2	120 14 3	105 7 0	30	40	74	8	22
1888-89	—		4,327 1 2	4,211 7 11	129 14 2	120 14 3	105 7 0	30	40	74	8	22

**Chapter V.**  
**Administration**  
**and**  
**Finance.**

The District School.

Statement showing number of scholars and result of Examinations of the Ferozepore Government School from 1883-84 to 1890-91.

YEAR.	Number of Scholars.			Number of Candidates Passed.			Remarks.
	Male	Female	Total Primary	Male	Female	Total Primary	
1883-84	29	62	210	7 out of 9	12	43	Expenditure per month at present is as follows. —
1884-85	22	79	217	4 out of 4	13	42	R. a. p. Teacher's pay ... 254 9 0
1885-86	41	79	219	7 out of 9	20	56	Social services pay — — 30 0 0
1886-87	47	82	229	8 out of 10	21	53	Contingencies ... 40 0 0
1887-88	77	102	189	8 out of 10	26	57	Total ... 220 9 0
1888-89	92	99	191	7 out of 10	22	56	Charged to Provincial Fund Rs. 120-120-0. The rest paid by the State Government out of its annual revenue and surpluses.

Medical.

There is a Civil Hospital at Ferozepore, a second class dispensary at Zira and a third class at Mukatsar. They are all under the general control of the Civil Surgeon, and in the immediate charge of an Assistant Surgeon and two Hospital Assistants. Besides the above-mentioned dispensaries, there is also a third-class dispensary at Jalalabad in Marnot, which is wholly maintained by the Marnot State. There is a Lock Hospital of the first class in cantonments, which was opened in 1887. Table No. XXXVIII shows the working of the District dispensaries for the last few years.

The date of the foundation of the Ferozepore Civil Hospital appears to be 1850. Formerly it was called a first class dispensary, but in the year 1851 it was raised from a first class dispensary to a Civil Hospital. It is situated about 100 yards south-east of the Delhi Gate of the city. The building contains two large wards situated on either side of operating, examination, dispensing, waiting, and Civil Surgeon's office rooms. These wards are for male in-door patients, one being reserved exclusively for Hindus and the other for Muhammadans. There is a separate female ward close to the main building. A small house for small-pox or cholera cases is situated at some distance from the dispensary compound. The Civil Hospital can afford accommodation for 52 beds.

The Police Hospital has been removed to a new building close to Police line in the Cantonment, and the old building taken over by the Municipal Committee for other purposes. A new Jubilee eye ward has been built, having a ward on either side of operating, and dark examination rooms, with bath-rooms and a verandah on three sides. This eye ward can accommodate four

patients, and can also be utilized for poor Europeans and Eurasians. The hospital is in charge of an Assistant Surgeon permanently attached to the hospital, under the supervision of the Civil Surgeon. The establishment consists of one compounder, one dresser, and menials. The number of major surgical operations performed during the last five years is shown in the margin.

St. Andrew's Memorial Church contains sittings for 588 persons, and is served by a Chaplain on the Bengal Establishment of the Church of England. A large Roman Catholic Chapel has lately been built. The services are conducted by a Roman Catholic Chaplain. There is also a branch of the American Presbyterian Mission in the city. The Minister officiates as Chaplain to the Presbyterians among British troops, holding service for them in the prayer-room in cantonments.

The head-quarters of the North-Western Railway are at Lahore. The Rajputana-Malwa Railway is managed by a Traffic Superintendent at Ajmere and District Traffic Superintendent at Sisra.

The Chief Engineer's head-quarters are at Ajmere, and the Executive Engineer's at Sisra. The Sirhind Canal is under the charge of the Executive Engineer, 4th Division, with head-quarters at Ferozepore. But a part of the canal in this district belongs to the 3rd Division, of which the head-quarters are at Ludhiana. The head-quarters of the Sirhind Canal Circle, under the Superintending Engineer, are at Umballa. The Grand Trunk Road from Ganda Singhwala to the 220th mile on the Ludhiana road is in immediate charge of a Subdivisional Officer of the Public Works Department, subordinate to the Executive Engineer, Jullundur Provincial Division, under the control of the Superintending Engineer, 2nd Circle, with head-quarters at Mooltan.

Chapter V.  
Administration  
and  
Finance.

Ferozepore Civil Hospital.

Ecclesiastical.

Head-quarters  
of other depart-  
ments.

**Chapter V.****Administration  
and  
Finance.****Head-quarters of  
other departments.**

The military buildings, fort and arsenal are in charge of the Executive Engineer, Ferozepore Division, Military Works, with head-quarters at Ferozepore, and the Superintending Engineer, Sircim and Lahore Commands, with head-quarters at Lahore. The telegraph lines and offices of the district are controlled by the Assistant Superintendent at Umballa. The district post offices are under the Postmaster at Ferozepore, who is in direct subordination to the Postmaster-General of the Punjab. The Executive Commissariat Officer is under the Deputy Commissary-General, Meem Moor.

**Cantonments,  
troops, &c.**

The district of Ferozepore has but one military station in it—the cantonment of Ferozepore itself, situated about five miles east from the river Sutlej and about two miles from the city of the same name, and 75 miles from Ludhiana. The roads to Lahore, distance 45 miles, and to Ludhiana, and also to the town of Faridkot are metalled. The cantonment is well laid out and planted. Water is supplied by wells at an average depth of 25 to 30 feet in cold and hot weather respectively. The main feature of the station is the fort, which encloses the arsenal. This important and vast establishment is the source from which all the military stores and material are supplied to the southern part of the Punjab and Derájat. The garrison of the fort consists of a detachment of British Infantry and a garrison battery with its proper armament of guns. The cantonment is situated on a flat, acid plain, with no elevated features to relieve the monotony of the view.

The garrison consists of one Battery Field Artillery, one

	Number of Companies allowed on each post.	Number of Non-Commissioned Officers and Men.
Field Artillery.	3	302
Garrison No.	2	132
British Infantry.	21	631
Native Cavalry.	11	622
Do. Infantry	24	609
Staff, &c.	22	—
Total.	79	2,724

Battery Garrison Artillery, one Regiment European Infantry, two Regiments Native Infantry, and one Regiment of Native Cavalry. The number of troops cantoned at Ferozepore in the year 1880 is shown in the margin. The divisional

head-quarters of the garrison is at Lahore.

A large Commissariat Department is established here, and is the principal depot for the supply of gun and siege train bullocks for the Punjab. These fine animals are bred at the Government farm at Hisar and are drafted into the service at four years of age. There are about 500 bullocks kept up here at all seasons ready for immediate use, and about 150 camels.

The district contains a large number of carts which are used in the grain trade; and camels in large numbers could be obtained at a few days' notice.

Within a radius of 20 miles are situated the famous battle-fields of the Sikh War.

Table No. XXIX gives figures for the principal items and totals of land revenue collections since 1868-69. Table No. XXXI gives details of balances, remissions, and agricultural advances for the last fourteen years; Table No. XXX shows the amount of assigned land revenue; while Table No. XIV gives the areas upon which the present land revenue of the district is assessed. Further details as to the basis, incidence and working of the current Settlement will be found on the following pages.

In 1840 Captain Lawrence made for the first time a five years' Settlement of *parganas* Ferozepore consisting of 64 villages, the *jama* of which was fixed at Company's Rs. 19,000, inclusive of *tum* lands. This term expired in 1845, and Captain Nicholson then continued the Settlement for one year longer at the same rate from *zhari* 1845 to *zabi* 1846, and Mr. Daniell extended it for one year till the end of 1847; and Major F. Mackeson, the Commissioner and Superintendent, increased the amount of assessment by one-third, or to twenty-five thousand rupees, at which rate it remained till the Revised Settlement by Mr. Brandreth in 1855. The other *parganas* comprised in the Ferozepore district, and annexed from the Sikhs' Government at Lahore after the Campaign of 1845, were also summarily assessed from 1846 till the end of 1856; but, owing to the absence of statistics, it is impossible to supply an accurate account of them. In 1856, the *zila* of the Nawab of Mambat was summarily assessed after its annexation in November 1855. It consisted then of 242 villages and 79 *chaks*, which were surveyed and mapped under the supervision of Mr. Thomson, Assistant Commissioner, and Muhammad Sultan, Extra Assistant Commissioner. The total *jama* proposed amounted to Rs. 33,786, inclusive of the sum of Rs. 6,223 derived from lease of jungle tracks, and the average rate of assessment was 12 annas a *ghumaria*. Originally this Settlement was sanctioned for a period of five years, but it lasted till the first Regular Settlement of *zilas* Muktsar in 1871-72. The statement showing by *talukas* the *jama* of the district for the last year in which the Summary Settlement was in force, as compared with the *jama* of the Regular Settlement, is given on the following statement showing the *jama* of the Summary and Regular Settlements of Ferozepore District:—

Name of Taluk.	Jama of the Summary Settlement.			Jama of the Regular Settlement.			Remarks.
	Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	
Ferozepore	27,014	14	0	36,110	0	0	Rs. 8,097 on account of <i>jama</i> of the eight villages of <i>zila</i> Chirka, are deducted, because those villages were given to <i>zila</i> of Kalan, and Rs. 61,000 was added to the <i>jama</i> of <i>zila</i> Khurree. Moreover, the Regular Settlement had been effected in 1872.
Zira	3,27,062	-1	0	3,46,014	0	0	
Moga	4,20,128	73	0	4,27,000	0	0	
Muktsar	1,01,909	0	0	1,11,807	0	0	
Total	42,415	23	0	51,391	0	0	

Chapter V.  
Administration  
and  
Finance.

Statistics of land  
revenue.

## Chapter V.

Administration  
and  
Finance.Statement of land  
revenue.

**Summary and re-**  
**gular assessments**  
**compared.**

The operations of a Regular Settlement were set on foot under Mr. E. L. Brandreth, Deputy Commissioner of the district, early in 1852, and were brought to a close in 1853. The new assessment received sanction in the following year for a term of 30 years, to expire in 1882, with a proviso leaving the assessment of the Mukatgar Taluk open to revision after ten years. This course was adopted at Mr. Brandreth's own suggestion, on the ground that the Mukatgar villages had been only recently acquired, and were in an exceedingly backward condition, and might be expected to develop rapidly. In accordance with this proviso, when the Montgomery District was placed under Settlement in 1868, the Mukatgar Taluk, together with the Mamdot territory (annexed in 1864), was added to the charge of the Settlement Officer of that district. The revision of the assessment was completed in 1871-72.

The summary assessment of the district, as constituted at

Description.	Summary Settlement.	Regular Settlement.
<i>Khalsa</i>	Rs. 3,77,409	Rs. 4,16,233
<i>Jigir and Mafat</i>	— + 1,21,251	— + 35,000
Total	Rs. 4,98,660	Rs. 4,50,233

the time when Mr. Brandreth's Settlement operations commenced, amounted to Rs. 4,98,660, of which Rs. 3,77,409

represented the actual State revenue, the remainder (Rs. 1,21,251) being alienated in *jigir* or remitted as *mafat*. Mr. Brandreth's assessment of the same area amounted to Rs. 5,03,438. The table given in the margin indicates the comparison between the two assessments. Before the conclusion of the Regular Settlement operations, however, other villages were attached to the district; and these being assessed at Rs. 1,16,233, the total assessment of the district, as finally concluded by Mr. Brandreth, was brought up to Rs. 6,19,875, of which the State share (*khalsa*) amounted to Rs. 4,16,233.

This assessment, however, was to be partly progressive; and the full sum here mentioned was not to be reached until after a period of years differing in different parts of the district. Taking the year 1855-56 as the first in which the new assessment took effect over the whole district, the following detail may be given of the initial and ultimate amounts of the revenue\*:

Taluk.	Bereas. 1855-56.	Ultimate revenue to be realized after term of years.	Year in which the revenue was to reach its full development.
Venjapore	Rs. 72,913	Rs. 36,343	1873-74
Zira	+ 1,80,000	+ 1,80,000	1873-74
Mamdot	+ 1,16,233	+ 1,16,233	1881-82
Mukatgar	+ 22,632	+ 35,000	1881-82
Total	Rs. 4,98,660	Rs. 4,50,233	—

\* The figures of this statement are taken from an Appendix to Mr. Brandreth's report. It will be seen that the total does not agree with that before given (Rs. 4,46,385). The difference seems to be due to re-arrangements of *khalsa* and *jigir* revenue.

In 1876 Mr. Purser reported his re-settlement of Mukatsar and Mamdot. In the former he revised Mr. Brandreth's assessments, which had [as already explained] been announced for a term of ten years only. In the latter he made a first Regular Settlement. In Mukatsar, Mr. Brandreth had imposed an initial demand of Rs. 47,477, rising gradually during its ten years' currency to Rs. 62,729; cultivation had since then increased by 81 per cent., and Mr. Purser finally assessed the tract at Rs. 98,330, being an increase of over 53 per cent. A further increase of Rs. 3,215 was demanded after ten years in certain villages in which the culturable area was exceedingly large.

Chapter V.  
Administration  
and  
Finance:

Re-settlement of  
Mukatsar and Mam-

In Mamdot, which had received an addition of 16 river estates since the Summary Settlement, the revenue had already been raised during currency of Settlement from Rs. 33,785 to Rs. 45,770. On the other hand, cultivation had increased by some 140 per cent. Mr. Purser assessed the tract at Rs. 63,093, rising to Rs. 67,440 after 10 years. The Settlement, both in Mukatsar and Mamdot, was sanctioned for a term of 20 years, dating from the *kharif* of 1872-73 in Mamdot and of 1873-74 in Mukatsar.

The Settlements and the dates on which they expire are thus distinct for Mukatsar, Mamdot, and for the northern part of the district. Since the announcement of the demands, the normal operation of alluvion and diluvion and similar causes, has reduced the fixed land revenue demand to Rs. 5,16,405.

The current assessment of the Fazilka Tahsil was made by Mr. Fazilka assessment. J. Wilson in 1881, as a part of the Sirsa District, revising the first Regular Assessment of that district, which was made in the years 1852-53. He at the same time revised the assessment of *pargana* Babak, which had been assessed by Mr. Brandreth in 1857-58, as part of the Perozepore District, on the deposition of the Nawâb of Mamdot, but which had afterwards been transferred to Sirsa. The results for the Fazilka Tahsil as then existing were an increase of revenue from Rs. 54,999 to Rs. 94,650, equivalent to 72 per cent. on the amount of the former demand.

Unripened crops ... ... Rs. 68 per acre  
Flooded crops ... ... { " 652 " "  
Well crops ... ... " 44 " "  
 owing to the uncertainty of the cultivation, which depends on the extent of the floods of

the season, 51 villages were wholly or partly placed under a system of fluctuating assessment based on the crop rates stated in the margin.

The incidence per acre of the revenue in the tract left under fixed assessment is about 3 annas per acre.

The assessment of the northern part of the district, which was made by Mr. Brandreth for a period of 30 years, expired in 1882-83. Operations for the revision of the Settlement were commenced in 1884, and were carried out by Mr. E. B. Francis, Settlement Officer. The Moga Tahsil was re-assessed with effect

Revision of Settle-  
ment, 1884-85.

**Chapter V.**  
**Administration**  
**and**  
**Finance.**

Revision of Settle-  
ment, 1884-85.

from *kharif* 1887, and the Zira and Ferowspore Talukas with effect from *kharif* 1888. The results of the new Settlement are shown

	Total	Former Revenue	Revised Revenue
Muga	—	Rs. 2,60,227	Rs. 4,20,700
Zira	—	Rs. 1,00,007	Rs. 2,20,213
Ferowspore	—	Rs. 30,000	Rs. 10,150
Total	—	Rs. 3,90,234	Rs. 6,50,922

by Colonel Grey's system of inundation canals.

The revenue derivable from this last named source will be about Rs. 30,000 per annum. Thus the total increase of revenue is about Rs. 2,87,000, equivalent to 60 per cent. on the amount of the former demand.

The revision of the assessment of the Mukatsar and Mamdot parganas was undertaken by the same officer immediately on the completion of work in the northern part of the taluk, but the revised assessments will not take effect until 1892-93 in Mamdot and 1893-94 in Mukatsar.

Current Settlement.

Class of Land.	Year of Assessment	Hectare Rate	Hectare Rate
Irrigated from wells	1882	Rs. 6/-	Rs. 6/-
	1882	Perwell Perwell	Perwell Perwell
	1889	12/-	12/-
	1890	12/-	12/-
Muga (settled)	1890	6/-	6/-
	1892	6/-	6/-
	1893	1/-	1/-
	1895	1/-	1/-
Dry	—	—	—
	1882	6/-	6/-
	1888	6/-	6/-

The areas upon which the revenue is collected are shown in Table No. XIV, while Table No. XXIX shows the actual revenue for the last 14 years. The statistics given in the following tables throw some light upon the working of the Settlement:—Table No. XXXI, Balances, remissions, and taluk advances; Table No. XXXII, Sales and mortgages of land; Tables Nos. XXXIII and XXXIII A, Registration.

Cesses.

Government lands,  
forests, &c.

Cess.	Percentage, Muga, Zira.	Mukatsar and Mamdot.
Local rate	Rs. 6/- P.	Rs. 6/- P.
Lumberdries	—	—
Patwari	—	—
Road	—	—
School	—	—
Post	—	—
Chief bazaar	—	—
Zamindar	—	—

by talukas in the margin. The figures given are those of the total demand without distinction between State revenue and assigned revenue. Law crop rates of 12 annas and 6 annas per *ghumāo* were also imposed as a water-advantage revenue on lands irrigated

are shown in the margin in percentages. Table No. XVII shows the area and income of Government estates. Table No. XLIX shows the area of land acquired by Government for public purposes. There are no forests in the district.

Table No. XXX shows the number of villages, parts of villages, and plots, and the area of land of which the revenue is assigned, the amount of that revenue, the periods of assignment, and the number of assignees for each tahsil as the figures stood in 1881-82. The principal *jagirs* are those of Mamdot, Mahršāj, and Bhūchān, the Dhūls of Arnanli, Sūduwāl and Jhāmlia, and the Sodhs of Buchchā.

Mr. Brandroth thus describes the origin of the minor revenue free grants of the district:—

"It is impossible within reasonable limits to describe all the different kinds of grants that have been upheld. These conferred in perpetuity are generally for the support of Hindu or Muhammadan places of worship, for the maintenance of tombs, for keeping up dhārāsāls or resting-places for travellers, for schools, for perpetual almsgivings, and such like purposes. The Rāni of Ferozepore always gave a small maintenance in land to the widows or heirs of those who fell in the numerous wars which she waged against her neighbour, the Chief of Faridkot. The Kardars of the Lahore Government gave small rent free tenures to those who had rendered them any service, to *fakirs*, to those who sunk wells for the public good, &c. These and such like grants have been upheld either for life or for the term of Settlement. Besides the rent-free tenures referred to above, there are also villages and shares in villages, and separate plots rent-free in the persons of Rāj-Kapura, which was made over to the Rāja of Faridkot as a reward for the good services rendered by him during the Sutlej Campaign, and regarding which it has been decided by superior authority that a separate account should be taken of them. The value of these estates is Rs. 9,143, of which Rs. 1,410 have been confirmed in perpetuity. In lieu of the remainder, as it appears by the deaths of the present occupants, certain villages on the borders of this district, and now belonging to Faridkot, will be annexed."

A full account of the introduction and the history of the inundation canals of the Ferozepore District is to be found in the printed reports of 1875, by Mr. H. C. Fanshaw, C. S., and that of Colonel Grey, for 1876-77. These canals are in charge of an Extra Assistant Commissioner as Superintendent, who has under him one Assistant Superintendent, an Overseer, two *sait-tahsildars*, five *dārīgahs*, and a few other subordinate officials. The total cost of the establishment for the Ferozepore canals is about Rs. 9,800 per annum. The Extra Assistant Commissioner in charge has judicial powers, which are confined to cases connected with the administration of the canals. From September 1883, the canals of the Fāzilka Tahsil have also been placed under the charge of the Ferozepore establishment with some addition thereto, sanctioned by the Government, the annual cost of which amounts to about Rs. 1,200. Thus the entire cost of the present canal establishment is about Rs. 11,000 per annum. About the middle of October of each year, when all the canals are dry, the Extra Assistant Commissioner starts on tour, and inspects every head of canals, and whenever a change in the course of the river makes it necessary to find a new head for any of the canals, a suitable head is searched out there and then, and the Overseer is ordered to survey it at once, in order to fit it into the existing channel of the canal; at the same time the silt deposited by the canals during the previous

**Chapter V.**  
Administration  
and  
Finance.  
Assignments of  
land revenue.

Minor assignments.

Administration of  
inundation canals.

**Chapter V.**  
**Administration**  
**and**  
**Finance.**

Administration of  
Irrigation canals.

season is measured up, and thus it is found for each canal how much work the *absoh* has to do by dividing the cubic contents of the whole work of the number of acres irrigated by the same canal. When it is found how much work is to be done by each *absoh* village on the different canals, orders are issued for the clearance of silt, and while this is being done by the people themselves under the supervision of the out-door establishment, such as *muk-tahsildars* and *darogahs*, &c., the Extra Assistant Commissioner, and his assistant go round and see the work carried on. When all the work is completed it is examined by the Surveyor, and, if found correct, passed by the Extra Assistant Commissioner, which generally takes place from end of April to end of May in every year, while the canals are opened. While the canals are running the out-door establishment look after the embankments and *bunds* during the time of high floods, special watchmen are appointed to watch the *bunds* and embankments night and day; and in the meanwhile the head of the canals are inspected by the head office establishment, as occasion requires, to find out how the heads of the canals are drawing water from the river.

In October, when the *girdawari* or field inspection of the kharif crop is made the *pattwari* records the irrigated area, the *mirab* and the canal *darogah* assisting, and the record is checked by the *girdawari* and the *tahsildar* or his *naih* when the returns are complete and papers received at the canal office, a date is fixed during the month of December of each year to hold a general meeting at a central point presided over by the Deputy Commissioner for the purpose of fixing the *bikhi*, or rate, for the ensuing year, which is done as follows:—

First, the detail of the area irrigated by each canal is read before the meeting; then the charges for the approaching year (beginning from April) are considered, and the latter distributed over the former. The rate per *ghumla* is thus found, which varies according to the increase and decrease in irrigation in each year. The highest rate hitherto charged was Re. 0-1-0 per acre, and the lowest Re. 0-2-3. Each canal has a certain number of *mirabs*, or water distributor, whose duty it is to assist the *darogah* of the canal in fixing the terms for the *absohs* for taking water. These *mirabs* are, as a general rule, appointed from such lumberdars and landholders, as have helped the cause of irrigation and take an interest in the development of the scheme, and are paid four pies for every *ghumla* irrigated, which amount, together with the two pies per *ghumla* for the *pattwari* who records the irrigated area, is charged to the *absoh* in addition to the rate or *bikhi* which the latter has to pay for the maintenance of the establishment. These canals irrigate over 150,000 acres each season.

**Sirhind Canal.** Two branches of the Sirhind Canal flow parallel to each other through the district in a direction generally north-east and south-west. The more northerly branch is termed the Abroar Branch and the southerly one the Bhatinda Branch.

The Abohar Branch enters the district at 39½ miles of its length in the lands of Dāodhār, where its bed width is 74 feet and its maximum carrying supply 71 feet depth of water, and terminates its course as a main canal, 120 miles from its head, near the village of Abohar, Fālikot Tāhīl, where its capacity has been reduced to a bed width of 22 feet and a maximum depth of water 6 feet. The water is, however, carried on for another 18 miles in a main distributary called the Panjāwa Rājbaha, which ends on the boundary between this district and the Bikaner State into which surplus water is delivered.

Chapter V.  
Administration  
and  
Finance.

Sirhind Canal.

The Abohar Branch is bridged at the following points :—

- 42 miles, Dāodhār lock and fall, inspection choki.
- 46 " Hadīni bridge.
- 48 " Rāmā loot-bridge.
- 51 " Ghōla fall, inspection choki.
- 54 " Phūlāwāla bridge.
- 58 " Chiniwāla fall, inspection choki.
- 60 " Dātewal foot-bridge.
- 64 " Samīsar Bridge.
- 66 " Samīsar fall, inspection choki.
- 72 " Sibīn fall.
- 74 " Dhūlwāla bridge.
- 77 " Dhaipet (Faridkot State) bridge, inspection choki.
- 77 " Rewār-Perozepore Railway bridge.
- 79 " Uhalpet foot-bridge.
- 81 " Naws Hari (Faridkot State) fall.
- 86 " Purana Hari bridge.
- 90 " Assalimtar bridge, inspection choki.
- 94 " Bhullar bridge.
- 99 " Sethia bridge.
- 102 " Mahārājwāla bridge, inspection choki.
- 105 " Sohakī foot-bridge.
- 107 " Jhurrā bridge.
- 111 " Akānwāla bridge, inspection choki.
- 113 " Sarwan fall.
- 116 " Kuttanwāla bridge.
- 120 " Chāndau Khēra bridge.
- 123 " Gohindgārt bridge, inspection choki.
- 126 " Regulator Panjāwa Rājbaha.

In addition to the inspection chokis mentioned above others have been built on certain main distributaries or rājbahis. These are :—

Rājbaha.	Choki.
Dhūlkot, 8 miles	Dhūlkot (Faridkot State).
Faridkot, 10 "	Dewāwāla (Faridkot State).
Ditto, 17 "	Dhimawāla (Faridkot State)
Ditto, 27 "	Biring.
Jaitū, 9 "	Jaitū (Nābhā State).
Ditto, 19 "	MaBān.
Ditto, 27 "	Chatiāna.
Arūwāla, 8 "	Mahāmūdar.
Ditto, 19 "	Dhīpanwāla.
Ditto, 28 "	Kamīlwāla.
Panjāwa 6 "	Churiwāla.

The Abohar Branch irrigates a large part of this district and portions of the Faridkot, Patiala and Nābhā States. The irrigation is done by 14 main distributaries or rājbahis from which

**Chapter V.**  
**Administration**  
**and**  
**Finance.**

**Sirhind Canal.**

smaller channels termed minors or *kassis* carry water to out-lying villages, and distribute it more equally. The system of irrigation is complete, with the exception of an extension to be made to an area in the south-west corner of the Fazilka Tahsil near the border of the Bikaner State.

At the 48th mile of the Abohar Branch the Sutlej Navigation Channel has its head, and, running in a north-westerly direction, tails into the river Sutlej between the villages of Palla and Megha.

This branch has a total length of 47 miles and bed width of 30 feet ; the banks, however, have been so arranged as to allow of its being widened to 60 feet hereafter, if necessary. The branch is not intended to be used for irrigation generally, though it has been found necessary to allow a small *rājbāla* from it for land which could not be watered from the Abohar Branch. The channel is intended for navigation purposes only, though also designed so that it can be used as an escape for the Abohar Branch. It is bridged at the following places :—

0 mile	Banis lock.
2 miles	foot-bridge.
5 "	Chhirah lock and fall.
8 "	foot-bridge.
10 "	Ghal lock and fall, inspection <i>choki</i> .
12 "	foot-bridge.
15 "	Jaimalwala lock and fall.
18 "	foot-bridge.
19 "	Baraghari lock and fall.
22 "	Phidda lock and fall, inspection <i>choki</i> .
24 "	Mudki bridge.
27 "	Pathi lock and fall.
28 "	foot-bridge.
32 "	Ghal lock and fall.
33 "	Phurnashahr bridge, inspection <i>choki</i> .
36 "	Ugoki lock and fall.
40 "	Wahr bridge, inspection <i>choki</i> .
43 "	foot-bridge.
45 "	Isewala bridge.
47 "	Palla lock and fall, inspection <i>choki</i> .

Navigation is continued up to the city of Ferozepore by a still water channel, 4 miles long, called the Ferozepore Navigation Channel, which, taking out of the Sutlej Navigation Channel just below the Isewala bridge, runs first close along the district road, and then occupies a portion of the Sukkar Nala, a former river channel, and finally ends close to the city walls.

There is a needle lock on it from the Sutlej Navigation Channel and two foot-bridges over it in the 1st and 2nd miles.

Navigation cannot be carried on in the lower portion of the Abohar Branch below the 51st mile fall, though the bridges have been specially built for traffic hereafter, should it be decided to build the necessary locks.

Good unmetalled roads for country carts have been made along the boundaries of both the Abohar Branch and Sutlej Navigation Channel. All inspection *chokis* are furnished. Well-

built mill-houses and grain godowns have been erected for grinding flour by water-power, at the Gholia, Chinowal, Samalsar, Sibián, Nawa Hari and Samwan falls on the Abchiar Branch, and the Baraghari, Phiddia and Ghat falls on the Sutlej Navigation Channel. Each mill-house contains 5 pairs of stones worked by native *panchakkis* or water wheels.

The Bhatinda Branch traverses the *pargana* of Mahráj and a portion of the Patiala State, and also two villages, Thoona and Jhumba of the Mukatsar Tahsil, and distances 100 miles from the head in Patiala territory within 3 miles from the district boundary. At the fall is a regulator from which bifurcate two large *rājbahás* which irrigate a large number of Fárikha villages. There are in all 6 large *rājbahás* or main distributaries, which with their branches and minor channels irrigate a large area of the Mahráj, Mukatsar and Fárikha Tahsils and the Párikot and Patiala States.

The Bhatinda Branch is bridged at the following places :—

67 miles	Mári bridge.
71	Pabla bridge, inspection choki.
79	Gobindpura bridge.
82	Bibiwála fall, inspection choki.
82	Bhatinda fall.
82	Rájputáns-Máluwa Railway bridge.
84	Bhatinda road bridge.
90	Thoona fall, inspection choki.
93	Jhumba bridge.
96	Jaangirán bridge.
100	Raike Regulator, inspection choki.

Besides the above-named inspection houses, the following have been built on main distributaries :—

*Koi Khil Rājbahá.*

8 miles,	Goniam (Párikot State) choki.
20	" Virak do. do.
29	" Hässner.

*Thoona Rājbahá.*

19 miles,	Mathna choki.
<i>Sukkharis Rājbahá.</i>	

16 miles,	Rasúlpur choki.
-----------	-----------------

Good unmetalled roads for country carts have also been made along the boundaries of the Bhatinda Branch.

A set of flour mills with godowns containing 10 pairs of stones, has been erected at the Bhatinda fall, 82nd mile.

Chapter V.  
Administration  
and  
Finance.  
Sircind Canal.

## CHAPTER VI.

### TOWNS, MUNICIPALITIES AND CANTONMENTS.

#### Chapter VI.

#### Towns, Municipalities and Cantonments.

General statistics Ferozepore District.—

Taluk.	TOWN.	Persons	Males.	Females.
Ferozepore	Ferozepore	30,370	15,371	15,000
Zira	Zira	9,007	4,862	5,144
Zira	Dhankot	—	—	—
Zira	Zira	—	—	—
Moga	Moga	1,000	511	489
Moga	Boga	—	—	—
Moga	Makhu	—	—	—
Muktsar	Muktsar	3,100	1,550	1,550

The distribution by religion of the population of these towns and the number of houses in each are shown in Table XLIII, while further particulars will be found in the Census Report in Table XIX and its Appendix and Table XX. The remainder of this chapter consists of a detailed description of each town, with a brief notice of its history, the increase and decrease of its population; its commerce, manufactures, municipal government, institutions, and public buildings; and statistics of births and deaths, trade and manufactures, wherever figures are available.

#### Ferozepore town: Description.

The town of Ferozepore is situated in N. latitude 30° 57' and E. longitude 74° 39', 645 feet above the sea level, on the old high bank of the Sutlej, 3½ miles from the present bed of the river. It is surrounded completely by a *kacha* wall with ten gates, of which the Delhi and Lodhiāna towards the south, the Makhu towards the east, the Bānīkuwāla towards the north, and the Kasur and Mooltan gates on the west, are the principal. By far the greater portion of the grain traffic enters the city by the Lodhiāna Gate.

A metalled circular road girdles the wall round the city, and is 23,870 feet long. Some of the gardens in the city belonging to the native inhabitants lie along this road. The town is surrounded on all sides by hamlets twelve in number. The

principal of them are Basti Rahmán Tihári, towards the south, opposite the jail; Basti Tenkánwali, towards the south-east; Basti Shaikha-wali on the east; Basti Kamboháu on the north; Basti Bawárián on the west; and Basti Bhattián, towards the south-west of the city.

The town itself is divided into two parts by the main bázár, which runs from the Delli Gate in the south to the Básánwala Gate in the north, and in which are to be found the shops of almost all the principal men in the city. The other streets are of less importance and have nothing remarkable in them, except the Ludhiána Gate bázár, where wheels for country carts are prepared in large numbers, the village carpenters who build the rest of the cart not being able to put wheels together. The gate of this bázár is of an elegant design, said to have been taken by Mr. Knox, Deputy Commissioner, from some gate at Baghdád, whence it is called the Baghdádi Gate. There are three principal markets in the city, viz., Mandi Shikárpuríán (also called Hirá Mandi), Mandi Nauharíán (also called Pardí Mandi), and Ganj Rámji Dás. The first is, perhaps, the finest of them all, surrounded on all sides with large double-storeyed buildings of the rich men carrying on the trade in iron in this market. The other two are chiefly remarkable for extensive dealings in grain, that take place in them, besides their being used as *dépôts* for the storage of grain.

The streets of the city are generally wide and well paved, but the drainage system is very defective, and stands much in need of improvement. The Municipality have under consideration a new drainage scheme which, when carried out, would greatly enhance the healthiness of the town. Wells, of which there is a large number within the city, constitute at present the only source of water-supply of the town. The water is generally good, but it is believed that the water-table has greatly risen in almost all the wells since the opening of the district canals, of which three are to be found within the municipal limits. One of these canals runs round the greater part of the city.

Ferozepore can boast of no buildings of any architectural importance. The only one that deserves mention in this place is the Hindu temple, called the *Ganga mandir*, having a small garden attached to it, and situated near the Básánwala Gate.

The old fort of the city is now no more, but some traces of it are still left; the tomb of a Mithanimadhan saint, called Nér Shah Vali, situated on an eminence opposite the tahsil indicates its site. The tomb is considered by the Muhammadan community to be a place of great sanctity, and even now large numbers gather around it every Thursday. There are two tanks in the city—one inside the walls, called *Ráni-ka-talíb* after Ráni Lachman Kaur, once the ruler of Ferozepore; and the other outside the Delli Gate and built by the Municipality. Both of these tanks are fed by water from a district canal (the

**Chapter VI.**  
Towns, Municipalities and Cantonments,  
*Ferozepore town Description.*

**Chapter VI.**

**Towns, Municipalities and Cantonments.**  
Ferozepore town  
Description.

Shahirwah). The principal buildings outside the city are the dispensary and the school-house, situated opposite to each other on the Knox Road about 100 yards from the Delhi Gate. The Municipal Hall is a fine building erected at the expense of the Municipality, has a small garden attached to it, and is also situated on the Knox Road a little to the south of the dispensary and the school-house. Near it is the District Board house, a smaller but good-looking building. Still further towards the cantonments and on the east side of the Knox Road is the Ferozepore Jail, having a garden attached to it. There are four sardars outside the city, of which the principal are—one belonging to Rāi Nāgar Mat, and situated on the Knox Road close to the dispensary; and another belonging to Lāla Bām Kaur.

**Cantonments.**

The cantonments lie to the south at a distance of about two miles from the city. They are connected with the city by the Knox Road, the most beautiful road in the station. Large shady trees and green grass line the whole length of the road on both sides; and it is kept clean and well sprinkled with water by the Municipality, and is resorted to for evening walks and drives by all sections of the community. The district court-house is situated within the cantonment limits. The cantonments were first constituted in the year 1839, since when they have been continuously occupied by troops. The garrison is noticed at page 122.

**History.**

Ferozepore was founded, according to one tradition, in the time of Fero Shah, Emperor of Delhi, A.D. 1351—1357, but was in a declining state at the period of British annexation. According to a census taken by Sir Henry Lawrence, in 1838, the population was 2,732; and in 1841, chiefly through the exertions of Sir Henry Lawrence, it had risen to 4,841. The market-place towards the east of the old fort was built by him, and the main bazaar was also completed under his directions, the oldest street in the town being the one now called the Purāna Bāzār. Since the successful close of the first Sikh War, the peace of the district has never been broken, except during the Mutiny in 1857, when one of the native regiments stationed at Ferozepore broke out into revolt and plundered and destroyed the buildings of the cantonments. The arsenal and magazine were, however, saved without loss of life, and the mutineers subsequently dispersed. The population as ascertained at the enumerations of 1868 and 1881 is shown in the margin.

Limits of enumeration.	Year of census.	Persons.	Males.	Females.
Whole town including cantonments.	1868	26,457	13,200	13,257
Municipal limits	1881	26,570	13,971	12,599
	1882	26,582	—	—
	1883	26,570	—	—

The arsenal and magazine were, however, saved without loss of life, and the mutineers subsequently dispersed. The population as ascertained at the enumerations of 1868 and 1881 is shown in the margin.

**Population and vital statistics.**

The constitution of the population, by religion and the number of occupied houses, are shown in Table No. XLIII. Details of sex will be found in Table XX of the Census Report.

Ferozepore District.]

CHAP. VI.—TOWNS, MUNICIPALITIES AND CANTONMENTS. 135

of 1881. The annual birth and death-rates

Year.	Birth-rates.			Death-rates.		
	Persons.	Males.	Females.	Persons.	Males.	Females.
1868	—	—	—	10	4	11
1869	—	—	—	12	5	11
1870	22	11	11	10	5	10
1871	23	12	11	10	5	10
1872	22	11	11	10	5	10
1873	23	12	11	10	5	10
1874	22	11	11	10	5	10
1875	23	12	11	10	5	10
1876	22	11	11	10	5	10
1877	23	12	11	10	5	10
1878	22	11	11	10	5	10
1879	23	12	11	10	5	10
1880	22	11	11	10	5	10
1881	23	12	11	10	5	10
Average —	22	11	11	10	5	10

years is shown in Table No. XLIV.

The municipality of Ferozepore was first constituted in December 1867. It is now a municipality of the second class. The committee consists of two ex-officio members, the Civil Surgeon, and the District Inspector of Schools, and 19 other members, of whom 14 are elected and the rest are nominated by Government. The income of the municipality is chiefly derived from octroi levied on almost all goods brought within the municipal limits.

The district of Ferozepore is pre-eminently the grain-producing district of the Punjab, the staple articles being gram, wheat, and rapeseed. The wheat trade has of late been considerably developed, and large quantities are exported to Karachi for shipment to Europe. The town is a favourite depot for the storage of grain, which remains collected in immense quantities, and is re-exported whenever favorable opportunity is found by the grain-dealers. Iron is also imported in large quantities direct from England, and is then sent out for distribution in the adjoining districts.

The only institutions in the town itself are the Charitable Dispensary and the District School. There is an Orphan Asylum in the cantonments kept up by the local Arya Samaj. Hindu and Muhammadan orphans are well brought up and receive a good training. The expenses of the asylum are defrayed from subscriptions and donations of private individuals.

Dharmkot is a small town of 6,007 inhabitants, situated on the old route to Lohiana from Ferozepore. The original name of Katalpur was changed to Dharmkot by the Sikh Chief Tārā Singh Dallewala, in 1760, when he subdued the sirdars of Kārial and Jālahabad, and built a fort and established himself here. The fort has now disappeared. This place is only a few miles from the Grand Trunk Road between the above two

Chapter VI.  
Towns, Municipalities and Cantonments.  
Population and vital statistics.

per mille of population since 1868 are given in the margin, the basis of calculation being in every case the figures of the most recent census. The actual number of births and deaths registered during the last five

Dharmkot town.

## Chapter VI.

**Town Municipalities and Cantonments.**  
Dharmkot town.

towns; and, as it has a good bazaar and is the only town in this neighbourhood, a considerable trade is carried on here in piece-goods, which are brought to this market via Ludhiana, and sold to all the people in the neighbourhood. There are some well-to-do native merchants here who possess brick houses of two and three storeys high. There is no wall around Dharmkot, nor is there any building of importance. It has a good bazaar mostly of brick shops, a *thana* and school house, and a brick *sarai* with a good well in it, and two rooms for European travellers on each side of the *sarai*. A bricked tank is being made near the town. The Municipality consists of eight members. The members are appointed by nomination. Its income for the last few years is shown in Table No. XLV and is derived from a tax levied on all goods brought in for sale. The reason why the municipal revenue is so small is, that the large dealers and money-lenders of this place do not bring their produce in to the city, but leave it in the villages where it is grown, and so it escapes octroi. There are no *chaukidars*, but a police establishment maintained by the Municipality. Formerly the head-quarters of the *tahsil* were located at Dharmkot. About thirty years ago the *tahsil* was removed to Zira, but it appears that Dharmkot has not suffered in any way from this change. The railway line between Ludhiana and Ferozspore now in contemplation, if constructed, is likely to pass not far from this place, which will probably add to its importance.

The population, as ascertained at the enumerations of 1868, 1873 and 1881 is shown in the margin. The constitution of the population by religion and the number of occupied houses are shown in Table No. XLIII. Details of sex will be found in Table No.

Limits of enumeration.	Year of census.	Per cent.	Males.	Females.
Whole town —	1868	5.275	2,750	2,229
	1873	6.007	3,339	2,824

Municipal limits	1868	5.275		—
	1873	6.007		—

XX of the Census Report of 1881. No separate statistics of births and deaths are available.

## Zira town.

Zira is a small place of 3,432 inhabitants situated on the old unmetalled road from Ferozspore to Ludhiana, about 12 miles from the Grand Trunk Road and 24 miles east of Ferozspore. The grain produced here, as also in the adjacent villages, goes to Ferozspore and Ludhiana, which are both export markets. The town contains mostly mud houses, a bricked tank (not quite complete yet) and a few brick shops. It has two bazaars (no grain market), a *thana*, schoolhouse, a dispensary, a small house for the municipality, and a brick *sarai* with a good well near it, and two rooms on each side of the *sarai* for European travellers. It has no walls. One of the inundation canals passes through Zira, and has improved the appearance of this place by the gardens which have been planted near and at Zira, also six water-mills are worked by the canal during the inundation season. There is also a stable for stallion house and a donkey kept here.

by Government for breeding purposes. The Municipal Committee consists of 10 members appointed by nomination. Its income for the last few years is shown in Table No. XLV, and is derived from an octroi tax levied on all goods brought in for sale. There are no *chaukidars* here, but a police establishment maintained by the Municipality. Zira was formerly an ordinary village when the head-quarters of the *taluk* were at Dharmkot, but since the transfer of the *taluk* from Dharmkot to Zira, about 30 years ago, this place has much improved in every respect, and is increasing in size gradually. In 1853 its population was only 2,702 souls. The population, ascertained at the enumerations of 1868,

Chapter VI.  
Towns, Municipalities and Cantonments,  
Zira town.

Class of town.	Year of census.	Sexes.	Males.	Females.	1875 and 1881, is shown in the margin.
Whole town.	1868 1872 1875 1881	2,702 3,000 3,000 3,000	1,300 1,300 1,300 1,300	1,402 1,400 1,400 1,400	The constitution of the population by religion and the number of occupied houses are shown in Table No. XLIII.
Municipal limits.	1868 1872 1875 1881	— — — —	— — — —	— — — —	

Details of sex will be found in Table No. XX of the Census Report of 1881. No separate statistics of births and deaths are available.

## Makhu town.

Makhu is a small place of 1,658 inhabitants, not far from the left bank of the Sutlej, at the point where it joins the Beas and about 12 miles from Zira. Although there is no market-place, a considerable trade in *gur* and *sakkar* (country brown and coarse sugar) is carried on here owing to the fact that this small town is at the point where traffic towards Ferozepore from Kapurthala and Jullundur crosses another line of traffic between Amritsar and the Moga country. The place is hardly more than one long street or *bazaar* without a wall or any building of importance. It has a *dhana*, wheel-house, and a small brick *caravani* with a room for European travellers in it. The municipality consists of six members appointed by nomination. Its income for the last few years is shown in Table No. XLV, and is derived from an octroi tax levied on all goods brought in for sale. Makhu was a very small place formerly, but since the introduction of the inundation canals by Colonel Grey there is a perceptible improvement in the condition of this place, as also in the villages round about, though it is improbable that it should ever become a large commercial town of any importance. The surrounding country is nearly impassable from June to October. The population ascertained at the enumerations of 1868, 1875, and 1881 is shown in the margin. The constitution of the population by religion and the number of

Class of town.	Year of census.	Persons.	Males.	Females.	occupied houses are shown in Table No. XLIII.
Whole town.	1868 1872 1875 1881	1,658 1,658 1,658 1,658	— — — —	— — — —	Details of sex will be found in Table No. XX of the Census Report of 1881.
Municipal limits.	1868 1872 1875 1881	— — — —	— — — —	— — — —	

**Chapter VI.**  
**Towns, Municipalities and**  
**Cantonments.**  
**Moga town.**

Moga is a large village of mud-houses and shops containing 6,430 inhabitants. The village itself is situated about a mile from the Grand Trunk Road between Ferozepore and Ludhiana; but the *tahsil* and other public buildings stand on the said road about 3½ miles from Ferozepore and 4½ from Ludhiana. There is a considerable trade in grain carried on at Moga and its vicinity with Ludhiana on the one side, and Ferozepore on the other, both being large grain markets and export towns. The village of Moga (it can hardly be called a town) has no wall and possesses no building of any importance; it is divided into two parts, or *patti*, each of which has a single small *bazar* of mostly mud-shops. There is no grain market here, as the cultivators of this place, as also those of its neighbourhood, take the agricultural produce of their locality in their own carts to Ludhiana and Ferozepore. There is a school-house and a small dispensary. This *khana* is included in the same building with the *tahsil*, with a rest-house for police and district officers. There is a brick *sarai* and a small *bazar* opposite the *tahsil* and a bricked tank which is filled in the rainy season with rain water. The water of Moga is slightly brackish, but wholesome. There is no encamping ground at Moga, as it is intermediate between two encamping grounds—Dugri and Mahna. The Municipal Committee of the village of Moga consists of eight members, appointed by nomination. The Municipality was constituted in June 1883. Its income is derived from octroi or *chungi* tax levied on all goods which come in for sale. More than 30 years ago, when the *tahsil* was established at Moga, this village was very small and of little local importance, but it has since improved a great deal owing to the Grand Trunk Road going through it to the two great trading towns; and it is possible that when the railway line between Ferozepore and Ludhiana, now in contemplation, is completed this village may become a populous town on account of its being the centre of the grain-producing part of the district. The population as ascertained at the enumerations of 1861 and 1881 is shown in the margin. The

Year of census	Persons	Males	Females
1861	5,231	2,607	2,624
1881	6,430	3,206	3,224

constitution of the population by religion and the number of occupied houses was shown in Table No. XLIII. Details of sex will

be found in Table No. XX of the Census Report of 1881. No separate statistics of births and deaths are available.

**Mudki town.**

Mudki is a large village with a population, according to the census of 1881, of 3,752 persons, chiefly Sidhu Jats, with some Dogars, &c. It possesses one or two money-lenders of considerable wealth, one of whom has built a brick tank and a temple on the road. There is a rest-house. But there is little trade or traffic. The road to Karnal on which the town is situated is now little used; another road between Zira and Faridkot crosses it here. The Municipality consists of eight members appointed by nomination. No separate statistics of population are available.

Mahrāj is a Sikh village of 5,758 inhabitants, situated to the south of, and about 35 miles from, Moga Tīhsil. It is really an aggregation of four large villages, the head-quarters of the Mahrājkīā Jān, a branch of whom formed the Phalikān clan, to which belong the Chiefs of Patialā, Jind, and Nālīha. A pond called the Tīkhārā is looked upon as sacred, and offerings are made monthly to the guardian priest, who is elected by the whole community. The Mahrājkīān, who are *shāhīdārs* of the surrounding country, form a distinct community. Physically they are a fine race; but they are difficult to control, very litigious, and tenacious of their rights. They have the reputation of eating opium to excess. Mahrāj, although a large village, is not of any importance from a mercantile point of view. It is in the heart of the most sandy part of the district. The agricultural produce of this place and its neighbourhood are taken to Ludhiana for sale. This village contains roomy mud houses and mud shops scattered all over the village without any regular trade. There is no grain market, no *dhāns*, *sāri*, or any other building of importance. There is no Municipality here. The six *chāukidārs* are paid by a *chāukidārī* tax levied per hectare on all residents. No change worthy of notice has taken place in this village during the last 30 years, but, now that a branch of the Sirhind Canal has passed through the lands of Mahrāj, improvements

**Chapter VI.**  
Towns, Municipalities and Cantonments.  
Town of Mahrāj.

Year of census.	Persons.	Males.	Females.
1861	3,601	1,838	1,763
1881	5,758	2,110	3,648

may be anticipated. The population, as ascertained at the enumerations of 1861 and 1881, is shown in the margin. The constitution of the population

by religion and the number of occupied houses are shown in Table No. XLIII. Details of sex will be found in Table No. XX of the Census Report of 1881. No separate statistics of births and deaths are available.

Mukatpur is a small town of 3,125 inhabitants, about 35 miles to the south of Ferozepore, and about 20 miles from the river Sutlej. After Fazilka it is the largest town and principal trade-mart of the western portion of the district. The roads leading to this place from Ferozepore and Sirsa, &c., are very sandy, and in several places almost impassable by bullock carts. But Mukatpur is now on the branch line which runs from Kot-Kapura to Fazilka and its trade is increasing.

Town of Mukatpur.

The town itself is an ordinary collection of native houses, mostly of mud, but a few brick buildings, some of which are two to three storeys high, and a wise man improves its appearance; especially the handsome Sikh shrine or *gurdwāra* with its lofty flagstaff, which stands on a large tank adds not only to the appearance of the place but also to its importance. Guru Gobind Singh's followers were massacred here by the officers of the Muhammadan Emperor, and the place has since become a sacred one to the Sikhs of the surrounding districts. The construction

**Chapter VI.****Towns, Municipalities and Cantonments,  
Mukatsar town.**

of the tank began during Mahâ-âja Ranjit Singh's time, and was completed by the help of the Rajâs of Patiala, Jîat, Nabha and Faridkot.

A village having a revenue of Rs. 2,500 per annum is held in jagir on behalf of the temple. The income is spent in keeping up a *langar*, or public cook-house, where every day poor men and travellers are fed, and also for other necessary expenses, as repairs to the shrine, &c. A large fair is held here every year about the middle of January, when 30,000 to 50,000 people assemble here for two days to bathe in the tank, (see page ante). Mukatsar has a single *bazaar* mostly of brick shops without any wall round the town. There is a school-house, a Municipal Committee house, a dispensary, tahâif, thana, and a brick *sarâi*, with encamping ground, and a good well in the *sarâi*. There are two rooms on each side of the *sarâi* for European travellers. A metalled road connects the *tahâif* and *sarâi* with the Railway station which is on the north side of the town.

The Municipal Committee consists of seven members appointed

Limits of communication.	Year of Service.	Persons.	Males.	Females.
Whole town.	1868 1881	4,023 4,125	2,014 2,062	2,009 2,063
Municipal limits.	1868 1881	2,004 2,062		

ed by nomination. Its income for the last few years is shown in Table No. XIV, and is derived from an octroi tax levied on the goods brought in for sale. The place

is gradually increasing both in size and importance, especially on account of the railway line which passes through Mukatsar. The population ascertained at the enumerations of 1868, 1875 and 1881 is shown in the margin. It is difficult to ascertain the precise limits within which the enumerations of 1868 and 1875 were taken. The figures for the population within municipal limits, according to the census of 1881, are taken from the published tables of the census of 1875; but it was noted at the time that their accuracy was in many cases doubtful.

The constitution of the population by religion and the number of occupied houses are shown in Table No. XLIII. Details of sex will be found in Table No. XX of the Census Report of 1881. No separate statistics of births and deaths are available.

**Fasila town.**

When, in 1844, the tract of country on the Sutlej was ceded by Bahawalpur, there was no village where Fasila now stands; but Mr. Vans Agnew, the first officer stationed there, built himself a bungalow, from which the place became known as *Hangla*, a name still given to the town and the *tahâif* by the people. Two years later Mr. Oliver established a few shops there, and gave the place the name of Fasila from

Fazil, one of the early Watta settlers. Its favorable position near the Sutlej has enabled it to engross almost the whole of the export trade from the great desert tract towards Sind, and made it very soon a flourishing mart, and its population and trade have steadily increased. Its population at the three enumerations which have taken place

Year.	Population.
1881	3,466
1872	4,320
1861	8,122

is shown in the margin. The numbers more than doubled within a period of 13 years. More than two-thirds of the total population are Hindus, and almost all the inhabitants are engaged in trade and operations connected with it. The greater part of the trade is in the hands of Acores from the west and south, some of them branches of important firms of

	Grain.	Sugar.	Ghi.
1881-82	32,124	20,601	32,124
1872-73	46,229	30,861	46,229
1861-62	30,779	18,422	30,779
Total	109,132	69,884	109,132

Mosian, Shikarpur and other towns towards Sind. The imports of grain, sugar, and ghi during the past six years, according to the municipal returns, were as shown in the margin. The trade in grain consists chiefly in

the export of barley, gram and oilseeds from the rohi tract towards Multan and Karachi, and varies with the nature of the harvests and the demand in that direction. Fazilka also exports large quantities of wool and *sajji* from the rohi tract, and imports sugar and articles of metal in exchange. A branch of the Rajputana-Maiwa Railway now runs from Kot-Kupura via Mukatsar to Fazilka, and the trade of the place is increasing. An hydraulic press has been set up for the compression of wool and other bulky articles for railway transit. Fazilka is a second class municipality with a Committee of nine members, of whom one-third are nominated *ex-officio* and two-thirds are elected. Its income which

1881-82	Rs.
1872-73	1,121
1861-62	1,121
Total	1,121

is principally derived from a low octroi on all imports has been as shown in the margin for the last three years. The town has been laid out with wide rectangular streets, and comprises some very spacious market places in which the camel caravans from the

desert country may alight and unload their goods. An Extra Assistant Commissioner, (native) is stationed here in charge of the subdivision. Besides the usual *tahsil* and *thana* buildings, there is a small mud fort made by Mr. Oliver in the Mutiny. His bungalow is still standing, surrounded by a garden some distance from the town, overlooking an old branch of the river. There is a rest-house near the *tahsil*. The school occupies a handsome building, forming part of a well built *sarai*. There is also a dispensary. The town is rapidly extending in more than one direction beyond its original bounds.

Chapter VI.  
Towns, Municipalities and Cantonments.  
Fazilka town.

**Chapter VI.**  
Towns, Municipalities and  
Cantonments.

Fazilka town.

The following statement shows the quantity or value of the chief articles imported which paid duties, in each of the municipal towns in the years 1887-88 and 1888-89:—

Municipal Town.	Year.	Oats.	Sugar.	Ghee.	Other articles	Total value	Dressings	Furniture	Drugs	Leather	Wool
Fazilka —	1887-88	622,427	36,766	5,200	10,749	21,000	8,37,729	1,22,300			
	1888-89	618,013	32,306	3,100	20,000	16,244	8,42,421	1,42,300			
Fazilka —	1887-88	30,719	31,425	1,497	18,723	27,322	7,31,022	31,322			
	1888-89	30,105	30,384	1,000	17,660	25,197	8,25,477	30,322			
Muktesar —	1887-88	18,079	6,442	20	12,107	8,023	6,42,208	11,322			
	1888-89	18,375	6,200	200	9,391	8,145	78,000	11,322			
Bhatinda —	1887-88	37,300	6,379	61	11,100	13,723	44,000	7,200			
	1888-89	46,305	6,305	22	10,113	12,100	32,000	8,000			
Zira —	1887-88	47,210	6,218	260	10,113	8,423	93,868	7,222			
	1888-89	47,200	6,218	167	12,100	8,122	49,200	8,122			
Muktsar —	1887-88	30,279	3,441	74	7,139	2,400	33,331	1,000			
	1888-89	32,249	3,358	12	2,389	1,422	38,000	1,000			
Moga —	1887-88	6,007	2,768	30	6,479	1,043	38,228	1,022			
	1888-89	2,004	2,133	60	3,000	1,217	38,007	2,100			
Mudhol —	1887-88	7,204	2,008	22	2,002	1,362	31,000	776			
	1888-89	9,073	2,030	37	3,078	1,618	32,000	776			

---

STATISTICAL TABLES  
APPENDIX TO THE  
G A Z E T T E E R  
OF THE  
FEROZEPORE DISTRICT.

---

*(INDEX ON REVERSE).*

---

## STATISTICAL TABLES.

	Page		Page
I.—Leading statistics	Frontis-piece	XXIII.—Occupations	xlv
II.—Development ...	iii	XXIV.—Manufactures	li
III.—Annual rainfall	iv	XXV.—River traffic	lii
III A.—Monthly ...	iv	XXVI.—Retail prices	xv
III B.—Seasonal ...	iv	XXVII.—Price of labour	xvi
IV.—Temperature ...	iv	XXVIII.—Revenue collections	lii
V.—Distribution of population ...	li	XXIX.—Land revenue	lii
VI.—Migration ...	v	XXX.—Assigned revenue ...	xvii
VII.—Religion and Sex ...	lii	XXXI.—Balance, remittances, &c.	lii
VIII.—Language ...	lii	XXXII.—Sales and mortgages of land	xviii
IX.—Major castes and tribes ...	xi	XXXIII.—Stamp and registration	xix
IXA.—Minor ...	lii	XXXIII A.—Registration	lii
X.—Civil condition ...	vii	XXXIV.—Licence tax	lii
XL.—Births and deaths ...	lii	XXXIV A.—Income Tax	xx
XIA.— " " (monthly, all months) ...	lii	XXXV.—Bank	lii
XIB.— " " (G. fever)	viii	XXXVI.—District funds	lii
XII.—Infirmities	lii	XXXVII.—Schools	xxi
XIII.—Education	lii	XXXVIII.—Dispensaries	xxi—†
XIV.—Surveyed and assessed areas	lii	XXXIX.—Civil and revenue litigation	xxii
XV.—Tenures from Government	ix—x	XL.—Criminal trials	lii
XVI.—" not from Government ...	xi	XL I.—Police inquiries	xxii
XVII.—Government lands	xii	XL II.—Jails	xxviii
XVIII.—Forests ...	xi	XL III.—Population of towns	xxix
XIX.—Land acquired by Government	xi	XL IV.—Births and deaths (towns)	lii
XX.—Crop areas ...	xi	XL V.—Municipal income	lii
XXI.—Rent rates and yield ...	xiii	XL VI.—Manufactures ...	...
XXII.—Live-stock	xi	XL VII.—Polynomestical table	xxx

Table No. II, showing DEVELOPMENT.

I	2	3	4	5	6	7
Decade.	1880-81.	1884-85.	1885-86.	1886-87.	1887-88.	
Population	—	—	—	—	—	
Cultivated area	900,010	746,120	—	—	—	
Dwelling areas	1,400,000	1,061,000	1,073,000	1,054,073	1,067,572	Taken from agricultural statistics,
" From Government works	100,000	107,000	93,000	100,000	97,000	
Assessment, land revenue, Rs.	4,79,000	4,36,000	7,03,000	7,04,000	7,07,000	Taken from Table No. VIII.
Revenue from land, Rs.	3,11,000	3,00,700	5,47,000	5,20,000	5,29,000	Taken from Table No. III of Administration Report.
Gross Revenue, Rs.	7,84,000	9,03,100	9,77,000	9,18,700	9,09,700	
Number of acres	—	—	360,000	360,000	360,000	
" Sheep and goats	—	—	144,220	167,000	169,000	From Agricultural Statistics No. XXV.
" Cattle	—	—	12,000	14,000	11,000	
Miles of inhabited roads	—	10	—	—	—	
" Unpaved roads	—	110	—	600	870	Taken from Table No. I of Administration Report.
" Pavements	—	—	120	120	120	
Bridges and	—	224	400	477	472	From No. III.
Promenades constructed	—	2,734	2,600	2,300	2,700	
Civil works—number	—	11,744	11,902	11,400	11,102	
" value in Rs.	6,36,000	8,00,000	7,00,000	10,70,000	10,00,000	From District Office.
Municipalities—number	—	8	8	7	7	
" Located in F.D.A.	32,200	21,000	21,200	21,000	21,200	
Dissemination—number of	—	4	2	3	2	
" districts	—	24,412	22,000	21,000	21,000	
Schools—number of	—	—	—	—	—	
" education	—	—	—	2,000	2,210	

\* Part of the Ferozepore District was added to this district in November 1884.

† Estimate of Ferozepore.

Table No. III, showing RAINFALL.

I	2	3	4	5	6	7	ANNUAL RAINFALL IN INCHES IN 100 FEET.					
							1880-81.	1884-85.	1885-86.	1886-87.	1887-88.	Average.
Hill-gauge stations.												
Ferozepore — {	134	129	129	129	129	129	134	129	129	129	129	129
Upper	—	—	—	—	—	—	—	—	—	—	—	—
Lower	—	—	—	—	—	—	134	129	129	129	129	129
Shimla	—	—	—	—	—	—	120	—	120	120	120	120
Moga	—	—	—	—	—	—	129	—	129	129	129	129
Mukteswar	—	—	—	—	—	—	260	129	129	129	129	129
Phoolia	—	—	—	—	—	—	120	129	129	129	129	129

Mukteswar was added to this district in November 1884.

Taken from weekly rainfall measurements.

Table No. IIIA, showing RAINFALL at HEAD-QUARTERS.

1	2	3	4	5	
				ANNUAL AVERAGES.	
MONTHS	Number of rainy days in each month, 1861—1884.	Number of inches of rain fall in each month, 1861— 1884.	MONTHS	Number of rainy days in each month, 1861—1884.	Number of inches of rain fall in each month for the 30 years.
January	1	11	October	4	8
February	1	11	November	3	8
March	1	11	December	1	8
April	1	11	1st January to 30th January	9	11
May	1	11	1st February to 30th April	7	12
June	1	11	1st April to 30th October	11	12
July	1	11	Whole year	21	12
August	1	11			
September	1	11			

Data from the Meteorological Bureau reported monthly to the District Office.

Note.—Plates were added to the data in the following table.

Table No. IIIB, showing RAINFALL at TAHSIL STATIONS.

1	2	3	4	5	
				ANNUAL FALL OF RAIN IN INCHES OF AN INCH FROM 1862-63 TO 1882-83.	
TAHSIL STATION	Total Rainfall per Taluk-District.	1st December to 30th April		1st April to 30th October	Whole year.
		11	11	11	11
Fazilka	11	11	11	11	11
Gurdaspur	11	11	11	11	11
Hoshiarpur	11	11	11	11	11
Mohali	11	11	11	11	11
Muktsar	11	11	11	11	11
Patiala	11	11	11	11	11

Data from the Meteorological Report of 1882-83.

Table No. V, showing the DISTRIBUTION of POPULATION.

1	2	3	4	5		7
				Total Population	Taluk Persons per sq. miles	
Total number of talukas, 1862-63	4,000,000	100,000	100,000	100,000	100,000	1,000,000
Cumulative square miles, 1862-63	2,000	27.5	27.5	27.5	27.5	450.0
Cumulative square miles, 1863-64	2,000	26.5	26.5	26.5	26.5	512.0
Approximate number of talukas in 1863-64	2,000	27.0	27.0	27.0	27.0	522.0
Total population	2,000,000	110,000	110,000	110,000	110,000	220,000
Taluk population	2,000,000	100,000	100,000	100,000	100,000	200,000
District population	2,000,000	100,000	100,000	100,000	100,000	200,000
Total population, per square mile	1,000	50	50	50	50	50
Total population per square mile	1,000	50	50	50	50	50
Population 10,000 and over	1,000	1	1	1	1	1
1,000 to 10,000	1,000	1	1	1	1	1
1,000 to 5,000	1,000	1	1	1	1	1
5,000 to 20,000	1,000	1	1	1	1	1
20,000 to 50,000	1,000	1	1	1	1	1
50,000 to 100,000	1,000	1	1	1	1	1
100,000 to 200,000	1,000	1	1	1	1	1
200,000 to 500,000	1,000	1	1	1	1	1
500,000 to 1,000,000	1,000	1	1	1	1	1
1,000,000 and over	1,000	1	1	1	1	1
Total	1,000	100	100	100	100	100
Occupied houses —	10,000	7,000	7,000	7,000	7,000	7,000
Villages —	10,000	10,000	10,000	10,000	10,000	10,000
Unoccupied houses —	1,000	3,000	3,000	3,000	3,000	3,000
Villages —	1,000	1,000	1,000	1,000	1,000	1,000
Residential families —	17,000	17,000	17,000	17,000	17,000	17,000
Villages —	17,000	22,000	22,000	22,000	22,000	22,000
Total & Totals						

Details of area taken from Measurement V. and VIII of the Agricultural Statement, and details of population taken from the District Office.

Ferozepore District.]

Table No. VI, showing MIGRATION.

Districts.	1 Inwards.	2 Outwards.	MIGRATION 1,000 OF BOTH SEXES.		DEMOGRAPHIC STATEMENT BY TOWNS.			
			3 Inwards.	4 Outwards.	5 Persons.	6 Males.	7 Females.	8 Males.
Bises	4,200	7,704	416	400	102	51	51	50
Ghazal	1,614	1,614	—	—	—	—	—	—
Lahkhan	14,000	20,000	264	260	1,327	663	663	662
Mohindar	10,000	6,000	600	590	1,200	600	600	599
Hoshiarpur	5,000	5,000	302	302	1,500	774	774	774
Ajmer	7,000	8,200	612	600	2,400	1,240	1,240	1,239
Gurdaspur	1,000	1,000	—	—	—	—	—	—
Sialkot	1,000	1,000	—	—	—	—	—	—
Lahore	15,000	10,000	220	212	1,000	500	500	498
Mianwali	6,000	2,000	420	412	1,000	500	500	499
Khyber P.	20,000	31,000	270	260	1,000	510	510	509
N.W. P. and Quetta	8,184	—	—	—	—	—	—	—
Hajiganj	2,000	—	900	—	1,000	450	450	449

NOTE.—These figures are taken from Table No. XX of the Census Report of 1881.

Table No. VII, showing RELIGION and SEX.

Districts.	1 Persons.	2 Males.	3 Females.	TOWNS.				Villages.
				4 Persons.	5 Males.	6 Females.	7 Males.	
Pitroni	610,010	307,310	—	100,100	50,500	50,600	221,200	311,610
Mohi	—	—	—	—	—	—	—	310,600
Punjab	10,000	5,000	5,000	20,000	10,000	10,000	22,000	22,000
Himachal	100,000	50,000	50,000	21,000	10,000	10,000	22,000	210,000
Shahze	100,000	50,000	50,000	12,000	6,000	6,000	12,000	120,000
Jamia	500	250	250	—	—	—	—	500
Banbhore	—	—	—	—	—	—	—	—
Zorawargarh	—	—	—	—	—	—	—	—
Muzaffarnagar	200,000	100,000	100,000	200,000	100,000	100,000	40,000	110,000
Chittorgarh	1,000	500	500	—	—	—	—	1,000
Orissa and Jhansi	—	—	—	—	—	—	—	—
Bengal and Bihar	—	—	—	—	—	—	—	—
—	1,000	500	500	—	—	—	—	1,000
Assam	900,000	450,000	450,000	1,000	500	500	40,000	25,000
Odisha	—	—	—	—	—	—	—	—
Wardha	1,000	500	500	—	—	—	—	1,000
Wazirabad	100	50	50	—	—	—	—	100

NOTE.—These figures are taken from Table Nos. III, IIIA, IIIB of the Census Report of 1881.

Table No. VIII, showing LANGUAGES.

Languages.	1 Persons.	2 Hindi.	3 Punjabi.	DEMOGRAPHIC STATEMENT.				Villages.
				4 Males.	5 Females.	6 Males.	7 Females.	
Hindi-Urdu	—	—	—	—	—	—	—	—
Punjabi	—	—	—	—	—	—	—	—
Pushtu	—	—	—	—	—	—	—	—
Pahari	—	—	—	—	—	—	—	—
Kashmiri	—	—	—	—	—	—	—	—
Dard	—	—	—	—	—	—	—	—
English	—	—	—	—	—	—	—	—

NOTE.—These figures are taken from Table No. I of the Census Report of 1881.

Table No. IX, showing MAJOR CASTES and TRIBES.

1 Serial No. in Census Table No. VIIIA	2 Caste or Tribe.	3 TOTAL NUMBER	4 Males.	5 Females.	6 Hindo.	7 Musl.	8 Juda.	9 Miscell.	10 Import- ation per mile of frontier-
					Persons.	Males.	Females.	Miscell.	
1	Total population	496,318	227,319	268,999	93,019	93,499	479	100,002	1,000
2	Punjabis	4,132	—	—	1,231	—	—	—	4
3	Jat	16,259	8,000	8,259	5,259	7,398	149	18,412	20
4	Takhtia	16,259	21,344	19,904	12,259	12,259	149	19,259	21
5	Dangi	12,137	7,200	5,937	—	—	—	8,937	22
6	Gurjar	12,018	6,018	6,000	—	—	—	6,000	23
7	Ardhi	11,048	22,200	23,240	—	—	—	—	28
8	Cawal	1,299	—	—	701	—	—	598	8
9	Makran	1,094	5,496	5,494	2,018	—	—	—	12
10	Bhatti	9,068	5,882	3,186	—	—	—	—	30
11	Sikhs	7,000	—	—	—	—	—	—	—
12	Khemis	22,079	7,001	15,078	6,004	134	—	—	32
13	Rajpal	2,012	1,000	1,012	—	—	—	—	6
14	Pular	2,002	1,212	1,200	—	—	—	—	6
15	Sal	2,004	1,212	1,200	1,007	933	—	—	12
16	Misra	2,004	1,200	1,200	—	—	—	—	11
17	Bappa	17,403	9,400	8,003	4,793	4,711	—	—	14
18	Chatti	1,174	1,000	1,000	4,000	—	—	—	13
19	Arora	10,298	5,000	5,298	4,002	3,298	—	—	12
20	Hawaiza	9,201	5,000	4,201	3,200	3,000	—	—	12
21	Chittas	9,197	27,100	27,119	23,549	8,447	—	—	100
22	Chander	20,021	7,000	2,000	2,000	1,000	—	—	24
23	Mohit	18,268	—	—	—	—	—	—	29
24	Jatka	20,019	11,000	9,019	—	—	—	—	44
25	Zhawar	9,543	5,472	4,071	2,200	1,602	—	—	20
26	Makhan	20,000	7,200	12,800	—	—	—	—	27
27	Lohar	7,007	—	—	—	—	—	—	11
28	Warkari	19,514	11,000	8,514	2,000	6,000	—	—	21
29	Kroobha	19,500	—	—	—	—	—	—	21
30	Khatri	20,000	—	—	—	—	—	—	20
31	Bali	20,000	—	—	—	—	—	—	20
32	Bauer	8,511	—	—	—	—	—	—	—

NOTE.—These figures are taken from Table No. VIIIA of the Census Report of 1901.

Table No. IXA, showing MINOR CASTES and TRIBES.

1 Serial No. in Census Table No. VIIIA	2 Caste or Tribe.	3 Persons.	4 Males.	5 Females.	6 Serial No. in Census Table No. VIIIA	7 Caste or Tribe.	8 Persons.	9 Males.	10 Females.			
Persons.	Males.	Females.	Persons.	Males.	Females.	Persons.	Males.	Females.	Persons.			
33	Biloch	—	1,308	940	468	34	Changar	—	1,313	620	693	
34	Kashtia	—	3,657	1,621	2,036	25	Bali	—	—	857	399	354
35	Abir	—	1,100	706	394	36	Udai	—	—	843	427	396
36	Moghul	—	1,107	612	495	37	Bilha	—	—	723	429	294
37	Qazai	—	714	419	394	38	Dangler	—	—	1,198	629	569
38	Mallah	—	1,000	672	327	39	Kashtia	—	—	608	308	294
39	Rohjia	—	2,100	1,209	1,221	40	Koti	—	—	692	348	279
40	Bairagi	—	1,108	647	461	41	Jhabal	—	—	1,076	628	377
41	Kalmi	—	1,309	1,047	262	42	Bodla	—	—	239	194	215
42	Mallhi	—	922	430	492	—	—	—	—	—	—	

NOTE.—These figures are taken from Table No. VIIIA of the Census Report of 1901.

Ferozepore District.]

71

- Table No. X, showing CIVIL CONDITION.

1 Annual number of males and females in each age group	2 BIRTHS. Deaths.	3		4		5		6		7	
		MALES.		FEMALES.		MARRIED.		WIDOWED.			
		Males.	Females.	Males.	Females.	Males.	Females.	Males.	Females.	Males.	Females.
All ages	10,000	4,132	1,112	166,972	144,100	10,000	3,672	36,717	32,334	36,717	32,334
0-15	2,140	600	1,000	27,402	20,300	4,000	1,000	4,000	3,000	4,000	3,000
15-25	2,000	500	900	27,402	20,300	3,000	900	3,000	2,000	3,000	2,000
25-35	1,800	400	700	22,000	18,000	2,000	500	2,000	1,500	2,000	1,500
35-45	1,600	300	500	18,000	15,000	1,500	400	1,500	1,000	1,500	1,000
45-55	1,400	200	400	15,000	12,000	1,000	300	1,000	700	1,000	700
55-65	1,200	100	300	12,000	10,000	800	200	800	500	800	500
65-75	1,000	50	200	9,000	7,000	600	100	600	400	600	400
75-85	800	20	150	6,000	4,000	400	80	400	200	400	200
Over 85	700	10	100	3,000	2,000	200	50	200	100	200	100

Note.—These figures are taken from Table No. VI of the Census Report.

Table No. XI, showing BIRTHS and DEATHS

1 TAXES.	2 TOTAL DEATHS REGISTERED.			3 TOTAL DEATHS SUBMITTED.			4 TOTAL DEATHS PENDING.			5 DEATHS BY CAUSES.		
	Males.			Females.			Unknown.			Unknown.		
	Males.	Females.	Persons.	Males.	Females.	Persons.	Unknown.	Females.	Persons.	Males.	Females.	Persons.
1905	10,000	12,200	22,200	7,000	8,350	15,350	—	—	—	4,000	4,000	8,000
1906	10,000	10,000	20,000	6,000	7,000	13,000	—	—	—	3,000	3,000	6,000
1907	15,000	14,000	29,000	12,000	13,000	25,000	—	—	—	12,000	12,000	24,000
1908	16,000	14,472	30,472	8,000	8,000	16,000	—	—	—	12,000	12,000	24,000
1909	20,000	16,000	36,000	12,000	12,000	24,000	—	—	—	16,000	16,000	32,000
1910	17,200	11,412	28,612	12,000	10,000	22,000	—	—	—	11,000	11,000	22,000
1911	18,000	17,200	35,200	12,000	12,000	24,000	200	200	200	12,000	12,000	24,000

Note.—These figures are taken from Tables Nos. I, II, VII, VIII, IX and X of the Sanitary Report.

Table No. XI A, showing MONTHLY DEATHS from all CAUSES

1 MONTHS.	2 TAXES.		3 TAXES.		4 TAXES.		5 TAXES.		6 TAXES.		7 TAXES.	
	TAXES.	TAXES.										
January	—	200	—	—	1,000	—	—	—	—	—	—	20,000
February	—	200	—	—	1,000	—	—	—	—	—	—	20,000
March	—	200	—	—	1,000	—	—	—	—	—	—	20,000
April	—	200	—	—	1,000	—	—	—	—	—	—	20,000
May	—	200	—	—	1,000	—	—	—	—	—	—	20,000
June	—	200	—	—	1,000	—	—	—	—	—	—	20,000
July	—	200	—	—	1,000	—	—	—	—	—	—	20,000
August	—	200	—	—	1,000	—	—	—	—	—	—	20,000
September	—	200	—	—	1,000	—	—	—	—	—	—	20,000
October	—	200	—	—	1,000	—	—	—	—	—	—	20,000
November	—	200	—	—	1,000	—	—	—	—	—	—	20,000
December	—	200	—	—	1,000	—	—	—	—	—	—	20,000
Total	—	14,200	—	—	7,000	—	—	—	—	—	—	142,000

Note.—These figures are taken from Statement No. 111 of the Sanitary Report, Patiala.

Table No. XIB, showing MONTHLY DEATHS from FEVER.

Month.	1	2	3	4	5	6	7	8	9
	1862.	1863.	1864.	1865.	1866.	1867.	1868.	1869.	Total.
January	—	912	467	607	1,224	560	1,000	1,292	8,602
February	—	645	345	612	1,028	367	622	621	3,234
March	—	625	369	782	1,202	503	1,072	721	5,127
April	—	—	—	327	1,000	499	1,018	1,000	5,000
May	—	—	—	367	1,000	247	1,000	1,000	5,000
June	—	—	—	328	1,000	499	1,000	1,000	5,000
July	—	—	—	228	1,000	499	1,000	1,000	5,000
August	—	—	—	247	1,000	499	1,000	1,000	5,000
September	—	—	—	247	1,000	499	1,000	1,000	5,000
October	—	—	—	247	1,000	499	1,000	1,000	5,000
November	—	—	—	247	1,000	499	1,000	1,000	5,000
December	—	—	—	247	1,000	499	1,000	1,000	5,000
TOTAL	4,902	6,066	11,082	12,549	13,702	14,034	15,242	15,791	117,791

Note.—These figures are taken from Table No. IX of the Monthly Report.

Table No. XII, showing INFIRMITIES.

1	2	3	4	5	6	7	8	9	
	Tribes.		Diseases.		Diseases.		Leprosy.		
	Males.	Females.	Males.	Females.	Males.	Females.	Males.	Females.	
All religions	Total	Villages	139	38	8,003	1,018	512	126	34
Hindus	Total	Villages	110	22	7,018	1,000	222	107	30
Buddhists	Total	Villages	21	11	908	104	42	19	10
Muslims	Total	Villages	21	4	667	67	12	8	6
Brahmins	Total	Villages	22	40	769	75	71	21	14

Note.—These figures are taken from Tables Nos. XIX to XXVII of the Census Report of 1881.

Table No. XIII, showing EDUCATION.

1	2	3	4	5	6	7	8	9		
	MALES.			FEMALES.			MALES.			
	Under 10 years	10 to 14 years	15 to 19 years	Under 10 years	10 to 14 years	15 to 19 years	Under 10 years	10 to 14 years		
All religions	Total	15,126	12,126	100	314	—	1,209	2,000	30	72
Hindus	Total	12,119	9,645	69	19	—	71	1,119	18	62
Buddhists	Total	4,007	3,447	75	27	—	1,001	1,772	12	29
Muslims	Total	224	2,047	0	10	—	101	2,000	45	41
Brahmins	Total	31	107	—	—	—	101	1,000	0	23
Brahminical	Total	—	—	—	—	—	127	2,322	0	34

Note.—These figures are taken from Table No. 2121 of the Census Report of 1881.

Table No. XIV, showing DETAILS of SURVEYED and ASSESSED AREA.

1	2	3	4	5	6	7	8	9	10	11	12
	CULTIVATED.				UNCULTIVATED.				Total area assessed square miles.		
	Irrigated		By per cent irrigated		Cultiva- ble land.	Total cul- tivated	Cultiva- ble land.	Total cul- tivable area	Total area assessed	Cross section square miles.	Total area assessed square miles.
1860-61	112,000	1,200,000	1,400,000	1,600,000	224,200	141,000	308,200	1,507,200	800,000	—	—
1861-62	112,000	1,200,000	1,400,000	1,600,000	110,200	101,000	200,200	1,301,200	600,000	40	40
1862-63	117,700	1,214,200	1,407,200	1,607,200	101,000	92,000	212,000	1,303,000	600,000	40	40
1863-64	118,000	1,214,200	1,407,200	1,607,200	94,700	111,000	183,700	1,287,700	600,000	40	40
1864-65	121,000	1,214,200	1,407,200	1,607,200	86,300	128,000	194,300	1,288,300	600,000	40	40
Total area for 1860-65	610,700	7,000,000	10,000,000	12,000,000	1,000,000	1,000,000	1,000,000	12,000,000	4,000,000	124	124
Punjab	70,000	1,200,000	1,400,000	1,600,000	10,000	10,000	10,000	10,000	10,000	—	—
Mohali	61,000	6,000	8,000	10,000	—	—	—	—	—	—	—
Malerkotla	61,000	6,000	8,000	10,000	—	—	—	—	—	—	—
Fazilka	61,000	6,000	8,000	10,000	—	—	—	—	—	—	—

Note.—Taken from Agricultural Statistics Nos. V and VI of the Administrative Report.

Taken from  
Table No.  
VIII of the  
Administrative  
Report.

Ferozepore District.)

Table No. XV, showing VARIETIES of TENURE held direct from Government as they stood in 1887-88.

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22		
	TENURE HELD.												TENURE HELD.											
	VANAS PRASARALA.												VANAS PRASARALA.											
Villages held by zamindars directly—																								
1. By zamindars—	22	20	16	17,915	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
2. By zamindars—	10	8	40	6,010	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Villages held by zamindars through	149	140	140	14,430	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Illes	79	26	2,410	4,210	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Estates held by zamindars without right of	1	1	1	1,200	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Total	310	94,620	20,070	37,915	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Aboriginals																								
1. Tribes holding the above held wholly or partially by zamindars—	22	9,720	—	—	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
2. Tribes holding part of zamindari—	9	6,310	—	—	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
3. Tribes subject to zamindars—	20	6,010	—	—	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
4. Tribes in the name of zamindars—	11	110	—	—	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
Total of these holdings	100	34,230	—	—	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	100	
B—Villages held in the above of which the ownership is communally maintained.	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	
A—Villages held in the above held wholly or partially by zamindars—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	

B—Villages held in the above of which the ownership is communally maintained.

Table No. XV, showing VARIETIES of TENURE held direct from Government as they stood in 1887-88—concluded.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	Tenth Percent.		Per Cent. Decrease.			
Villages held direct from Government																												
1. By inheritance	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	
2. By severaltenure	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
Villages held on permanent lease																												
By leasehold tenure	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
From Government or State or Panchayat	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
<b>ADDITIONS.</b>																												
Additions included in the above, but wholly or partially free of rent, etc.—																												
1. In property free of revenue, etc.—	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
2. In property subject to certain taxes, etc.—	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
3. For life or lives, etc.—	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
4. By right of succession.	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"	"		
Total of these additions	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		
5. Total additions in the above, etc., which the ownership is uncertain, by right of succession, or otherwise.	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—		

Note.—These figures are taken from statement No. 12 of the Budget Report.

Ferapore District.]

Table No. XVI. Return showing the cultivating occupancy of land for the year ending Rabi 1888.

1.	2.		3.		4.		5.		6.		7.		8.		9.		10.			
	Principals.	Mans.	Mans.	21as.																
DEVALI.																				
Total area under cultivation by cultivators, & others, & their agents, & others, not included in the above.	22,044 10,122 10,922	22,044 11,000 14,000	22,044 10,000 13,000	22,044 10,000 13,000	22,044 11,000 14,000															
With rights of occupancy, but not possessors.																				
With rights of occupancy, but not possessors, but not held by agents.	20,031 2,000 1,000																			
With rights of occupancy, but not possessors, but not held by agents, but not held by agents.	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212	1,212			
With rights of occupancy, but not possessors, but not held by agents, but not held by agents, but not held by agents.	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000	2,000			
With rights of occupancy, but not possessors, but not held by agents, but not held by agents, but not held by agents.	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000			
Area.																				
DEVALI.																				
Total area under cultivation.	22,044 2,000 1,000																			
Zamindars, Talukah, Chowka, Bazar, Talukah, Chowka, Bazar, Talukah, Chowka, Bazar.	2,000 1,000 1,000 1,000 1,000 1,000 1,000 1,000 1,000																			
Total area under cultivation.	22,044 2,000 1,000																			

Note.—This return gives the area under cultivation in the districts of Ferapore, Dharwar, and Khandesh.

Table No. XVII, showing GOVERNMENT LANDS.

1	2	3	4	5		6		7		8		9	
				Area held under cultivating leases.		Holding area.		Holding area.		Holding area.			
				Chittagong	Mymensingh	Chittagong	Mymensingh	Dhaka	Khulna	Dhaka	Khulna		
White District													
Vizier Parganah	11,111	11,111	10	5,297	1,213	1,088	229	512	250	111	111	1,294	
Zira				—	499	217	—	—	—	—	—	499	
Mona				—	—	—	—	—	—	—	—	—	
Mohammer				—	—	—	—	—	—	—	—	—	
Fazilka				—	—	—	—	—	—	—	—	—	
				11,111	1,213	1,088	229	512	250	111	111	1,294	
				11,111	1,213	1,088	229	512	250	111	111	1,294	
				11,111	1,213	1,088	229	512	250	111	111	1,294	

Note.—These figures are taken from the District Collector's Report.

Table No. XIX, showing LAND ACQUIRED by GOVERNMENT.

Purpose for which acquired.			Acres acquired.	Compensation paid in Rupees.	Inclusion of revenue in Budget.
Roads	—	—	—	—	—
Canals	—	—	—	2,284	1,09,387
State Railways	—	—	—	1,209	42,996
National Railways	—	—	—	—	—
Miscellaneous	—	—	—	499	20,079
					1,294

Note.—These figures are taken from Statements No. XII of itself and No. XXIV of 1907-08 of the Revenue Reports.

Table No. XX, showing ACRES UNDER CROPS.

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
TALUK.	TALUK.	Hill.	Wood.	Amb.	Bar.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.	Bajra.
1907-08	1,000,000	5,156	905,000	219,737	65,000	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000
1908-09	2,001,000	2,307	905,000	219,737	40,700	238,000	71,400	306,000	270	1,740	12,000	1,740	12,000	1,740	12,000

TAKES AVERAGE OF THE FIVE YEARS FROM 1904-05 TO 1908-09.

Panjorpur	1,129	21,000	25,847	5,200	19,284	3,072	42,180	8,041	7	327	12,200	7	327	12,200	7
Moja	439,472	47,427	272,129	9,088	53,272	5,307	98,522	30,118	3	30	11,717	3	30	11,717	3
Zira	284,029	8,101	22,348	901	10,729	2,100	30,756	6,612	3	3,000	11,267	3	3,000	11,267	3
Mona	300,740	2,101	60,780	21,700	25,923	5,922	56,120	12,300	2	2,000	11,098	2	2,000	11,098	2
Mohammer	225,452	8,101	22,347	80,100	54,726	5,007	51,286	5,007	2	1,200	11,098	2	1,200	11,098	2
Total	1,671,260	4,332	846,700	210,450	231,560	63,329	947,600	30,184	32	3,000	11,130	32	3,000	11,130	32

\* Miscellaneous No. XLIII and XLV of the Administration Report.

† From Agricultural Statistics No. VIII.

Table No. XXI, showing RENT RATES and AVERAGE YIELD.

	Nature of Crop.	1			2			3		4	
		Maximum	Minimum	Avg.	Maximum	Minimum	Avg.	Average produce per acre estimated in 1895-96 in Rs.	In Rs.	Average produce per acre estimated in 1895-96 in Rs.	In Rs.
Rice	—	—	—	—	—	—	—	—	—	—	—
Julip	—	—	—	—	—	—	—	—	—	—	—
Cotton	—	—	—	—	—	—	—	—	—	—	—
Sugarcane	—	—	—	—	—	—	—	—	—	—	—
Opium	—	—	—	—	—	—	—	—	—	—	—
Tobacco	—	—	—	—	—	—	—	—	—	—	—
Wheat	Irrigated	—	—	—	—	—	—	—	—	—	—
	Unirrigated	—	—	—	—	—	—	—	—	—	—
Other grains	Irrigated	—	—	—	—	—	—	—	—	—	—
	Unirrigated	—	—	—	—	—	—	—	—	—	—
Oilsseeds	Irrigated	—	—	—	—	—	—	—	—	—	—
	Unirrigated	—	—	—	—	—	—	—	—	—	—
Fibres	Irrigated	—	—	—	—	—	—	—	—	—	—
	Unirrigated	—	—	—	—	—	—	—	—	—	—
Gram	—	—	—	—	—	—	—	—	—	—	—
Barley	—	—	—	—	—	—	—	—	—	—	—
Bajra	—	—	—	—	—	—	—	—	—	—	—
Jowar	—	—	—	—	—	—	—	—	—	—	—
Vegetables	—	—	—	—	—	—	—	—	—	—	—
Tea	—	—	—	—	—	—	—	—	—	—	—

Note.—These figures are taken from Statement No. XIV of the Administration Report. Lesser information not available.

Table No. XXII, showing NUMBER of STOCK.

1	2	3	4	5	6	7		8							
						WEEKLY REPORT FOR THE YEAR					TAXES FOR THE YEAR 1895-96.				
						1895-96.	1895-96.	1895-96.	1895-96.	1895-96.	Per-	Hogs.	21rs.	Mil-	Rs.
Cows and bullocks	140,000	167,000	204,204	241,274	260,784	702,340	*125,034	*102,000	*100,000	*72,001	Per-	—	—	—	—
Horses	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Ponies	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Donkeys	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Sheep and goats	70,000	82,000	72,000	91,000	104,000	354,070	40,000	30,000	30,000	44,000	Per-	—	—	—	—
Pigs	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Geese	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Carries	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Floughts	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—
Bosta	—	—	—	—	—	—	—	—	—	—	Per-	—	—	—	—

Note.—These figures are taken from Statement No. XIV of the Finance Report.  
\* Including buffaloes.

Table No. XXIII, showing OCCUPATIONS of MALES.

Name of occupation.	Males above 15 years of age.			Males below 15 years of age.			Name of occupation.	Males above 15 years of age.			
	Town	Vill.	Total	Town	Vill.	Total		Town	Vill.	Total	
1. Total population	36,091	101,204	137,295	17	Agricultural labourers	—	—	—	—	—	—
2. Unemployed agricultural labourers	24,205	72,209	96,414	18	Porters	—	—	172	3,249	1,123	4,311
3. Agricultural labourers employed	6,877	29,995	36,772	19	Cooks and other servants	—	—	1,452	3,018	2,304	5,774
4. Agricultural labourers not employed	—	—	—	20	Team drivers	—	—	221	—	—	221
5. Civil Administration	2,045	1,002	3,047	21	Labourers and porters	—	—	980	11,019	10,514	19,513
6. Army	1,008	362	1,370	22	Workers in coal, iron, brass, copper, etc.	—	—	218	925	—	218
7. Religion	—	—	—	23	Workers in leather	—	—	146	—	—	146
8. Commerce	217	2,242	2,459	24	Housekeepers	—	—	907	3,088	2,000	4,095
9. Other professions	810	1,211	1,291	25	Workers in wood and peacock feathers	—	—	47	19	—	47
10. Manufacturing, general	871	902	1,773	26	— silk	—	—	—	—	—	—
11. Manufacturing, cotton	—	—	—	27	— cotton	—	—	1,261	9,007	1,000	11,268
12. Manufacturing, jute	4,008	1,167	5,175	28	— wood	—	—	216	2,614	2,217	4,037
13. Manufacturing, jute, cotton, &c.	1,208	467	1,675	29	Workers in glass and silver	—	—	220	908	1,128	2,256
14. Manufacturing, cotton, &c.	1,022	971	1,993	30	Workers in iron	—	—	107	1,147	1,000	2,114
15. Manufacturing, cotton, &c.	—	—	—	31	General labourers	—	—	1,027	3,021	2,000	4,048
16. Manufacturing, cotton, &c.	728	775	1,493	32	Peasants, cultivators, and their wives	—	—	1,026	7,604	7,000	8,726
17. Manufacturing, cotton, &c.	2,029	27,303	30,332	33							
18. Manufacturing, cotton, &c.	2,000	20,007	21,997	34							
19. Manufacturing, cotton, &c.	2,000	2,000	2,000	35							

Note.—These figures are taken from Table No. XXII A of the Census Report of 1901.

Table No. XXIV. showing MANUFACTURES.

1	2			3			4			5		
	Town	Villages	Wards	Urban municipal towns	Town	Villages	Urban municipal towns	Town	Villages	Urban municipal towns	Town	Villages
Number of mills and large factories	—	—	—	—	—	—	—	—	—	—	—	—
Number of private houses or small works	—	4,246	—	—	—	11	622	394	—	—	112	—
Number of workmen	—	—	—	—	—	—	—	—	—	—	—	—
1. Male	—	—	—	—	—	—	—	—	—	—	—	—
2. Female	—	—	—	—	—	—	—	—	—	—	—	—
Number of workmen in small works or independent artisans	—	1,000	—	—	—	23	704	1,158	—	—	300	—
Value of work in small works	—	—	—	—	—	—	—	—	—	—	—	—
Estimated annual income of all workmen in small works	—	8,00,271	—	—	—	2,429	1,01,918	2,77,300	—	—	75,183	1,00,212
Number of mills and large factories	—	—	—	—	—	—	—	—	—	—	—	—
Number of private houses or small works	—	1,072	600	544	—	—	—	—	—	—	407	6,768
Number of workmen	—	—	—	—	—	—	—	—	—	—	—	—
1. Male	—	—	—	—	—	—	—	—	—	—	—	—
2. Female	—	—	—	—	—	—	—	—	—	—	—	—
Number of workmen in small works or independent artisans	—	1,102	1,310	1,068	—	—	—	—	—	—	434	15,810
Value of work in large works	—	—	—	—	—	—	—	—	—	—	—	—
Estimated annual income of all workmen in large works	—	8,00,100	1,10,444	7,79,000	—	—	—	—	—	—	47,901	47,73,238

Note.—These figures are taken from the Report on Industrial Trade and Manufactures for 1901-02.

Table No. XXV. showing RIVER TRAFFIC.

1	2			3			4	5			6	
	From	To	Passenger	Mercantile	Passenger	Mercantile		Passenger	Mercantile	Passenger	Mercantile	
Sukkur	—	—	Passes	—	—	—	Lahore	20,000	—	8	100	249
Dalwalipur	—	—	Passes	—	—	—	Irrawadi	10,000	—	—	—	193
Fazilka	—	—	Passes	—	—	—	Constance	2,000	40	—	40	200
Fazilka	—	—	Passes	—	—	—	Datta	2,000	—	—	—	200
				Passes	—	—	Goree	20,000	—	—	—	200
				Passes	—	—	Madras	20,000	—	—	—	200
				Passes	—	—	Calcutta	20,000	—	—	—	200
				Passes	—	—	Takamira	20,000	—	—	—	200

## Ferozepore District.]

xxv

Table No. XXVI, showing RETAIL PRICES.

Year	Retails of Rice &c. Current as Buyed.												Rate per Hd. (Rs.)	
	White			Green			Yellow			Red				
	Ch.	Rs.	Ch.	Rs.	Ch.	Rs.	Ch.	Rs.	Ch.	Rs.	Ch.	Rs.		
1866-67	—	—	—	—	—	—	—	—	—	—	—	—	—	
1867-68	—	—	—	—	—	—	—	—	—	—	—	—	—	
1868-69	—	—	—	—	—	—	—	—	—	—	—	—	—	
1869-70	—	—	—	—	—	—	—	—	—	—	—	—	—	
1870-71	—	—	—	—	—	—	—	—	—	—	—	—	—	
1871-72	—	—	—	—	—	—	—	—	—	—	—	—	—	
1872-73	—	—	—	—	—	—	—	—	—	—	—	—	—	
1873-74	—	—	—	—	—	—	—	—	—	—	—	—	—	
1874-75	—	—	—	—	—	—	—	—	—	—	—	—	—	
1875-76	—	—	—	—	—	—	—	—	—	—	—	—	—	
1876-77	—	—	—	—	—	—	—	—	—	—	—	—	—	
1877-78	—	—	—	—	—	—	—	—	—	—	—	—	—	
1878-79	—	—	—	—	—	—	—	—	—	—	—	—	—	
1879-80	—	—	—	—	—	—	—	—	—	—	—	—	—	
1880-81	—	—	—	—	—	—	—	—	—	—	—	—	—	
1881-82	—	—	—	—	—	—	—	—	—	—	—	—	—	
1882-83	—	—	—	—	—	—	—	—	—	—	—	—	—	
1883-84	—	—	—	—	—	—	—	—	—	—	—	—	—	
1884-85	—	—	—	—	—	—	—	—	—	—	—	—	—	
1885-86	—	—	—	—	—	—	—	—	—	—	—	—	—	
1886-87	—	—	—	—	—	—	—	—	—	—	—	—	—	
1887-88	—	—	—	—	—	—	—	—	—	—	—	—	—	
1888-89	—	—	—	—	—	—	—	—	—	—	—	—	—	
1889-90	—	—	—	—	—	—	—	—	—	—	—	—	—	
1890-91	—	—	—	—	—	—	—	—	—	—	—	—	—	
1891-92	—	—	—	—	—	—	—	—	—	—	—	—	—	
1892-93	—	—	—	—	—	—	—	—	—	—	—	—	—	
1893-94	—	—	—	—	—	—	—	—	—	—	—	—	—	
1894-95	—	—	—	—	—	—	—	—	—	—	—	—	—	
1895-96	—	—	—	—	—	—	—	—	—	—	—	—	—	
1896-97	—	—	—	—	—	—	—	—	—	—	—	—	—	
1897-98	—	—	—	—	—	—	—	—	—	—	—	—	—	
1898-99	—	—	—	—	—	—	—	—	—	—	—	—	—	
1899-1900	—	—	—	—	—	—	—	—	—	—	—	—	—	
1900-01	—	—	—	—	—	—	—	—	—	—	—	—	—	
1901-02	—	—	—	—	—	—	—	—	—	—	—	—	—	
1902-03	—	—	—	—	—	—	—	—	—	—	—	—	—	
1903-04	—	—	—	—	—	—	—	—	—	—	—	—	—	
1904-05	—	—	—	—	—	—	—	—	—	—	—	—	—	
1905-06	—	—	—	—	—	—	—	—	—	—	—	—	—	
1906-07	—	—	—	—	—	—	—	—	—	—	—	—	—	
1907-08	—	—	—	—	—	—	—	—	—	—	—	—	—	
1908-09	—	—	—	—	—	—	—	—	—	—	—	—	—	
1909-10	—	—	—	—	—	—	—	—	—	—	—	—	—	
1910-11	—	—	—	—	—	—	—	—	—	—	—	—	—	
1911-12	—	—	—	—	—	—	—	—	—	—	—	—	—	
1912-13	—	—	—	—	—	—	—	—	—	—	—	—	—	
1913-14	—	—	—	—	—	—	—	—	—	—	—	—	—	
1914-15	—	—	—	—	—	—	—	—	—	—	—	—	—	
1915-16	—	—	—	—	—	—	—	—	—	—	—	—	—	
1916-17	—	—	—	—	—	—	—	—	—	—	—	—	—	
1917-18	—	—	—	—	—	—	—	—	—	—	—	—	—	
1918-19	—	—	—	—	—	—	—	—	—	—	—	—	—	
1919-20	—	—	—	—	—	—	—	—	—	—	—	—	—	
1920-21	—	—	—	—	—	—	—	—	—	—	—	—	—	

Note.—These figures are taken from Statement No. XXXVII of the Administrative Report in 1880 and from 1881 to 1910-11 from the Annual Reports of each year.

Note.—These figures represent the price as it stood on the 1st of January of each year.

Table No. XXVII, showing PRICE of LABOUR.

1	2	3	4	5	6	7	8	9	10	11	12	13	14
YEAR.	WAGES OF LABOUR PER DAY.				CRAFTS PER DAY.		MISCELLANEOUS.		DRAUGHTS FOR DOGS PER DAY.		HOSES PER DAY.		
	BILLED.		CASHED.										
	Highest	Lowest	Highest	Lowest	Highest	Lowest	Highest	Lowest	Highest	Lowest	Highest	Lowest	
1888-89	Rs. 8. p.	Rs. 5. 10	Rs. 6. 10	Rs. 6. p.	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	Rs. 6. 10	
1889-90	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1890-91	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1891-92	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1892-93	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1893-94	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1894-95	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1895-96	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1896-97	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	
1897-98	0. 8	0. 6	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	0. 7	0. 5	

NOTE.—These figures are taken from Table No. XLVII of the Administration Report.

Table No. XXVIII, showing REVENUE COLLECTED.

1	2	3	4	5	6	7	8	9	10
YEAR.	Total Land Revenue.	PROCESSIONAL AND MISCELLANEOUS LAND REVENUE.		Tributes.	Total value.	EXCISE.		Stampa.	Total Collection.
		Rs.	Rs.			Spices.	Drugs.		
1888-89	—	2,14,369	2,000	—	24,379	20,000	10,250	—	1,11,244
1889-90	—	2,15,263	2,000	—	25,275	20,000	10,250	—	1,11,200
1890-91	—	2,16,267	2,000	—	26,774	20,000	10,250	—	1,11,200
1891-92	—	2,17,267	2,000	—	26,275	20,000	10,250	—	1,11,200
1892-93	—	2,18,267	2,000	—	27,275	20,000	10,250	—	1,11,200
1893-94	—	2,19,267	2,000	—	27,275	20,000	10,250	—	1,11,200
1894-95	—	2,20,267	2,000	—	27,275	20,000	10,250	—	1,11,200
1895-96	—	2,21,267	2,000	—	27,275	20,000	10,250	—	1,11,200
1896-97	—	2,22,267	2,000	—	27,275	20,000	10,250	—	1,11,200
1897-98	—	2,23,267	2,000	—	27,275	20,000	10,250	—	1,11,200

NOTE.—These figures are taken from Particular No. XLIV of the Revenue Report, Punjab, up to 1888-89 and for 1897-98 from Statements Nos. XX and XXXII of the Revenue Report.

Table No. XXIX, showing REVENUE DERIVED from LAND

1	2	3	4	5	6	7	8	9	10	11	12	13	14
YEAR.	Total Land Revenue.	PROCESSIONAL REVENUE.						MISCELLANEOUS REVENUE.					
		Rs.	Rs.	Rs.	Rs.	Rs.	Rs.	Grazing fees.	Wood-timber etc.	Wood-timber etc.	Wood-timber etc.	Wood-timber etc.	Total misce- naneous revenue.
Total of 1 year— 1888-89 to 1894-95	Rs. 2,14,369	Rs. 2,000	Rs. 2,000	Rs. 2,000	Rs. 2,000	Rs. 2,000	Rs. 2,000	Rs. 20,000	Rs. 10,250	Rs. 10,250	Rs. 10,250	Rs. 10,250	Rs. 1,11,244
1895-96	2,15,263	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1896-97	2,16,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1897-98	2,17,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1898-99	2,18,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1899-1900	2,19,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1900-01	2,20,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1901-02	2,21,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1902-03	2,22,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1903-04	2,23,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1904-05	2,24,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1905-06	2,25,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1906-07	2,26,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1907-08	2,27,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1908-09	2,28,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1909-10	2,29,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1910-11	2,30,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1911-12	2,31,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1912-13	2,32,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1913-14	2,33,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1914-15	2,34,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1915-16	2,35,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1916-17	2,36,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1917-18	2,37,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1918-19	2,38,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1919-20	2,39,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
1920-21	2,40,267	2,000	2,000	2,000	2,000	2,000	2,000	20,000	10,250	10,250	10,250	10,250	1,11,200
Total totals for 5 years 1888-89 to 1892-93	10,70,729	—	—	—	—	—	—	—	—	—	—	—	—
Yarmouth	5,70,729	—	—	—	—	—	—	—	—	—	—	—	—
Mars	10,70,729	—	—	—	—	—	—	—	—	—	—	—	—
Zira	—	—	—	—	—	—	—	—	—	—	—	—	—
Wishkar	4,70,729	—	—	—	—	—	—	—	—	—	—	—	—
Bhaluka	3,70,729	—	—	—	—	—	—	—	—	—	—	—	—

Table No. XXX showing ASSIGNED LAND REVENUE for 1887-88.

TAX.	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	25		
PERIOD OF ASSESSMENT—GENERAL.														NUMBER OF ASSESSED.													
For ever 1/2.		For more than half 1/2.		During which month of assessment.		Period of assessment.		1/2. Heredit.		For entire 1/2.		For more than half 1/2.		During which month of assessment.		1/2. Heredit.		For entire 1/2.		For more than half 1/2.		During which month of assessment.		1/2. Heredit.		For entire 1/2.	
Area.		Revenue.		Area.		Revenue.		Area.		Revenue.		Area.		Revenue.		Area.		Revenue.		Area.		Revenue.		Area.		Revenue.	
Ferozepore	1,073	Rs. 1,073	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	Area.	Rs.	
Moga	1,176	Rs. 1,176	7,000	Rs. 7,000	1,176	Rs. 1,176	2,000	Rs. 2,000	12,000	Rs. 12,000	20,000	Rs. 20,000	22,000	Rs. 22,000	22,000	Rs. 22,000	22,000	Rs. 22,000	22,000	Rs. 22,000	22,000	Rs. 22,000	22,000	Rs. 22,000	22,000	Rs. 22,000	
Sira	4,352	Rs. 4,352	5,000	Rs. 5,000	4,352	Rs. 4,352	5,000	Rs. 5,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	10,000	Rs. 10,000	
Makranur	20,957	Rs. 20,957	5,000	Rs. 5,000	20,957	Rs. 20,957	5,000	Rs. 5,000	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	20,957	Rs. 20,957	
Vadka	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	62	Rs. 62	
Total Districts	40,310	Rs. 40,310	65,126	Rs. 65,126	40,310	Rs. 40,310	65,126	Rs. 65,126	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	95,242	Rs. 95,242	

NOTE.—These figures are taken from Statement No. XXV of the Revenue Report for 1887-88.

Table No. XXXI, showing BALANCES, REMISSION and TAKAVI.

TAX.	Balances of Land Revenue in Rupees.			Reductions of land demand in amount of land revenue due in arrears.	Takavi advances in Rupees.		Remises.
	Paid in Advance.	Excessions and Discrepancies.	Interest.		Personnel.	Interest.	
1887-88	—	940	—	—	8,000	2,400	
1888-89	—	944	—	—	200	22	
1889-90	—	720	—	—	2,000	1,000	
1890-91	—	12,144	—	—	8,219	7,200	
1890-91	—	21,298	302	—	28,988	9,004	
1891-92	—	—	—	—	—	—	
							Taken from Tables No. I, II, III and XVI of the Revenue Report.

Table No. XXXII, showing SALES and MORTGAGES of LAND.

District	Sales or Leases.							Mortgages or Lases.							Purchase or Sales of Land.						
	Old Assessments.			New Assessments.				Old Assessments.			New Assessments.				Old Assessments.			New Assessments.			
	Number of cases	Area of land in acres.	Number of cases	Area of land in acres.	Number of cases	Area of land in acres.	Number of cases	Area of land in acres.													
District totals for 4 years from 1862 to 1865—	3,602	60,307	10,173	904	27,612	4,752	66	3,610	22,731	3,610	16,442	3,610	16,442	100	1,000	1,000	3,727	3,727	3,727	3,727	
District totals for 1866-70—	4,110	4,052	70,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	400	4,042	4,042	4,042	
Taluk	100	—	200	11,250	10,000	25	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Taluk	100	—	100	1,000	1,000	100	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Taluk	100	—	100	1,000	1,000	100	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Taluk	100	—	100	1,000	1,000	100	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Taluk	100	—	100	1,000	1,000	100	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Total	207	4,044	1,633	33	1,327	67,919	1,000	11,200	7,610,432	400	6,754	3,610,432	400	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Mohals	—	—	200	2,400	2,400	600	600	24,000	12,641	10,200	16,572,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Mohals	—	—	100	1,000	1,000	600	600	2,000	6,000	6,000	10,620,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Mohals	—	—	100	1,000	1,000	600	600	2,000	6,000	6,000	10,620,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Mohals	—	—	100	1,000	1,000	600	600	2,000	6,000	6,000	10,620,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Mohals	—	—	100	1,000	1,000	600	600	2,000	6,000	6,000	10,620,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	
Talukas	—	—	100	1,000	1,000	600	600	2,000	6,000	6,000	10,620,218	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000	

Note.—These figures are taken from Statistical Abstracts of the Mysore Reports.

Table No. XXXII, showing SALE of STAMPS and REGISTRATION of DEEDS.

YEAR	SALES OF STAMPS				REGISTRATION OF DEEDS				VALUATION OF PROPERTY			
	Amount in Rupees		No. issued & Average Price per Stamp		Number of Deeds registered		Value of Property (Local & Foreign)		Amount in Rupees		Rate per Square Yards	
	Year	Total	Year	Avg.	Year	Total	Year	Total	Year	Total	Year	Total
1892-93	95,000	35,400	1892-93	20,700	1892-93	1,160	1892-93	3,084	1892-93	1,07,320	1892-93	1,06,254
1893-94	90,000	31,700	1893-94	21,000	1893-94	1,120	1893-94	3,000	1893-94	102,440	1893-94	1,07,477
1894-95	95,572	30,000	1894-95	21,500	1894-95	1,140	1894-95	3,010	1894-95	100,000	1894-95	1,06,184
1895-96	179,200	31,500	1895-96	22,100	1895-96	1,160	1895-96	3,250	1895-96	122,000	1895-96	1,14,425
1896-97	130,000	32,000	1896-97	22,500	1896-97	1,180	1896-97	3,300	1896-97	120,000	1896-97	1,14,420
1897-98	125,000	32,500	1897-98	22,000	1897-98	1,160	1897-98	3,200	1897-98	120,000	1897-98	1,14,420
1898-99	120,000	32,000	1898-99	21,500	1898-99	1,140	1898-99	3,100	1898-99	119,000	1898-99	1,14,370

Note.—Taken from Appendix A of the Statistical Abstract of the Indian Empire, and Registration No. 11 and 12 of Registration Report.

Table No. XXXIII, showing REGISTRATION.

YEAR	REGISTRATION OF DEEDS						VALUATION OF PROPERTY					
	Number of Deeds registered			Value of Property			Number of Deeds registered			Value of Property		
	1892-93	1893-94	1894-95	1892-93	1893-94	1894-95	1892-93	1893-94	1894-95	1892-93	1893-94	1894-95
	Completed	Optimal	Total	Completed	Optimal	Total	Completed	Optimal	Total	Completed	Optimal	Total
Registration, Ferozepore	—	—	—	—	—	—	—	—	—	—	—	—
Sub-Registration, Ferozepore	—	—	—	—	—	—	—	—	—	—	—	—
District, Ferozepore Taluk	—	—	—	—	—	—	—	—	—	—	—	—
Town, Jalandhar	—	—	—	—	—	—	—	—	—	—	—	—
Town, Amritsar	—	—	—	—	—	—	—	—	—	—	—	—
Town, Lahore	—	—	—	—	—	—	—	—	—	—	—	—
Town, Multan	—	—	—	—	—	—	—	—	—	—	—	—
Town, Jullundur	—	—	—	—	—	—	—	—	—	—	—	—
Town, Rawalpindi	—	—	—	—	—	—	—	—	—	—	—	—
Town, Sialkot	—	—	—	—	—	—	—	—	—	—	—	—
Town, Nowshera	—	—	—	—	—	—	—	—	—	—	—	—
Town, Peshawar	—	—	—	—	—	—	—	—	—	—	—	—
Town, Patti	—	—	—	—	—	—	—	—	—	—	—	—
Total of Ferozepore District	—	—	—	—	—	—	—	—	—	—	—	—

Note.—This Series are taken from Statement No. 1 of Registration Report.

Table No. XXXIV, showing LICENSE TAX COLLECTIONS.

YEAR	NUMBER OF LICENSES GRANTED IN EACH CLASS AND THEIR VALUE												NUMBER OF LICENSES GRANTED AND THEIR VALUE		
	CLASS I.				CLASS II.				CLASS III.				Total No. of lic.	Total Value	Total No. of lic.
	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	No. of lic.	Total No. of lic.	Total Value	Total No. of lic.
	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Ru. lak.	Total No. of lic.	Total Value	Total No. of lic.
1892-93	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1893-94	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1894-95	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1895-96	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1896-97	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1897-98	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
1898-99	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—

Note.—These figures are taken from Statement No. 2 of the License Tax Report.

Table No. XXXIVA, showing INCOME TAX COLLECTIONS.

TAXES.	1888-89.		1889-90.	
	Number of persons taxed.	Amount realized.	Number of persons taxed.	Amount realized.
Excise	402	Rs. 12,000	407	Rs. 12,000
Mohur	314	Rs. 1,000	320	Rs. 1,000
Duty	317	Rs. 1,000	314	Rs. 1,000
Malabar	112	Rs. 100	174	Rs. 100
Fines	100	Rs. 100	101	Rs. 100
Total Income	1,034	Rs. 12,100	1,010	Rs. 12,100

Taken from Statement No. III of the Income Tax Report.

Table No. XXXV, showing EXCISE STATISTICS.

YEAR.	Total Excise Revenue in Rs. Lakhs.	PERCENTAGE LEGISLATION.			EXCISE LEGISLATION UNITS.						EXCISE REVENUE FROM		
		Number of Excise Units.		Constituted in millions.	Number of the Excise Units.			Constituted in millions.			Excise Revenue from		
		Excise Units in millions.											
1885-86	—	—	—	—	—	—	—	—	—	—	—	—	—
1886-87	—	—	—	—	—	—	—	—	—	—	—	—	—
1887-88	—	—	—	—	—	—	—	—	—	—	—	—	—
1888-89	—	—	—	—	—	—	—	—	—	—	—	—	—
1889-90	—	—	—	—	—	—	—	—	—	—	—	—	—
1890-91	—	—	—	—	—	—	—	—	—	—	—	—	—
1891-92	—	—	—	—	—	—	—	—	—	—	—	—	—
1892-93	—	—	—	—	—	—	—	—	—	—	—	—	—
1893-94	—	—	—	—	—	—	—	—	—	—	—	—	—
1894-95	—	—	—	—	—	—	—	—	—	—	—	—	—
1895-96	—	—	—	—	—	—	—	—	—	—	—	—	—
1896-97	—	—	—	—	—	—	—	—	—	—	—	—	—
1897-98	—	—	—	—	—	—	—	—	—	—	—	—	—
1898-99	—	—	—	—	—	—	—	—	—	—	—	—	—
1899-1900	—	—	—	—	—	—	—	—	—	—	—	—	—
Total Average	Rs. 11	Rs. 112	Rs. 11	Rs. 2,000	Rs. 1,000	Rs. 112	Rs. 112	Rs. 100	Rs. 100	Rs. 112	Rs. 112	Rs. 112	Rs. 112

Note.—Taken from Statements A, C, D, and Statement No. II of Appendix B of the Excise Report.

Table No. XXXVI, showing DISTRICT FUNDS.

YEAR.	Annual Revenue in Rs. Lakhs.	Annual Expenditure in Rupees.			Annual Expenditure in Rupees.						District Grants, in Rupees.	
		Annual Expenditure in Rupees.			Annual Expenditure in Rupees.							
		Administrative Expenditure	Interest on Debt and Accumulated Interest on Debt	Total Expenditure	Administrative Expenditure	Interest on Debt and Accumulated Interest on Debt	Total Expenditure	Administrative Expenditure	Interest on Debt and Accumulated Interest on Debt	Total Expenditure		
1885-86	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1886-87	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1887-88	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1888-89	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1889-90	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1890-91	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1891-92	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1892-93	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1893-94	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1894-95	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1895-96	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1896-97	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1897-98	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1898-99	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
1899-1900	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	Rs. 112	
Total	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	Rs. 1,120	

Note.—Taken from District Board Office.

TABLE No. XXXVII showing GOVERNMENT and AIDED SCHOOLS.

Table No. XXXVIII, showing the WORKING of the DISPEN

1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16
Name of District.	Place of Dispen-	Number of Patients													
		Male.						Female.							
		1900	1901	1902	1903	1904	1905	1906	1907	1908	1909	1910	1911	1912	1913
Panjab	Old Hospital	1,200	4,000	2,000	6,000	6,000	10,000	9,000	1,000	1,000	1,000	1,000	1,000	1,000	1,000
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Panjab	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Moga	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Dharmkot	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Dharmkot	Old Hospital	—	—	—	—	—	—	—	—	—	—	—	—	—	—

Note.—These figures are taken from Tables Nos. II, III, IV

## SAHES of FEROZEPORE DISTRICT for the years 1883 to 1888.

17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	28.	29.	30.	31.
-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----	-----

TREASSED.

Children.							Total of Patients.							
1882.	1883.	1884.	1885.	1886.	1887.	1888.	1882.	1883.	1884.	1885.	1886.	1887.	1888.	
1,000	1,018	2,119	2,109	2,209	2,144	2,204	10,129	9,281	10,799	12,118	14,281	14,209	14,009	
1,000	1,089	2,090	2,102	2,101	1,981	2,022	9,891	9,024	9,907	9,956	9,322	1,962	1,207	
-	300	70	425	400	300	425	-	4,021	3,429	7,129	8,296	4,307	4,422	
400	300	1,272	825	1,001	825	1,000	2,067	2,711	6,019	4,000	8,272	5,000	2,724	
-	-	-	-	-	-	-	450	-	-	-	-	-	5,724	
-	-	300	200	100	600	800	-	-	-	3,046	5,304	4,272	4,000	6,000

Table No. XXXVIII. showing the WORKING of the DISPENSARIES of

1.	2.	3.	4.	5.	6.	7.	8.	9.	10.	11.	12.	13.	14.		
NAME OF DISPENSARY.	CLASS OF DISPENSARY.	NUMBER OF PATIENTS TREATED.							EXPENDITURE IN RUPEES.						
		Infect. Patients.							Expenditure in Rupees.						
		15.	16.	17.	18.	19.	20.	21.	22.	23.	24.	25.	26.	27.	
Tourapur	Capital	460	340	127	610	204	511	611	2,000	5,723	8,169	4,254	2,211	5,209	4,227
Phalia	2nd Class	120	207	261	240	220	220	211	2,897	2,000	5,121	2,110	2,000	3,016	2,000
Mohindar	2nd Class	-	8	13	26	47	60	80	-	600	512	3,234	1,172	197	844
Zira	2nd Class	1	28	36	101	141	139	100	229	677	600	1,176	1,162	1,217	1,000
Moga	2nd Class	1	—	—	—	—	—	—	—	—	—	—	—	—	4,000
Dhankot	2nd Class	1	—	27	38	62	30	87	—	—	477	6,042	5,300	1,000	720

Note.—These figures are taken from Table No. II

## FEROZEPORE DISTRICT for the years 1882 to 1888—concluded.

42	43	44	45	46	47	48	49	50	51	52
DISPENSARIES.										
Names.										
1882.	1883.	1884.	1885.	1886.	1887.	1888.				
30	100	175	200	100	125	150				
21	60	90	40	60	75	75	56	This Dispensary came under control of Civil Engineers, Ferozepore, in November 1886.		
—	10	20	21	3	11	—	9	This Dispensary was opened in June.		
1	—	4	1	10	11	—	—			
—	—	—	—	—	—	—	11	This Dispensary was opened in 1888.		
—	—	—	10	6	10	—	—	—	This Dispensary was opened in September 1888.	

Table No. XXXIX, showing CIVIL and REVENUE LITIGATION.

Year	Number of Civil suits concluded				Value of Suits in Rupees			Number of Revenue cases	
	Money or movable property.	Real and Immoveable rights.	Total and Revenue movable property.		Total.	Arrears, movable.	Total.	Original	Appeals
			Total.	Revenue.					
1903-04	9,229	817	1,701	11,247	1,15,189	6,66,247	6,70,002	7,137	29
1904-05	9,229	1,108	2,517	11,257	2,46,127	6,43,217	6,49,222	9,114	38
1905-06	9,229	—	2,517	11,246	2,46,029	6,42,000	7,37,009	9,022	115
1906-07	10,072	—	2,517	12,589	2,31,209	6,35,201	6,35,201	9,007	171
1907-08	11,011	—	2,517	13,528	2,32,210	6,37,209	6,36,710	11,000	27
1908-09	10,886	—	2,412	13,301	2,31,900	6,31,000	6,30,500	—	—

Note.—These figures are taken from Statements Nos. II and III of the Civil Report and Revenue and from Statements Nos. XVII and XVIII of the Revenue Report.

Table No. XL, showing CRIMINAL TRIALS.

Period covered by Statement	1		2		3		4		5		6		7	
	Details	1898	1899	1900	1901	1898	1899	1900	1901	1898	1899	1900	1901	
Brought to trial during the year	—	3,032	7,040	8,132	9,759	6,535	6,535	6,535	6,535	9,322	9,322	9,322	9,322	
Discharged	—	4,038	4,068	3,677	3,678	4,531	4,531	4,531	4,531	4,500	4,500	4,500	4,500	
Accused	—	1,106	1,106	1,241	1,241	1,081	1,081	1,081	1,081	1,259	1,259	1,259	1,259	
Convicted	—	3,238	2,408	3,168	3,731	3,731	3,731	3,731	3,731	3,944	3,944	3,944	3,944	
Committed to prison	—	141	36	14	—	—	—	—	—	46	46	46	46	
Inquests under Chapter I	—	1,062	2,009	2,041	1,764	1,632	1,632	1,632	1,632	3,031	3,031	3,031	3,031	
True Summary	—	1,062	—	—	—	179	179	179	179	181	181	181	181	
Written sum (Report)	—	1,062	1,062	1,071	1,060	2,000	2,000	2,000	2,000	3,034	3,034	3,034	3,034	
False Summary	—	—	1	—	—	20	20	20	20	22	22	22	22	
Inquiries under Chapter IV	—	47	12	31	36	36	36	36	36	49	49	49	49	
Total cases disposed of	—	4,271	7,870	8,298	9,133	6,300	6,300	6,300	6,300	9,378	9,378	9,378	9,378	
Death	—	—	8	8	8	7	7	7	7	—	—	—	4	
Transportation for life	—	—	2	2	2	2	2	2	2	—	—	—	2	
For a term	—	—	—	1	—	—	—	—	—	—	—	—	4	
Penal servitude	—	—	2	1	12	27	27	27	27	—	—	—	2	
Prison under Sec. 10	—	3,429	1,700	2,294	2,100	6,307	6,307	6,307	6,307	3,400	3,400	3,400	3,400	
For the Ad. Express	—	304	303	303	303	260	260	260	260	647	647	647	647	
For 3 months	—	—	20	20	20	22	22	22	22	30	30	30	30	
For 6 months to 1 year	—	—	12	8	8	8	8	8	8	12	12	12	12	
For 1 to 3 years	—	—	—	—	—	—	—	—	—	—	—	—	—	
For 3 to 7 years	—	—	—	—	—	—	—	—	—	—	—	—	—	
Over 7 years	—	—	—	—	—	—	—	—	—	—	—	—	—	
Over 1,000 rupees	—	—	—	—	—	—	—	—	—	—	—	—	—	
Imprisonment under 6 months	—	309	301	304	308	301	301	301	301	630	630	630	630	
For 6 months to 1 year	—	141	122	107	918	983	983	983	983	126	126	126	126	
For over 1 year	—	—	10	8	8	8	8	8	8	29	29	29	29	
Whipping	—	—	60	23	60	60	60	60	60	60	60	60	60	
Final execution of the person	—	—	2	25	20	17	17	17	17	21	21	21	21	
Remission to keep the person	—	47	35	19	111	39	39	39	39	6	6	6	6	
Dismissal for good behaviour	—	21	21	21	226	138	138	138	138	272	272	272	272	

Note.—These figures are taken from Statements Nos. IV and V of the Criminal Reports and Notices.

Ferozepore District.]

Table No. XII, Statement showing POLICE INQUIRIES.

NAME OF OFFICER,	STATEMENT OF POLICE INQUIRIES.										STATEMENT OF POLICE INQUIRIES.											
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22
<i>Number of cases registered 1882.</i>																						
Boeing or married woman	—	10	23	37	20	28	20	13	175	110	120	101	201	201	201	110	140	90	100	210	111	83
Widow and dependents under	—	4	8	13	11	20	27	20	40	10	27	10	40	40	40	40	4	4	7	34	13	8
Total married women aged at the period	—	101	66	137	200	210	271	160	202	67	140	101	201	201	201	110	140	90	100	210	111	124
Abilities of married women	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Total income derived against property	—	262	275	370	600	600	240	600	100	100	100	100	100	100	100	100	100	100	100	200	310	100
Estimated income derived from agriculture, 1882	—	25	40	62	60	30	30	110	110	200	110	80	80	80	80	10	20	10	10	10	10	—
Other Wks.	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Total number of cases against property	—	410	429	1,001	1,220	2,071	3,010	942	620	420	600	1,000	2,000	2,000	2,000	100	400	600	600	600	600	410
Total commutable offence	—	162	643	1,570	2,001	3,407	3,200	3,172	1,477	310	3,207	3,400	3,200	3,400	3,200	700	617	602	619	1,120	1,300	642
Estimated amount of property taken	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Estimated amount of property recovered	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Offences relating to property	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Total apprehension of cases	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—

Table No. XIII, showing CONVICTIONS in GAOL.

Three sources are taken from *Elements*, Nos. 82, 911, 935, 1001, 1007, 1009, 1011, and 1017, of the Administration Test.

Table No. XLIII, showing the POPULATION of TOWNS.

1	2	3	4	5	6	7	8	9	10
Taluk.	Town.	Total population.	Muslim.	Sikhs.	Cadres.	Musalmans.	Others.	Number of incorporated houses.	Per cent per 100 occupied houses.
Ferozepore	Ferozepore	22,279	20,694	1,202	72	17,869	1,823	7,200	683
Zira	Bhawalpur	8,007	1,200	1,204	—	8,072	—	700	818
Zira	Zira	3,432	3,119	123	32	3,080	—	223	602
Moga	Moga	3,328	300	12	—	3,027	—	204	904
Moga	Moga	6,435	5,103	2,232	—	5,104	—	600	722
Moga	Moga	8,789	7,200	1,589	—	6,957	—	673	600
Muzaffarpur	Muzaffarpur	3,125	3,000	125	—	3,104	—	404	700
Muzaffarpur	Muzaffarpur	8,311	4,317	11	16	4,378	—	1,118	612

Note.—These figures are taken from 'Table No. XX' of the Census Report of 1881.

Table No. XLIV, showing BIRTHS and DEATHS for TOWNS.

Towns.	Total population by the census of		Total births registered during the year.								Total deaths registered during the year.								
	Bir.	Mil.	1882.	1883.	1884.	1885.	1886.	1887.	1888.	1889.	1890.	1891.	1892.	1893.	1894.	1895.	1896.	1897.	1898.
			Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.	Male.	Female.	
Muzaffarpur	Male.	12,913	229	504	309	801	430	791	—	711	222	529	328	580	465	—	—	—	
Muzaffarpur	Female.	8,327	212	452	413	397	403	478	—	712	225	529	272	300	273	—	—	—	
Total	—	21,240	441	956	722	800	833	870	—	1,423	457	1,052	600	880	738	—	—	—	

Note.—Taken from Table No. LVII of the Administration Report.

Table No. XLV, showing MUNICIPAL INCOME.

Municipal.	Per capita	Muslim.	Christian	Other	Muslim.	Christian	Muslim.	Christian	Total									
1885-86	—	41,744	4,107	—	5,000	2,007	—	300	—	—	372	479	73	—	—	372	479	851
1886-87	—	49,377	2,200	—	2,500	2,000	—	900	—	—	1,000	400	400	—	—	1,000	400	1,400
1887-88	—	42,018	3,100	—	2,000	2,100	—	500	—	—	700	422	222	—	—	700	422	1,122
1888-89	—	36,071	3,700	—	2,000	2,000	—	4,000	—	—	700	300	300	—	—	700	300	1,000
1889-90	—	41,000	3,000	—	2,000	2,000	—	300	—	—	300	400	400	—	—	300	400	700
1890-91	—	30,500	3,000	—	2,000	2,000	—	1,200	—	—	675	725	—	—	—	675	725	1,400
1891-92	—	35,000	3,100	—	2,000	2,000	—	1,200	—	—	675	725	—	—	—	675	725	1,400

Note.—Taken from Municipal Board Office.





UNIVERSITY

*"A book that is shut is but a block"*

CENTRAL ARCHAEOLOGICAL LIBRARY  
GOVT. OF INDIA  
Department of Archaeology  
NEW DELHI

Please help us to keep the book  
clean and moving.

---