



संस्कृति मंत्रालय
Ministry of Culture
Government of India



कला यस्मिन् प्रतिष्ठिता

इन्दिरा गाँधी राष्ट्रीय कला केन्द्र
सूत्रधार

INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS

Sutradhara

Janpath Building, (Near Western Court)

Janpath, New Delhi-110 001

Website: www.ignca.gov.in

F.No. D-11011/21/2021-ABCD

Date: - 08.11.2024

Subject: - Construction of Soak Pit and Providing/Fixing WC including Miscellaneous Civil
Electrical works at Project AATMAN Red Fort, New Delhi.

Notice Inviting Quotation

Sealed percentage rate quotations are invited on behalf of Indira Gandhi National Centre for the Arts (IGNCA), New Delhi for the work mentioned above.

Quotations duly filled signed and sealed as mentioned in Schedule of quantity (Annexure - A) shall be submitted manually in the office of the PPS/Incharge, Estate Management Unit, IGNCA, Janpath Building New Delhi-110001 by **11.11.2024 on or before 03:00 pm.**

The terms & conditions are applicable on above mentioned work as mentioned on Annexure – B.

(D R Juyal)

PPS/Incharge(EMU)

'Annexure-A'

Indira Gandhi National Centre for the Arts, New Delhi					
Estate Management Unit					
Subject:- Construction of Soak Pit and Providing/Fixing WC including Miscellaneous Civil Electrical works at Project AATMAN Red Fort, New Delhi-reg.					
S.no.	Description of Item	Qty	Unit	Rate	Amount
1	Making soak pit 2.5 m diameter 3.0 metre deep with 45 x 45 cm dry brick honey comb shaft with bricks and S.W. drain pipe 100 mm diameter, 1.8 m long complete as per standard design. With common burnt clay F.P.S. (non modular) bricks of class designation 7.5	1	each	26861.90	26861.9
2	Excavating trenches of required width for pipes, cables, etc, including excavation for sockets, depth upto 1.5 m, including getting out the excavated materials, returning the soil as required in layers not exceeding 20 cm in depth, including consolidating each deposited layers by ramming, watering etc., stacking serviceable material for measurements and disposal of unserviceable material as directed, within a lead of 50 m : Ordinary rock : Pipes, cables etc. exceeding 80 mm dia but not exceeding 300 mm dia	10	meter	998.65	9986.5
3	Providing and fixing on wall face unplasticised Rigid PVC pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. 150mm dia pipe	10	meter	377.40	3774
4	Providing and fixing vitreous china dual purpose closet suitable for use as squatting pan or European type water closet (Anglo Indian W.C pan) with seat & lid fixed with C.P. brass hinges and rubber buffers, 10 litre low level flushing cistern with fitting and brackets, 40 mm flush bend, 20 mm over flow pipe, with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required: White vitreous china dual purpose WC pan with white solid plastic seat and lid with white vitreous china flushing cistern and C.P. flush bend. Sample/make must got approved from Engineer-in-charge before execution.	2	each	11847.65	23695.3
5	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern. Sample/make must got approved from Engineer-in-charge before execution.	1	each	6258.75	6258.75
6	Providing and Fixing Hand shower (Health faucet) 8mm dia 1.2 meter long of approved make. Sample must got approved before execution. All complete as per direction of Engineer-in-charge.	3	each	1220	3660
7	Providing and fixing two way bib cock of approved quality. 15 mm nominal bore. Sample must got approved before execution. All complete as per direction of Engineer-in-charge.	2	each	1400	2800

8	Repair/Replacement work of the sensors of existing 03 nos of Automatic-doors including labour and required parts etc. All complete as per direction of Engineer-in-charge.	3	Job	8500	25500
9	Cleaning of Septic Tanks including required machinery and labours. All complete as per direction of Engineer-in-charge.	1	Job	20000	20000
10	Suply of MCCB 4 Core 100 Amp.	7	each	9000	63000
11	Supply of Following items:-				
11.1	Medium Size Battery	2	each	10	20
11.2	Small Size Battery	2	each	40	80
11.3	Electrical Tapes	10	each	10	100
11.4	Large Size Multiplug with Small Pin	10	each	550	5500
11.5	Warm white bulbs	3	each	40	120
11.6	Transparent yellow light bulb	4	each	40	160
11.7	Extension Board (Heavey Duty)	10	each	750	7500
Total					199016.45
Quoted Percentage(Above/Below/At Par)					
Total Amount(Rs.)					



 A. N. JEC

Terms & Conditions:-

1. The work shall be executed as per CPWD specification.
2. No secured advance etc. shall be paid or allowed to the contractor.
3. The rates quoted by the vendor are including of all Taxes/GST etc and nothing shall be paid on account of any taxes what so ever.
4. In the case of Extra Item(s) & substituting items being the schedule items (Delhi Schedule of Rates items), these shall be paid as per the schedule rate (approved in CPWD) (at the time of NIQ) enhancement or abutment of the NIQ.
5. The vendor will have to observe all the prevalent laws including contract labor laws, safety laws etc.
6. No escalation on account of increase of labor wages or material is admissible.
7. No reimbursement is admissible on account of levy of any tax etc.
8. If contractor or his worker damages any property of the IGNCIA, the recovery will be made from the contractor as decided by the Engineer-In- Charge, and decision of Engineer -In-Charge is final and binding.
9. All the safety rules should be followed by the Engineer/Technicians of the firm while working in IGNCIA, Institute has no liabilities in case of any accident/mishap.
10. Vendor warrants that all Products, at the time of execution of work will conform with all written specifications provided from time to time by Engineer – in – charge, (b) will be free of defects in material, workmanship, and design, and (c) will comply with all applicable laws and regulations.
11. The IGNCIA reserves the right to reject any material if not found satisfactory.
12. The payment will be made after satisfactory completion of above mentioned work.
13. Final amount will be calculated after the completion of the aforesaid work as per actual measurement.
14. Please also note that the scope of work may be reduced from the estimated quantities and no claim on this account will be entertained.
15. Please also note that if the scope of work increased from the estimated quantities then, the payment will be done as per quoted rate.
16. The Quotations duly filled as mentioned in Schedule of quantity (Annexure - A) and signed and sealed and the sealed quotation shall be submitted manually in the office address of The PPS/Incharge, Estate Management Unit, IGNCIA, New Delhi-110001

Name :.....
Designation :.....
Company with Seal :.....
Address :.....
.....