

No.7/1(1)/2017-SD/EMU**INDIRA GANDHI NATIONAL CENTRE FOR THE ARTS****SUTRADHARA DIVISION****ESTATE MANAGEMENT UNIT**

Quotation NO.008

New Delhi 15th May, 2018**SUB : Provision of Bathroom for Rehearsal Hall in Central Vista Mess Building, Janpath, New Delhi.**

Sealed percentage rate quotations are invited for erection of Bathroom for Rehearsal Hall in Central Vista mess Building, Janpath, New Delhi, from the experience vendors. The sealed quotations super scribed as quotation for the subject matter must reach to **Under Secretary (EMU)** at No.3, Dr. Rajendra Prasad Road, New Delhi-110 001 latest by **22th May, 2018 (Tuesday) till 3:00 PM.** The same will be opened on same day i.e. **on 22th May, 2018 (Monday) at 4:00 PM.**

The last date of issue of quotations form and other details are shown in the table below:

1.	2.	3.	4.	5.	6.	7.	8.	9.
Sl. No.	Name of Work	Estimated cost	Cost of Quotation	Earnest Money	Last date of sale/issue of Quotation Form	Last date of receipt of quotation	Last date of opening of Quotation	Period of completion of work
1.	Erection of Bathroom for Rehearsal Hall in Central Vista Mess Building, Janpath, New Delhi.	Rs.2,46,399/-	Free of cost	Rs. 4,900/- (Rupees Four thousand nine hundred only)	21-05-18 (Monday) Till 4:00 PM.	22-05-18 (Tuesday) 3:00 PM	22-05-18 (Tuesday) 4:00 PM	15 (fifteen) days after award of work

The participated firms must have valid VAT & Service Tax numbers, Rate and Taxes should be shown separately in the Quotation. For more details please contact Consultant (Chief Engineer), EMU, IGNC A at No.3, Dr. Rajendra Prasad Road. New Delhi.

Terms & conditions of the Quotation are attached herewith separately at **ANNEXURE-'B'**.

(SUNIL GOEL)
Under Secretary (EMU)

I/We quote my/our over-all item rates for the items as laid down in Schedule of Quantities (Schedule of Rate/Quote) as per the details given below:

(SUNIL GOEL)
Under Secretary (EMU)

No.7/1(1)/2017-SD/EMUINDIRA GANDHI NATIONAL CENTRE FOR THE ARTSSUTRADHARA DIVISIONESTATE MANAGEMENT UNITQuotation NO.008New Delhi 15th May, 2018

SUB : Provision of Bathroom for Rehearsal Hall in Central Vista Mess Building, Janpath, New Delhi.

Schedule of quantity

S. N O	DSR 2016 Code of Civil	Description	Quantity	Rates	Amount
1.	17.2.1	<p>Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid.</p>	3 Nos.		
2.	17.4.1	<p>Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and</p>			

		<p>340x410x265 mm sizes respectively</p> <p>with automatic flushing cistern with standard flush pipe and C.P. brass</p> <p>spreaders with brass unions and G.I clamps complete, including painting of</p> <p>fittings and brackets, cutting and making good the walls and floors wherever</p> <p>required :</p> <p>One urinal basin with 5 litre white P.V.C. automatic flushing cistern</p>	1 Nos.		
3.	17.7.1	<p>Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar</p> <p>taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings</p> <p>and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P.</p> <p>brass pillar taps</p>	2 Nos.		
4.	17.16A	<p>Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube upto 1 metre</p> <p>long with S.S. triangular plate to European type W.C. of quality and make as</p> <p>approved by Engineer - in - charge.</p>	3 Nos.		
5.	17.32.1	<p>Providing and fixing mirror of superior glass (of approved quality) and of</p> <p>required shape and size with plastic moulded frame of approved make and</p> <p>shade with 6 mm thick hard board backing :</p> <p>Circular shape 450 mm dia</p>	2 Nos.		

6.	17.35. 1.1	<p>Providing and fixing soil, waste and vent pipes :</p> <p>100 mm dia Sand cast iron S&S pipe as per IS: 1729</p>	20m		
7.	18.34. 1	<p>Constructing masonry Chamber 90x90x100 cm inside, in brick work in cement mortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box</p> <p>100 mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) with chained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm nominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarse sand) 12 mm thick, finished with a floating coat of neat cement complete as per standard design :</p> <p>With common burnt clay F.P.S.(non modular) bricks of class designation.</p>	1 Nos.		
8.	18.64	<p>Providing and fixing PTMT swivelling shower, 15 mm nominal bore, weighing not less than 40 gms.</p>	1 Nos.		
9.	18.65	<p>Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.</p>	2 Nos.		

10.	10.2	Structural steel work with Built- up Section (40*40*5mm) riveted, bolted or welded in built up sections for trusses including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer.	455.6 kg		
11.	10.16.1	Steel work in built up tubular(square hollow tubes vertical member of (50*50*3mm) etc. including cutting, hoisting, fixing in position and applying a priming coat of approved primer, including welding and bolted with special shaped washers etc. complete. 10ft*9piece	280 kg		
12.	12.50	Providing and fixing G.I. Sheet 0.50mm of size of total coated thickness with zinc coating 120g /sqm as per i.s. 277, in 240mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyster top coat 18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied. The sheet shall be fixed using drilling screws of size (5.5*55m) with EPDM seal, complete upto any pitch in horizontal/vertical, curved etc. surfaces, including cutting to size and shape.	146 sqm		
13.	10.31	T – Section frame for 4 door – (1.9*0.8m) 2 door – (1.9*0.9m)	30 kg		
14.	9.5.2.1	Providing and fixing panelled doors, windows, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws, with kiln wood for one door of	9.5 sqm		

		<p>(1.9*0.8m) *4doors</p> <p>(1.9*0.9m)*2 doors</p>			
15.	18.7.3	<p>Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge.</p> <p>Internal work - Exposed on wall.</p> <p>25 mm nominal outer dia Pipes</p> <p>Including tapes</p>	13.92 m		
				TOTAL	
				Extra 18% G.S.T	
				TOTAL	
				<u>Say</u>	

ANNEXURE-'B'**Terms & Conditions :-**

1. Tenderer should ensure that the tender/quotation is received before the date and time as specified.
2. The work shall be carried out as per CPWD specifications for Civil Works amended up to date also as per Manufacturers Specifications wherever required.
3. The tender/quotation can be obtained free of cost from the Office of Under Secretary (EMU), Estate Management Unit (EMU), IGNSA at No.3, Dr. Rajendra Prasad Road, New Delhi.
4. Your sealed quotation shall be addressed to Under Secretary (EMU), Estate Management Unit (EMU), IGNSA at No.3, Dr. Rajendra Prasad Road, New Delhi.
5. The Tender/Quotation shall be signed, stamped and shall be submitted in sealed envelope by the Contractor/Firm.
6. The Tenderers/Quotations shall have to submit EMD of Rs.4,900/- (Rupees Four thousand nine hundred only) by way of Demand Draft/Pay Order of Schedule Bank in favour of Indira Gandhi National Centre for the Arts, New Delhi. The EMD will be refunded to un-successful bidders within a Month of Opening of Tender/Quotation and no interest will be paid on it.
7. The work may be inspected at site before quoting the rates.
8. The rates should be given in figures and words and will be inclusive of all taxed and cartage etc. Nothing extra shall be paid on any account.
9. The rates quoted by the tenderers shall be valid for acceptance for a period of three months (90) days from the date of opening of the Tender/Quotation.
10. Any deficiency in the Tender/Quotations or in the tendering process shall be brought to the notice of the Under Secretary (EMU), IGNSA, before quoting the rates.
11. All corrections/over writing wherever filling Tenders must be initial by the Tenderer/Quotationer.
12. The conditional tender/quotation shall not be accepted.
13. The IGNSA reserve the right to reject or accept any Tender/quotation without assigning any reason. Decision of IGNSA in this regard will be final and binding to the contractor/firm.
14. The material to be used in the work shall be got approved from Head Draftsman (EMU), IGNSA, New Delhi.

15. The Contractor shall acquainted himself with the site conditions and make his own arrangements for storage of materials at site. No materials and men powers shall be supplied by the IGNCA.
16. Prior permission has to be taken by the Contractor in advance if the work is to be carried out before or late office hours ie. from 9.00 a.m. to 5.40 p.m. or Saturdays, Sundays and Govt. Holidays. If the permission is not granted by the Competent Authority, IGNCA, the work shall not be carried out.
17. During the time of execution of work the Contractor will be fully responsible for any injury, incidence or accident to any person(s) employed by them, to the residents and for any damage to any structure or any part of the property which may arise due to operation/negligence of the Contractor of its workers.
18. If any extra item is required to be executed during the execution of work a prior approval for the same has to be taken by the Contractor from the Competent Authority, IGNCA. If the work of extra items shall be carried out without obtaining any approval of Competent Authority, the same shall not be paid to the Contractor/firm.
19. If the contractor fails to complete the work within the stipulated time frame a penalty for non-completion of the work @ Rs. 100/- (Rupees one hundred only) for each day of delay including holidays subject to maximum of 10% (ten per cent) of the cost of work. The decision of IGNCA in this regards, shall final and binding to the contractor.
20. Security Deposit @ 5% (five percent) of the Gross amount of the Contractor's Bill shall be deducted which will be refunded after six months from the date of successfully completion of work.
21. TDS: Income Tax @ 2% and water/electrical charges @ 1% shall be deducted from the gross amount of Contractor bill.
22. After completion of work the Contractor has to clear the site/used areas in all respect at his own risk/cost to entire satisfaction of Head Draftsman (EMU), failing which a suitable amount from the Contractor's Bill will be deducted.
23. After successfully completion of work the Contractor shall submit the bill in duplicate, giving description of items of work done strictly as per Bill/Schedule of Quantities. Full and final payment shall be made on completion of work satisfactorily.

(SUNIL GOEL)
Under Secretary (EMU)